

SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94-F3000-05-BT	COOK	102	3
STA.	TO STA.		
PROJECT NO. TE-D001 (610)			
CENTENNIAL TRAIL			
CONTRACT NO. 83859			

	CODE NO	PAY ITEM	UNIT	TOTAL QUANTITY Y047	FOREST PRESERVE DISTRICT OF COOK COUNTY Y047	FOREST PRESERVE DISTRICT OF DUPAGE COUNTY Y047
	Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	100%	0%
	20101200	TREE ROOT PRUNING	EACH	50	40	10
	M2010110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	500	400	100
	M2010210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	1,000	800	200
	M2020010	EARTH EXCAVATION	CU M	10,260	10,260	0
	M2020020	ROCK EXCAVATION	CU M	14	14	0
	M2021200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU M	23,889	19,655	4,234
	M2040800	FURNISHED EXCAVATION	CU M	2,087	0	2,087
	M2070420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU M	3,983	3,277	706
	M2080150	TRENCH BACKFILL	CU M	55	55	0
	M2101000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ M	51,628	37,588	14,040
	M2113150	TOPSOIL FURNISH AND PLACE, 150 MM	SQ M	53,090	40,540	12,550
*	M2500115	SEEDING, CLASS 1B	HA	1.74	1.26	0.48
*	M2500300	SEEDING, CLASS 3	HA	0.05	0.05	0.00
*	M2500312	SEEDING, CLASS 4A	HA	3.58	2.79	0.79
*	M2500400	NITROGEN FERTILIZER NUTRIENT	KG	485	359	126
*	M2500500	PHOSPHORUS FERTILIZER NUTRIENT	KG	485	359	126
*	M2500600	POTASSIUM FERTILIZER NUTRIENT	KG	485	359	126
	M2510630	EROSION CONTROL BLANKET	SQ M	53,090	40,540	12,550
	M2520200	SUPPLEMENTAL WATERING	UNIT	100	80	20
	28000300	TEMPORARY DITCH CHECKS	EACH	44	44	0
	M2800400	PERIMETER EROSION BARRIER	METER	14,190	11,040	3,150
	M2810103	RIPRAP, CLASS A2	SQ M	128	128	0
	M2820200	FILTER FABRIC	SQ M	128	128	0
	M3511100	AGGREGATE BASE COURSE, TYPE B 100 MM	SQ M	3,360	730	2,630
	M3511150	AGGREGATE BASE COURSE, TYPE B 150 MM	SQ M	45,930	34,230	11,700
	M4060100	BITUMINOUS MATERIALS (PRIME COAT)	LITER	100,200	70,240	29,960
	M4205200	PROTECTIVE COAT	SQ M	41	35	6
	M4240150	PORTLAND CEMENT CONCRETE SIDEWALK 150MM	SQ M	41	35	6
	M4248000	DETECTABLE WARNINGS	SQ M	14	12	2
	M4402000	PAVEMENT REMOVAL	SQ M	29	29	0
	M4402045	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	METER	14	14	0
	M4402050	SIDEWALK REMOVAL	SQ M	10	10	0
	M4812000	AGGREGATE SHOULDERS, TYPE B	M TON	668	332	336
	60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	1	1	0
	60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	1	1	0
*	M6300100	STEEL PLATE BEAM GUARD RAIL, TYPE A	METER	64	64	0
*	63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	3	3	0
	M6320030	GUARDRAIL REMOVAL	METER	27	27	0

* INDICATES SPECIALTY ITEMS

REVISIONS		
NO.	NAME	DATE

URS 100 S. WACKER DR., SUITE 500 TEL (312)-939-1000
CHICAGO, IL 60606 FAX (312)-939-4198

FOREST PRESERVE DISTRICT OF COOK COUNTY
CENTENNIAL TRAIL
SUMMARY OF QUANTITIES

DATE: 10/20/06 DRAWN BY:
DESIGNED BY: MIA, DIH CHECKED BY: DDL