	F.A.P. RTE.	F.A.P. SECTION				COUNT	ГҮ	TOTAL SHEETS	SHEET NO.
	331	3-2,	BX-1,	4-2		SALI	NE	233	4
	STA. TO STA.								
	FED. ROAD DIST. NO.			ILLINOIS		FED.	AID	PROJECT	

COMMITMENTS

AS A RESULT OF THE PROPOSED PROJECT, WILMOUTH STREET WILL BE ELIMINATED IN THE AREA OF THE OWNERS FIELD ACCESS. THE DEPARTMENT WILL PROVIDE A NEW FIELD ACCESS POINT TO THE OWNERS REMAINING LAND. ACCESS POINT TO BE LOCATED OFF OF NEWLY CONSTRUCTED WILMOUTH STREET CONNECTOR.

THE CONTRACTOR WILL CONSTRUCT ALL ENTRANCES ONE HALF AT A TIME IN ORDER TO PRESERVE ACCESS TO THE BAR-B-Q BARN PROPERTY, PARCEL 149. THIS WILL APPLY TO BOTH ENTRANCES ALONG ILL 34.

A 20' X 100' AREA SOUTH OF THE ALLEY SOUTH OF THE BAR-B-Q BARN AND WEST OF THE ALLEY EAST OF THE BAR-B-O BARN WILL BE USED FOR PARKING. THE CONTRACTOR SHALL NOT USE THIS AREA FOR CONSTRUCTION OPERATIONS. IF ANY CHANGE IN THIS PARKING CONFIGURATION IS REQUIRED DUE TO CONSTRUCTION OPERATIONS, CONSTRUCTION PERSONNEL SHALL NOTIFY THE MANAGER OF THE BAR-B-Q BARN AT 618-252-6190 OR RANDY JONES, OWNER, AT 618-994-2266.

ENVIRONMENTAL COMMITMENTS

SPECIAL WASTE:

IN CONSULTATION WITH THE CHIEF COUNSEL'S OFFICE, IF RIGHT-OF-WAY ACQUISITION INCLUDES A PARCEL WITH AN UNDERGROUND STORAGE TANK(S) AND LAND ACQUISITION PROCEDURES ARE FOLLOWED AND IF CONSTRUCTION EXCAVATION AND UTILITY RELOCATION DO NOT EXCEED THE MAXIMUM TESTING DEPTH AT EACH SITE AND DOES NOT EXCEED THE FOLLOWING EXCAVATION LIMITATIONS, THEN NO ADDITIONAL PRELIMINARY TESTING FOR THE PROJECT IS NECESSARY.

LANE ERECTORS ADDRESS: 622 N. GRANGER ISGS BORING: 710B-16A EXCAVATION DEPTH: 3 FEET

LANE ERECTORS ADDRESS: 622 N. GRANGER ISGS BORING: 710B-16C EXCAVATION DEPTH: 6 FEET

COFFEE ENTERPRISES ADDRESS: 621 N. JACKSON ISGS BORING: 710B-R EXCAVATION DEPTH: NO GRADING

VACANT LOT ADDRESS: 629 N. MAIN ISGS BORING: 710B-18A EXCAVATION DEPTH: 6 FEET

ATMOS ENERGY ADDRESS: 611 N. MAIN ISGS BORING: 710B-19A EXCAVATION DEPTH: 6 FEET

H & H MOTORSPORTS ADDRESS: 620 N. MAIN ISGS BORING: 710B-20A EXCAVATION DEPTH: 3 FEET

H & H MOTORSPORTS ADDRESS: 620 N. MAIN ISGS BORING: 710B-10B EXCAVATION DEPTH: 3 FEET

PLEASE NOTE: IF ANY CHANGES ARE TO BE MADE TO THE CONSTRUCTION LIMITS OR EXCAVATION DEPTHS BEFORE OR DURING THE CONSTRUCTION PHASE, PLEASE CONTACT THE D-9 ENVIRONMENTAL COORDINATOR AT 618-351-5284 TO REPORT THE CHANGE SO THAT POSSIBLE INVOLVEMENT WITH THESE LISTED SITES CAN BE INVESTIGATED.

ACCORDING TO THE PROPOSED PLANS AND CROSS SECTIONS FOR THIS PROJECT, EXCAVATION EXCEEDS THE RECOMMENDED DEPTHS AT ALL LOCATIONS LISTED ABOVE. HANDLING AND DISPOSAL OF THIS MATERIAL SHALL BE CONDUCTED IN ACCORDANCE WITH THE SPECIAL PROVISIONS FOR THIS PROJECT.

AS DETAILED IN THE WETLAND TECHNICAL REPORT, FOUR WETLANDS HAVE BEEN IDENTIFIED IN THIS PROJECT CORRIDOR. THE AS DETAILED IN THE WEILAND JECHNICAL REPORT, FOOR WEILANDS HAVE BEEN IDENTIFIED IN THIS PROJECT CORRIDOR. THE FIRST SITE IS A MARSH LOCATED 85 FEET NORTHWEST OF US ROUTE 45 NAD 670 FEET SOUTH OF MIDDLE FORK SALINE RIVER. THE THIRD SITE IS A MARSH LOCATED 3530 FEET WEST OF U.S. ROUTE 45 AND 670 FEET SOUTH OF MIDDLE FORK SALINE RIVER. THE THIRD SITE IS A MARSH LOCATED 40 FEET NORTHWEST OF U.S. ROUTE 45 AND 925 FEET EAST OF THE INTERSECTION THE WETLAND IMPACT EVALUATION, THIS PROJECT WILL NOT IMPACT ANY OF THE SITES WITHIN THE PROJECT CORRIDOR. THEREFORE, NO COMMITMENTS ARE REQUIRED WITH RESPECT TO WETLANDS.