



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

January 10, 2024

SUBJECT: Route FAU 1321 (Irving Park Road)  
Section 10-00055-02-WR (Streamwood)  
Cook County  
Contract No. 61K06  
Item 151  
January 19, 2024 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised Page 2 of the Index to the Special Provisions.**
- 2. Revised Pages 6 and 87 of the Special Provisions.**
- 3. Added Pages 87A – 87C and 100A – 100B to the Special Provisions.**
- 4. Revised Sheets 2, 8 - 10, 12, 26 – 36 of the Plans.**
- 5. Revised the Schedule of Prices.**

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.  
Bureau Chief, Design and Environment

AUXILIARY VALVE BOX EXTENSION .....	41
FIRE HYDRANTS TO BE REMOVED .....	41
FIRE HYDRANTS TO BE ADJUSTED .....	42
TRENCH BACKFILL, WATER MAIN .....	42
GENERAL REQUIREMENTS FOR WEED CONTROL SPRAYING .....	43
WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE .....	44
PROTECTION OF EXISTING TREES.....	45
STUMP REMOVAL .....	48
PLANTING WOODY PLANTS .....	49
PLANTING PERENNIAL PLANTS.....	56
MULCH PLACEMENT FOR EXISTING WOODY PLANTS.....	59
SUPPLEMENTAL WATERING .....	60
FAILURE TO COMPLETE PLANT CARE AND ESTABLISHMENT WORK ON TIME .....	61
GENERAL ELECTRICAL REQUIREMENTS.....	62
BREAKWAY DEVICE .....	77
ELECTRIC SERVICE INSTALLATION .....	77
ELECTRIC UTILITY SERVICE CONNECTION (COMED).....	77
LIGHT POLE, SPECIAL .....	78
LUMINAIRE, LED, SPECIAL .....	79
UNDERGROUND RACEWAYS.....	83
UNIT DUCT .....	84
WIRE AND CABLE .....	85
AVAILABLE REPORTS (D1 LR).....	87
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (PROJECT SPECIFIC) .....	87
IDOT TRAINING PROGRAM ON-THE-JOB TRAINING SPECIAL PROVISION (TPG).....	88
INSURANCE (LR 107-04).....	90
LOCAL QUALITY ASSURANCE/QUALITY MANAGEMENT QC/QA (LR 1030-2).....	91
STORM WATER POLLUTION PREVENTION PLAN.....	93
LPC 663.....	100A

The above represents the best information available to the Department and is included for the convenience of the bidder. The days required for conflict resolution should be taken into account in the bid as this information has also been factored into the timeline identified for the project when setting the completion date. The applicable portions of the Standard Specifications for Road and Bridge Construction shall apply.

Estimated duration of time provided in the action column for the first conflicts identified will begin on the date of the executed contract regardless of the status of the utility relocations. The responsible agencies will be working toward resolving subsequent conflicts in conjunction with contractor activities in the number of days noted.

The estimated relocation dates must be part of the progress schedule submitted by the contractor. A utility kickoff meeting will be scheduled between the Department, the Department's contractor and the utility companies. The Department's contractor is responsible for contacting J.U.L.I.E. prior to any and all excavation work.

### **TRAFFIC CONTROL PLAN (D1)**

Effective: September 30, 1985

Revised: January 1, 2007

Traffic Control shall be according to the applicable sections of the Standard Specifications, the Supplemental Specifications, the "Illinois Manual on Uniform Traffic Control Devices for Streets and Highways", any special details and Highway Standards contained in the plans, and the Special Provisions contained herein.

Special attention is called to Article 107.09 of the Standard Specifications and the following Highway Standards, Details, Quality Standard for Work Zone Traffic Control Devices, Recurring Special Provisions and Special Provisions contained herein, relating to traffic control.

The Contractor shall contact the District One Bureau of Traffic at least 72 hours in advance of beginning work.

### **Standards**

701006-05, 701011-04, 701101-05, 701106-02, 701301-04, 701311-03, 701427-05, 701501-06, 701502-09, 701602-10, 701801-06, 701901-09

### **Details**

Traffic Control and Protection for Side Roads, Intersections and Driveways (TC-10)  
Raised Reflective Pavement Markers (Snow Plow Resistant) (TC-11)  
District One Typical Pavement Markings (TC-13)  
Traffic Control and Protection at Turn Bays (To Remain Open to Traffic) (TC-14)  
Pavement Marking Letters and Symbols for Traffic Staging (TC-16)  
Arterial Road Information Sign (TC-22)  
Driveway Entrance Signing (TC-26)

### **Special Provisions**

Maintenance of Roadways (D1)  
Public Convenience and Safety (D1)  
Traffic Control and Protection (Arterials) (D1)  
Keeping Arterial Roadways Open to Traffic (D1)  
Temporary Information Signing (D1)  
Work Zone Traffic Control Devices (BDE)  
Vehicle and Equipment Warning Lights (BDE)  
Speed Display Trailer (D1)(BDE)  
Raised Reflective Pavement Marker, Reflector Removal  
Raised Reflective Pavement Marker, Reflector Replacement

**AVAILABLE REPORTS (D1 LR)**

Effective: July 1, 2021

No project specific reports were prepared.

When applicable, the following checked reports and record information is available for Bidders' reference upon request:

- Record structural plans
- Preliminary Site Investigation (PSI) (IDOT ROW)
- Preliminary Site Investigation (PSI) (Local ROW)
- Preliminary Environmental Site Assessment (PESA) (IDOT ROW)
- Preliminary Environmental Site Assessment (PESA) (Local ROW)
- Soils/Geotechnical Report
- Boring Logs
- Pavement Cores
- Location Drainage Study (LDS)
- Hydraulic Report
- Noise Analysis

Those seeking these reports should request access from:

HR Green, Inc./Jack Melhuish/Project Manager  
1391 Corporate Drive, McHenry, IL 60050  
jmelhuish@hrgreen.com  
815.759.8342

**REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (PROJECT SPECIFIC)**

**Description.** This work shall consist of the removal and disposal of regulated substances according to Section 669 of the Standard Specifications as revised below.

**Contract Specific Sites.** The excavated soil and groundwater within the areas listed below shall be managed as either "uncontaminated soil", hazardous waste, special waste or non-special waste. For stationing, the lateral distance is measured from centerline and the farthest distance is the offset distance or construction limit, whichever is less.

**Soil Disposal Analysis.** When the waste material requires sampling for landfill disposal acceptance, the Contractor shall secure a written list of the specific analytical parameters and analytical methods required by the landfill. The Contractor shall collect and analyze the required number of samples for the parameters required by the landfill using the appropriate analytical procedures. A copy of the required parameters and analytical methods (from landfill email or on landfill letterhead) shall be provided as Attachment 4A of the BDE 2733 (Regulated Substances Final Construction Report). The price shall include all sampling materials and effort necessary for collection and management of the samples, including transportation of samples from

the job site to the laboratory. The Contractor shall be responsible for determining the specific disposal facilities to be utilized; and collect and analyze any samples required for disposal facility acceptance using a NELAP certified analytical laboratory registered with the State of Illinois.

Site 2359V2-10: Residences, 1699-1711 E. Chicago Street, Elgin, and 31W003 E. Chicago Street, Unincorporated Cook County

- Station 105+50 to Station 109+70 (CL Irving Park Rd.), 0 to 50 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminant of concern sampling parameter: Manganese.
- Station 109+70 to Station 110+25 (CL Irving Park Rd.), 0 to 50 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(2). Contaminant of concern sampling parameter: Manganese.

Site 2359V2-12: Residence, 30W790 Chicago Street, Unincorporated Cook County

- Station 105+50 to Station 109+00 (CL Irving Park Rd.), 0 to 50 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(2). Contaminant of concern sampling parameter: Manganese.
- Station 109+00 to Station 111+65 (CL Irving Park Rd.), 0 to 50 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminant of concern sampling parameter: Manganese.

Site 2359V2-13: Residence, 30W793 Chicago Street, Unincorporated Cook County

- Station 110+25 to Station 112+70 (CL Irving Park Rd.), 0 to 70 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(2). Contaminant of concern sampling parameter: Manganese.

Site 2359V2-17: Residences, 108-301 English Oak Lane, Streamwood, Cook County

- Station 111+65 to Station 114+60 (CL Irving Park Rd.), 0 to 50 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminants of concern sampling parameters: Arsenic, and Manganese.
- Station 114+60 to Station 120+65 (CL Irving Park Rd.), 0 to 50 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(2). Contaminants of concern sampling parameters: Arsenic, and Manganese.
- Station 120+65 to Station 123+50 (CL Irving Park Rd.), 0 to 50 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Contaminants of concern sampling parameters: Arsenic, and Manganese.
- Station 123+50 to Station 126+45 (CL Irving Park Rd.), 0 to 50 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(2). Contaminant of concern sampling parameter: Manganese.
- Station 126+45 to Station 129+60 (CL Irving Park Rd.), 0 to 80 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Contaminants of concern sampling parameter: Manganese.
- Station 129+60 to Station 132+65 (CL Irving Park Rd.), 0 to 50 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminants of concern sampling parameters: Arsenic, and Manganese.
- Station 132+65 to Station 134+65 (CL Irving Park Rd.), 0 to 50 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(2). Contaminant of concern sampling parameter: Manganese.

Site 2359V2-18: Residences, 30 W 461 W. Irving Park Road, 30 W 400 block of W. Irving Park Road, 10 Sherwood Road, and 10 Gromer Road, Elgin and Unincorporated Cook County

- Station 112+70 to Station 115+45 (CL Irving Park Rd.), 0 to 70 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(2). Contaminant of concern sampling parameter: Arsenic.

- Station 115+45 to Station 118+40 (CL Irving Park Rd.), 0 to 50 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminant of concern sampling parameter: Manganese.
- Station 118+40 to Station 124+50 (CL Irving Park Rd.), 0 to 50 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(2). Contaminants of concern sampling parameters: Lead, and Manganese.
- Station 124+50 to Station 127+45 (CL Irving Park Rd.), 0 to 50 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Contaminants of concern sampling parameters: Benzo(a)pyrene, Arsenic, Lead, and Manganese.
- Station 127+45 to Station 128+15 (CL Irving Park Rd.), 0 to 50 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminants of concern sampling parameters: Arsenic, and Manganese.

Site 2359V2-19: Residences, 7-33 Gromer Road and 660-665 Castlewood Drive, Elgin and Streamwood, Cook County

- Station 128+15 to Station 130+40 (CL Irving Park Rd.), 0 to 50 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminants of concern sampling parameters: Arsenic, and Manganese.
- Station 130+40 to Station 141+55 (CL Irving Park Rd.), 0 to 80 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(2). Contaminants of concern sampling parameters: Arsenic, and Manganese.

Site 2359V2-20: Sunny Hill Park, 1440 W. Irving Park Road, Streamwood, Cook County

- Station 134+65 to Station 135+55 (CL Irving Park Rd.), 0 to 70 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(2). Contaminant of concern sampling parameter: Manganese.
- Station 135+55 to Station 138+30 (CL Irving Park Rd.), 0 to 50 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminant of concern sampling parameter: Manganese.
- Station 138+30 to Station 141+10 (CL Irving Park Rd.), 0 to 50 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(2). Contaminant of concern sampling parameter: Manganese.

Site 2359V2-21: Residences, 1100 block of Irving Park Road and 3 Wildflower Way, Streamwood, Cook County

- Station 141+10 to Station 149+20 (CL Irving Park Rd.), 0 to 50 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(2). Contaminants of concern sampling parameters: Lead, and Manganese.
- Station 149+20 to Station 152+20 (CL Irving Park Rd.), 0 to 50 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Contaminants of concern sampling parameters: Arsenic, Lead, and Manganese.
- Station 152+20 to Station 156+15 (CL Irving Park Rd.), 0 to 80 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(2). Contaminants of concern sampling parameters: Lead, and Manganese.

Site 2359V2-22: John R. White Tree and Nature Conservancy Area, 30W300 block of Irving Park Road, Streamwood, Cook County

- Station 141+55 to Station 142+10 (CL Irving Park Rd.), 0 to 50 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(2). Contaminant of concern sampling parameter: Manganese.
- Station 142+10 to Station 144+60 (CL Irving Park Rd.), 0 to 50 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminant of concern sampling parameter: Manganese.

- Station 144+60 to Station 147+10 (CL Irving Park Rd.), 0 to 50 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Contaminants of concern sampling parameters: Arsenic, and Manganese.
- Station 147+10 to Station 149+25 (CL Irving Park Rd.), 0 to 80 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(2). Contaminants of concern sampling parameters: Arsenic, and Manganese.

Site 2359V2-23: Residences and Vacant Land, 30W121-30W263 Irving Park Road, 30W100 block of Irving Park Road and 701 Blue Ridge Drive, Streamwood and Unincorporated Cook County

- Station 149+25 to Station 155+90 (CL Irving Park Rd.), 0 to 50 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(2). Contaminant of concern sampling parameter: Manganese.
- Station 155+90 to Station 162+75 (CL Irving Park Rd.), 0 to 50 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminant of concern sampling parameter: Manganese.

Site 2359V2-24: Vacant Land and Pond, 1100 block of W. Irving Park Road, Streamwood, Cook County

- Station 156+15 to Station 159+45 (CL Irving Park Rd.), 0 to 50 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(2). Contaminant of concern sampling parameter: Manganese.
- Station 159+45 to Station 162+75 (CL Irving Park Rd.), 0 to 50 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Contaminants of concern sampling parameters: Benzo(a)pyrene, Pentachlorophenol, and Manganese.

**Work Zones**

Three distinct OSHA HAZWOPER work zones (exclusion, decontamination, and support) shall apply to projects adjacent to or within sites with documented leaking underground storage tank (LUST) incidents, or sites under management in accordance with the requirements of the Site Remediation Program (SRP), Resource Conservation and Recovery Act (RCRA), or Comprehensive Environmental Response, Compensation and Liability Act (CERCLA), or as deemed necessary. For this project, the work zones apply for the following ISGS PESA Sites: **None**



# Illinois Environmental Protection Agency

1021 North Grand Avenue East • P.O. Box 19276 • Springfield • Illinois • 62794-9276 • (217) 782-3397

## Uncontaminated Soil Certification by Licensed Professional Engineer or Licensed Professional Geologist for Use of Uncontaminated Soil as Fill in a CCDD or Uncontaminated Soil Fill Operation LPC-663

Revised in accordance with 35 Ill. Adm. Code 1100, as amended by PCB R2012-009 (eff. Aug. 27, 2012)

This certification form is to be used by professional engineers and professional geologists to certify, pursuant to 35 Ill. Adm. Code 1100.205(a)(1)(B), that soil (i) is uncontaminated soil and (ii) is within a pH range of 6.26 to 9.0. If you have questions about this form, please telephone the Bureau of Land Permit Section at 217/524-3300.

This form may be completed online, saved locally, printed and signed, and submitted to prospective clean construction or demolition debris (CCDD) fill operations or uncontaminated soil fill operations.

### I. Source Location Information

(Describe the location of the source of the uncontaminated soil)

Project Name: FAU 1321 (IL ROUTE 19 / IRVING PARK RD.) Office Phone Number, if available: \_\_\_\_\_

Physical Site Location (address, including number and street):

30W790 Chicago Street [southeast corner of Chicago Street (Irving Park Road / IL 19) and Schaumburg Road]

City: Unincorporated State: IL Zip Code: 60120

County: Cook Township: Hanover

Lat/Long of approximate center of site in decimal degrees (DD.ddddd) to five decimal places (e.g., 40.67890, -90.12345):

Latitude: 42.02751 Longitude: -88.22293  
(Decimal Degrees) (-Decimal Degrees)

Identify how the lat/long data were determined:

GPS  Map Interpolation  Photo Interpolation  Survey  Other

IEPA Site Number(s), if assigned: BOL: \_\_\_\_\_ BOW: \_\_\_\_\_ BOA: \_\_\_\_\_

Approximate Start Date (mm/dd/yyyy): N/A Approximate End Date (mm/dd/yyyy): N/A

Estimated Volume of debris (cu. Yd.): 157

### II. Owner/Operator Information for Source Site

Site Owner

Name: Illinois Department of Transportation

Street Address: 201 West Center Court

PO Box: \_\_\_\_\_

City: Schaumburg State: IL

Zip Code: 60196-1096 Phone: 847-705-4122

Contact: Irma Romiti-Johnson

Email, if available: Irma.Romiti-Johnson@illinois.gov

Site Operator

Name: Illinois Department of Transportation

Street Address: 201 West Center Court

PO Box: \_\_\_\_\_

City: Schaumburg State: IL

Zip Code: 60196-1096 Phone: 847-705-4122

Contact: Irma Romiti-Johnson

Email, if available: Irma.Romiti-Johnson@illinois.gov

This Agency is authorized to require this information under Section 4 and Title X of the Environmental Protection Act (415 ILCS 5/4, 5/39). Failure to disclose this information may result in: a civil penalty of not to exceed \$50,000 for the violation and an additional civil penalty of not to exceed \$10,000 for each day during which the violation continues (415 ILCS 5/42). This form has been approved by the Forms Management Center.

Uncontaminated Soil Certification

**III. Basis for Certification and Attachments**

For each item listed below, reference the attachments to this form that provide the required information.

- a. A Description of the soil sample points and how they were determined to be sufficient in number and appropriately located 35 Ill. Adm. Code 1100.610(a)]:

LOCATION 2359V2-12-B01 WAS SAMPLED ADJACENT TO SITE 2359V2-12. SEE TABLE 3b AND FIGURE 2 OF THE FINAL PRELIMINARY SITE INVESTIGATION REPORT.

- b. Analytical soil testing results to show that soil chemical constituents comply with the maximum allowable concentrations established pursuant to 35 Ill. Adm. Code Part 1100, Subpart F and that the soil pH is within the range of 6.25 to 9.0, including the documentation of chain of custody control, a copy of the lab analysis; the accreditation status of the laboratory performing the analysis; and certification by an authorized agent of the laboratory that the analysis has been performed in accordance with the Agency's rules for the accreditation of environmental and the scope of the accreditation [35 Ill. Adm. Code 1100.201 (g), 1100.205(a), 1100.610]:

EUROFINS ANALYTICAL REPORT - EUROFINS JOB ID NUMBER: 500-239905-1.

**IV. Certification Statement, Signature and Seal of Licensed Professional Engineer or Licensed Professional Geologist**

I, Savo Radulovic, L.P.G (name of licensed professional engineer or geologist) certify under penalty of law that the information submitted, including but not limited to, all attachments and other information, is to the best of my knowledge and belief, true, accurate and complete. In accordance with the Environmental Protection Act [415 ILCS 5/22.51 or 22.51a] and 35 Ill. Adm. Code 1100.205(a), I certify that the soil from this site is uncontaminated soil. I also certify that the soil pH is within the range of 6.25 to 9.0. In addition, I certify that the soil has not been removed from the site as part of a cleanup or removal of contaminants. All necessary documentation is attached.

***Any person who knowingly makes a false, fictitious, or fraudulent material statement, orally or in writing, to the Illinois EPA commits a Class 4 felony. A second or subsequent offense after conviction is a Class 3 felony. (415 ILCS 5/44(h))***

Company Name: Andrews Engineering, Inc.  
Street Address: 420 Eisenhower Lane North  
City: Lombard State: IL Zip Code: 60148  
Phone: 630-953-3332

Savo Radulovic  
Printed Name:



Licensed Professional Engineer or  
Licensed Professional Geologist Signature:

Nov 27, 2023  
Date:

