

COUNTY SHEETS NO. SECTION COOK 631 286 STA. FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT

CONTRACT NO. 62111

+ (2425 & 2626) R-2

- I, DURING CONSTRUCTION STAGES LAND II, CERTAIN SIDEWALK AND PEDESTRIAN CROSSINGS ARE CLOSED. THE CONTRACTOR SHALL BAG THE APPROPRIATE PEDESTRIAN SIGNALS WHEN THESE SITUATIONS OCCUR.
- 2. DURING CONSTRUCTION STAGE ITHE WESTBOUND BERNICE ROAD LEFT TURN MOVEMENT IS NOT ALLOWED AND THE SIGNAL SECTIONS PROVIDING THIS MOVEMENT SHALL BE BAGGED AND THE CONTROLLER SEQUENCE REVISED.
- 3. QUANTITIES FOR REMOVAL OF THE EXISTING SIGNAL HEADS, BACKPLATES AND PEDESTRIAN SIGNAL HEADS AND REPLACEMENT WITH NEW L.E.D. SIGNALS AND BACKPLATES HAVE BEEN INCLUDED IN THIS CONTRACT, CABLE AND EXISTING TRAFFIC SIGNAL PLANS SHALL BE PROVIDED AT THE PRE-CONSTRUCTION MEETING.

## REMOVAL NOTES:

THE FOLLOWING ITEMS SHALL BE REMOVED BY THE CONTRACTOR AND SHALL BE DISPOSED OF BY THEM OUTSIDE THE RICHT-OF-WAY AT THEIR EXPENSE. THE SALVAGE VALUE OF THE REMOVED EQUIPMENT SHALL BE REFLECTED IN THE CONTRACT BID PRICE.

TRAFFIC SIGNAL BACKPLATE SIGNAL HEAD, I-FACE, 3-SECTION SIGNAL HEAD, I-FACE, 4-SECTION SIGNAL HEAD, I-FACE, 5-SECTION PEDESTRIAN SIGNAL HEAD, I-FACE

ILLINOIS DEPARTMENT OF TRANSPORTATION F.A.I. ROUTE 80/94 (KINGERY EXPRESSWAY) EB & WB INSIDE LANES (MAINLINE) CONSTRUCTION

COOK COUNTY TEMP TRAFFIC SIGNAL INSTALLATION BURNHAM AVENUE AT BERNICE ROAD STAGE 1 NAME DRAWN BY: JFS CHECKED BY: RF

SCALE: DATE: 9/13/05 **TENG** 

TENG & ASSOCIATES, INC. ENGINEERS/ARCHITECTS/PLANNERS CHICAGO, ILLINOIS

ENERGY SUPPLY CONTACT:

 $\boxtimes$ 

 $\Box$ 

---

CT

UD

\_\_\_\_ 

 $\mathbb{H}$ 

CONFIRMATION BEACON

G.S. CONDUIT IN GROUND

HEAVY DUTY HANDHOLE

COMMON TRENCH

UNIT DUCT

HANDHOLE

PHONE: COMPANY:

ILLINOIS DEPARTMENT OF TRANSPORTATION 201 WEST CENTER COURT SCHAUMBURG, ILLINOIS 60196-1096

TOTAL =

I.D.O.T.