

SUMMARY OF QUANTITIES

CONTRACT NO. 64577		• 177-13, 4, 4-1-1		
F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	•	STEPHENSON	290	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CODE NO.	Item	Unit	← 80% FED 20% ST →			CODE NO.	Item	Unit	80% FED 20% ST			
				1000-2A	1000-2A					1000-2A	1000-2A	
			TOTAL QUANTITY	ROADWAY	ROADWAY				TOTAL QUANTITY	ROADWAY	ROADWAY	
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	2762.5	0	2762.5	* 78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	7435	7435		
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	3	0	3	* 78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	146	146		
* 63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	2	0	2	* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	89127	89127		
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	8	0	8	* 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	1576	1576		
* 63100169	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)	EACH	9	0	9	* 78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	678	678		
63200310	GUARDRAIL REMOVAL	FOOT	3025	3025		* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	851	851		
63500105	DELINEATORS	EACH	350	350		* 78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	94	94		
66500105	WOVEN WIRE FENCE, 4 FT	FOOT	317	317		* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1430	1430		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	16	16		* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	25	25		
67000600	ENGINEER'S FIELD LABORATORY	CAL MO	16	16		78100300	REPLACEMENT REFLECTOR	EACH	84	84		
67100100	MOBILIZATION	L SUM	1	1		78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	144	144		
70100315	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	EACH	1	1		78200410	GUARDRAIL MARKERS, TYPE A	EACH	53	53		
70100410	TRAFFIC CONTROL AND PROTECTION, STANDARD 701416	EACH	2	2		78200510	BARRIER WALL MARKERS, TYPE A	EACH	9	9		
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	7	7		78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	14	14		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		78300100	PAVEMENT MARKING REMOVAL	SQ FT	20213	20213		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		78300200	REMOVE RAISED REFLECTIVE PAVEMENT MARKERS	EACH	380	380		
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1		X4074170	POLYMERIZED BITUMINOUS CONCRETE PAVEMENT, (FULL DEPTH), SUPERPAVE, 14"	SQ YD	90165	90165		
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1		A2C10863	TREE, JUGLANS CINEREA (BUTTERNUT HICKORY), 3-GALLON	EACH	100	100		
70100805	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	L SUM	1	1		542A0217	PIPE CULVERTS, CLASS A, TYPE 1 12"	FOOT	74	74		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	100	100		542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	281	281		
70300100	SHORT TERM PAVEMENT MARKING	FOOT	59957	59957		542A1057	PIPE CULVERTS, CLASS A, TYPE 2 12"	FOOT	40	40		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1100	1100		542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	500	500		
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	227	227		* A2C022G3	TREE, CARYA ILINOENSIS (PECAN), 3-GALLON	EACH	300	300		
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	28	28		* A2C030G3	TREE, FAXINUS PENNSYLVANICA (GREEN ASH), CONTAINER GROWN, 3-GALLON	EACH	300	300		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	3852.5	3852.5		* A2C040G3	TREE, PLATANUS OCCIDENTALIS (SYCAMORE), 3-GALLON	EACH	300	300		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	3075	3075		* A2C050G3	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), CONTAINER GROWN, 3-GALLON	EACH	300	300		
* 72000200	SIGN PANEL - TYPE 2	SQ FT	91	91		* A2C060G3	TREE, QUERCUS PALUSTRIS (PIN OAK), CONTAINER GROWN, 3-GALLON	EACH	300	300		
* 72000300	SIGN PANEL - TYPE 3	SQ FT	1909	1909		X0322054	REMOVAL OF PRECAST FLARED END SECTION	EACH	2	2		
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	7	7		X0322261	REMOVE AND RELAY PRECAST FLARED END SECTION	EACH	1	1		
72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	4	4		X0322392	BEVELED PIPE AND GUARD	EACH	4	4		
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	17810	17810		X0323523	REMOVE TEMPORARY LIGHTING	L SUM	1	1		
* 73000100	WOOD SIGN SUPPORT	FOOT	70	70		X0712400	TEMPORARY PAVEMENT	SQ YD	1911	1911		
73200100	CONCRETE FOUNDATIONS FOR WOOD SIGN SUPPORT	EACH	4	4		X4069414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	10740	10740		
* 73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	29.8	29.8		X4069528	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N90	TON	3264	3264		
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1786	1786		X4069915	POLYMERIZED LEVEL BINDER (MACHINE METHOD), SUPERPAVE, N90	TON	2176	2176		

REVISIONS	
NAME	DATE
PRE-FINAL	05/24/05

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
US ROUTE 20

SCALE: VERT. N/A
HORIZ. N/A
DATE 10/28/05
DRAWN BY TVN
CHECKED BY JAM

* SPECIALTY ITEM