
CONTRACT NO. 64577


F.A.P.	SECTION	co	UNTY	TOTAL SHEETS	SHEET NO.
301	•	STE	PHENSON	290	15
STA. TO STA.					
FED. ROAD DIST. NO. 2 ILLINOIS FED. AID PROJECT					

* 177~(3, 4, 4~1)-1

SMOKEY HOLLOW ROAD



PROPOSED TYPICAL SECTION STATION 890+90.01 TO STATION 902+76.49



BASE COURSE DETAIL ON SMOKEY HOLLOW ROAD

NOTES:

- THIS CONTRACT DOES INCLUDE PAVING WORK ON US ROUTE 20 MAINLINE.
- 2. STANDARD DITCH IS 3' DEEP.
- 3. FORESLOPE SHALL BREAK TO 1:3 WHEN IT EXTENDS MORE THAN 35' FROM PROPOSED EDGE OF PAVEMENT.
- 4. SEE CROSS SECTIONS FOR AREAS OF TOPSOIL EXCAVATION AND PLACEMENT.
- 5. IN AREAS OF ROCK CUT PLACE 12" OF TOPSOIL.
- 6. THE FOLLOWING UNIT WEIGHTS WERE USED IN CALCULATING THE BITUMINOUS QUANTITIES: 112/LBS/SY/IN SURFACE COURSE 112/LBS/SY/IN BINDER COURSE 115/LBS/SY/IN SUB-BASE GRANULAR MATERIAL

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION			
NAME	DATE	ILLINOIS DEFARIMENT OF TRANSPORTATION			
PRE-FINAL	5/24/05				
		TYPICAL SECTIONS			
		SMOKEY HOLLOW ROAD			
		COULT VERT. N/A			
		SCALE: HORIZ. N/A DRAWN BY TVN			
		DATE 10/28/05 CHECKED BY JAM			