

ROUTE NO.	SECTION	COUNTY		SHEETS	NO
FAP 315		MoLEAN		44	22
STA			TO STA		
FED. POAD DIST. NO.		ILLINOIS	PED. ALD PROJECT-		
*102X-BR-2		DWG. N	10. 10	0F 17	

#5 vertical bars in new backwall construction. Cost included in Concrete Removal.

WEST ABUTMENT							
<u>BILL</u>	0F	MATERIAL					

Bar	No.	Size	Length	Shape	
h (E)	12	#6	27'-11"		
h1(E)	2	#5	36'-6"		
h₂(Ε)	3	#5	4'-9"	J	
v (E)	40	#5	2'-6"		
	1				
Concrete Removal			Cu. Yd.	3.6	
Concrete Structures			Cu. Yd.	5.3	
Reinforcement Bars, Epoxy Coated			Pound	700	
Asbestos Bearing Pad Removal			Each	30	
Bridge Seat Sealer			Sq. Ft.	21	
Epoxy Crack Sealing			Foot	30	
Formed Concrete Repair (Depth Equal to or Less Than 5")			Sq. Ft.	20.8	
Bar Splicers			Each	32	

REPAIR LEGEND Inspection Date: 11-15-01 T Rust Stained Area Moisture Stained or Leached Area ) HL Hairline Crack - Not to be Sealed )c.-6' Crack (> 16" Width) EPOXY CRACK SEALING L.C.-6' Leached Crack (> 16" Width) s.F. 🕖 Delaminated Area <u>FORMED CONC.</u> REPAIR s.F. 🚫 Spalled Area (Depth ≤ 5") WEST ABUTMENT US 136 OVER BRANCH OF SALT CREEK FAP ROUTE 315 - SECTION 102X-BR-2 MCLEAN COUNTY STATION 616+99.00 STRUCTURE NO. 057-0185