

CODE NO.	PAY ITEM	UNIT	QUANTITIES	FED / CITY 70% / 30%			
				1000-2A	Y030-1E	Y031-1F	NON-
				ROADWAY	LIGHTING	TRAFFIC SIG.	PART
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	153	153			
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	275	275			
20101000	TEMPORARY FENCE	FOOT	8,500	8,090			410
20101100	TREE TRUNK PROTECTION	EACH	113	113			
20101200	TREE ROOT PRUNING	EACH	113	113			
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	62	62			
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	55	55			
20200100	EARTH EXCAVATION	CU YD	7,500	6,600			900
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	2,535	2,535			
20400800	FURNISHED EXCAVATION	CU YD	150	150			
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	2,535	2,535			
20800150	TRENCH BACKFILL	CU YD	3,309	3,300			9
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	1,425	820			605
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	14,710	13,450			1,260
* 21101815	COMPOST FURNISH AND PLACE, 4"	SQ YD	900	900			
21301072	EXPLORATION TRENCH 72" DEPTH	FOOT	250	250			
* 25000310	SEEDING, CLASS 4	ACRE	0.3	0.3			
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	206	190			16
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	206	190			16
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	206	190			16
* 25100630	EROSION CONTROL BLANKET	SQ YD	900	900			
* 25200110	SODDING, SALT TOLERANT	SQ YD	14,710	13,450			1,260
25200200	SUPPLEMENTAL WATERING	UNIT	311	284			27
* 25300600	TRANSPLANTED SALVAGED TREES	EACH	11	11			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	350	350			
28000400	PERIMETER EROSION BARRIER	FOOT	4,390	4,300			90
28000510	INLET FILTERS	EACH	84	84			
28100105	STONE RIPRAP, CLASS A3	SQ YD	60	60			
28100107	STONE RIPRAP, CLASS A4	SQ YD	40	40			
28200200	FILTER FABRIC	SQ YD	100	100			
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	500	500			
35300400	PORTLAND CEMENT CONCRETE BASE COURSE 9"	SQ YD	23,300	23,300			
35301200	HIGH-EARLY-STRENGTH PORTLAND CEMENT CONCRETE BASE COURSE 9"	SQ YD	825	825			
35400400	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 9"	SQ YD	101	101			
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	4,400	4,200			200
40600300	AGGREGATE (PRIME COAT)	TON	45	40			5
40600895	CONSTRUCTING TEST STRIP	EACH	1	1			
42001300	PROTECTIVE COAT	SQ YD	9,200	8,335			865
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	80	80			
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	14,010	11,935			2,075

F.A.U.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2832	00-00218-00-FP	COOK	108	3
STA	TO STA			
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 83773

CODE NO.	PAY ITEM	UNIT	QUANTITIES	FED / CITY 70% / 30%			
				1000-2A	Y030-1E	Y031-1F	NON-
				ROADWAY	LIGHTING	TRAFFIC SIG.	PART
42400400	PORTLAND CEMENT CONCRETE SIDEWALK 7 INCH	SQ FT	3,140				3,140
44000007	BITUMINOUS SURFACE REMOVAL 2"	SQ YD	2,540				2,540
44000011	BITUMINOUS SURFACE REMOVAL 4"	SQ YD	3,970	3,970			
44000100	PAVEMENT REMOVAL	SQ YD	23,820	23,820			
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	425	425			
44000300	CURB REMOVAL	FOOT	200	200			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	11,075	11,026			49
44000600	SIDEWALK REMOVAL	SQ FT	13,510	11,140			2,370
44003100	MEDIAN REMOVAL	SQ FT	390	390			
44201349	CLASS C PATCHES, TYPE I, 10 INCH	SQ YD	50	50			
44201353	CLASS C PATCHES, TYPE II, 10 INCH	SQ YD	150	150			
44201357	CLASS C PATCHES, TYPE III, 10 INCH	SQ YD	150	150			
44201359	CLASS C PATCHES, TYPE IV, 10 INCH	SQ YD	50	50			
50104400	CONCRETE HEADWALL REMOVAL	EACH	4	4			
54216180	REINFORCED CONCRETE PIPE TEE, 12" PIPE WITH 12" RISER	EACH	7	7			
54216185	REINFORCED CONCRETE PIPE TEE, 15" PIPE WITH 12" RISER	EACH	3	3			
54216190	REINFORCED CONCRETE PIPE TEE, 18" PIPE WITH 12" RISER	EACH	3	3			
54216195	REINFORCED CONCRETE PIPE TEE, 21" PIPE WITH 12" RISER	EACH	3	3			
54216205	REINFORCED CONCRETE PIPE TEE, 27" PIPE WITH 12" RISER	EACH	1	1			
55100200	STORM SEWER REMOVAL 6"	FOOT	157	157			
55100300	STORM SEWER REMOVAL 8"	FOOT	568	568			
55100400	STORM SEWER REMOVAL 10"	FOOT	199	199			
55100500	STORM SEWER REMOVAL 12"	FOOT	344	344			
56100600	WATER MAIN 6"	FOOT	28	28			
56100700	WATER MAIN 8"	FOOT	5	5			
56106200	ADJUSTING WATER MAIN 4"	FOOT	50	50			
56106400	ADJUSTING WATER MAIN 8"	FOOT	50	50			
56106500	ADJUSTING WATER MAIN 10"	FOOT	50	50			
56106600	ADJUSTING WATER MAIN 12"	FOOT	50	50			
56400100	FIRE HYDRANTS TO BE MOVED	EACH	2	2			
56400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	2	2			
56400500	FIRE HYDRANTS TO BE REMOVED	EACH	2	2			
56400600	FIRE HYDRANTS	EACH	1	1			

* - SPECIALTY ITEMS

REVISIONS	
NAME	DATE
CEC/PAS	5/23/05

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
McCORMICK BOULEVARD

SCALE: NTS

DATE 9/03/04
DRAWN BY CEW
CHECKED BY PAS