

CODE NO.	PAY ITEM	UNIT	QUANTITIES	FED / CITY 70% / 30%			
				1000-2A	Y030-1E	Y031-1F	100% CITY
				ROADWAY	LIGHTING	TRAFFIC SIG.	NON-PART
* A2007628	TREE, TAXODIUM DISTICHUM (COMMON BALD CYPRESS), 3 1/2" CALIPER, BALLED AND BURLAPPED	EACH	2	2			
* A2018720	TREE, ULMUS CARPINIFOLIA MORTON, (ACCOLADE ELM), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	10	10			
* A2022166	TREE, AESCULUS PAVIA (RED BUCKEYE), 6' HEIGHT, BALLED AND BURLAPPED	EACH	1	1			
* B2006070	TREE, SYRINGA PEKINENSIS (PEKING LILAC), 8' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	1	1			
* B2010066	TREE, CHIONANTHUS VIRGINICUS (WHITE FRINGETREE), 6' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	1	1			
X0301834	STORM SEWER TO BE FILLED	FOOT	4,052	4,052			
X0321297	REMOVE EXISTING SIGN POST	EACH	1	1			
X0321556	SANITARY MANHOLES TO BE ADJUSTED	EACH	3	3			
X0322033	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	752	662			90
X0322035	STORM SEWER (WATER MAIN REQUIREMENTS) 18 INCH	FOOT	136	136			
X0322089	STORM SEWER (WATER MAIN REQUIREMENTS) 36 INCH	FOOT	133	133			
X0322125	STORM SEWER (WATER MAIN REQUIREMENTS) 24 INCH	FOOT	130	130			
X0322127	STORM SEWER (WATER MAIN REQUIREMENTS) 30 INCH	FOOT	170	170			
X0322525	STORM SEWER (WATER MAIN REQUIREMENTS) 21 INCH	FOOT	365	365			
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	168	168			
X3550300	BITUMINOUS BASE COURSE SUPERPAVE 6"	SQ YD	265	265			
X3550500	BITUMINOUS BASE COURSE SUPERPAVE 8"	SQ YD	45	45			
X4020700	AGGREGATE SURFACE COURSE, TYPE B 8"	SQ YD	100	100			
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	12	12			
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	6	6			
X4023000	TEMPORARY ACCESS (ROAD)	EACH	10	10			
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	340	40			300
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	2,450	2,450			
X4066616	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N70	TON	580	580			
X4067100	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE, IL-4.75, N50	TON	1,200	1,200			
X5121800	PERMANENT STEEL SHEET PILING	SQ FT	690	690			
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	4	4			
* X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	2			2	
* X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	1,056			1,056	
* X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	852			852	
* X8800020	SIGNAL HEAD ,LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	10			10	
* X8800035	SIGNAL HEAD ,LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	6			6	
* X8800040	SIGNAL HEAD ,LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	3			3	
* X8800045	SIGNAL HEAD ,LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	3			3	
* X8810610	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED	EACH	2			2	
* X8810620	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED	EACH	4			4	

F.A.U.	SECTION	COUNTY	TOTAL SHEET
2832	00-00218-00-FP	COOK	SHEETS NO.
STA	TO STA		108 6
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT	

CONTRACT NO. 83773

CODE NO.	PAY ITEM	UNIT	QUANTITIES	FED / CITY 70% / 30%			
				1000-2A	Y030-1E	Y031-1F	100% CITY
				ROADWAY	LIGHTING	TRAFFIC SIG.	NON-PART
* XX002957	REMOVE AND RE-ERECT EXISTING SIGN	EACH	1	1			
* XX004970	TEMPORARY PAVEMENT SUPERPAVE	SQ YD	439	439			
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	27,700	27,700			
Z0019600	DUST CONTROL WATERING	UNIT	160	160			
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1			
Δ Z0076600	TRAINEES	HOOR	1,500	1,500			
* XX006400	LIGHT POLE AND LUMINAIRE, INSTALL ONLY	EACH	3		3		
X0322032	STORM SEWER (WATER MAIN REQUIREMENTS) 10 INCH	FOOT	26	26			
* XX006401	TELEVISION OF MWRD INTERCEPTOR	FOOT	9,800	9,800			
XX006402	REMOVE AND REERECT STONE WALL	L SUM	1	1			
XX006416	END SECTIONS 24", SPECIAL	L SUM	1	1			
XX006403	END SECTIONS 30", SPECIAL	L SUM	1	1			
XX006404	END SECTIONS 36", SPECIAL	L SUM	1	1			
XX006405	LIMESTONE SCREENINGS, 2"	SQ YD	500	500			
* XX006406	BRICK PAVERS (PERMEABLE)	SQ YD	605				605
XX006407	AGGREGATE BASE COURSE 15", SPECIAL	SQ YD	605				605
XX006408	AUGERED PILE 24"	FOOT	360	360			
* K1004469	PERENNIAL PLANTS, PRAIRIE TYPE	UNIT	6	6			
42400800	DETECTABLE WARNINGS	SQ FT	120	120			

* - SPECIALTY ITEMS
Δ - Y080

REVISIONS	
NAME	DATE
CEC/PAS	5/23/05
CEC/PAS	9/06/05
CEC/PAS	12/02/05

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
McCORMICK BOULEVARD

DATE 9/03/04
DRAWN BY CEW
CHECKED BY PAS