COUNTY TOTAL SHEET SHEETS NO. F.A.U. SECTION 2832 00-00218-00-FP COOK 108 46 STA TO STA FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT

CONTRACT NO. 83773

EXISTING EQUIPMENT TO BE REMOVED LEGEND

EXISTING SIGNAL HEAD TO BE REMOVED

"E"- \Box - EXISTING SERVICE INSTALLATION TO BE REMOVED

O EXISTING SIGNAL POST AND FOUNDATION TO BE REMOVED

"E" EXISTING CONTROLLER AND FOUNDATION TO BE REMOVED

"E" \(\subseteq \text{EXISTING HANDHOLE TO BE REMOVED}

MERGENCY VEHICLE LIGHT DETECTOR TO BE REMOVED

D-O-(CONFIRMATION BEACON

"E" H EXISTING HEAVY-DUTY HANDHOLE TO BE REMOVED

EXISTING STEEL MAST ARM POLE AND FOUNDATION TO BE REMOVED

EXISTING PEDESTRIAN SIGNAL HEAD TO BE REMOVED

EXISTING PEDESTRIAN PUSH BUTTON TO BE REMOVED

NOTES FOR EXISTING TRAFFIC SIGNAL EQUIPMENT REMOVAL

THE FOLLOWING EXISTING TRAFFIC SIGNAL EQUIPMENT SHALL BE REMOVED BY THE CONTRACTOR AND SHALL REMAIN THE PROPERTY OF THE AGENCY LISTED BELOW. THE CONTRACTOR SHALL SAFELY STORE AND ARRANGE FOR PICK UP OF ALL EQUIPMENT TO BE RETURNED TO THE LISTED AGENCY AS PER THE TRAFFIC SIGNAL SPECIFICATIONS.

AGENCY: CITY OF EVANSTON

1 CONTROLLER AND CABINET (COMPLETE)

2 EMERGENCY VEHICLE LIGHT DETECTORS

THE FOLLOWING ITEMS SHALL BE REMOVED BY THE CONTRACTOR AND DISPOSED OF BY HIM AT HIS EXPENSE, THE SALVAGE VALUE OF THE REMOVED EQUIPMENT SHALL BE REFLECTED IN THE CONTRACT

2 EACH STEEL MAST ARM ASSEMBLY AND POLE 4 EACH SIGNAL POSTS 7 EACH SIGNAL HEADS

2 EACH PEDESTRIAN SIGNAL HEADS 2 EACH PEDESTRIAN PUSH BUTTONS

ILLINOIS DEPARTMENT OF TRANSPORTATION

TRAFFIC SIGNAL REMOVAL PLAN

McCORMICK BOULEVARD AT GREEN BAY ROAD



DATE 9/03/04 DRAWN BY GEW CHECKED BY SRF