



PIPE UNDERDRAIN DETAIL BITUMINOUS SHOULDER TYPICAL SECTION







SECTION E-E

SECTION F-F

DETAIL OF GUTTER OUTLET DUNCAN RD. STA. 119+40.0, 23.0' LT.






NOTES:

- 1. THE PIPE UNDERDRAINS SHALL BE PLACED AT THE LOCATIONS SHOWN ON THE PLAN AND PROFILE SHEETS.
- 2. THE PIPE UNDERDRAINS SHALL BE OUTLET INTO PROPOSED DRAINAGE STRUCTURES AS SHOWN ON THE PLAN AND PROFILE SHEETS.
- 3. THE PIPE UNDERDRAINS WILL BE PAID FOR AT THE CONTRACT UNIT PRICE PER FOOT WHICH WILL INCLUDE ALL LABOR, EQUIPMENT, PIPE, FABRIC ENVELOPE, TRENCHING, AND SAND BACKFILL
- THE APPLICABLE ARTICLES OF SECTION 601 OF THE STANDARD SPECIFICATIONS SHALL APPLY EXCEPT DELETE ALL REFERENCE TO MEASUREMENT AND PAYMENT.

PIPE UNDERDRAIN DETAIL CURB & GUTTER TYPICAL SECTION




SECTION

COUNTY 807 00-00374-00-PV CHAMPAIGN 149

- 1. THE GUTTER OUTLET SHALL BE POURED TO THE FULL DEPTH OF THE ADJACENT PAVEMENTS WITH A MINIMUM THICKNESS OF 9". THE COST OF THE ADDITIONAL GUTTER THICKNESS SHALL BE CONSIDERED INCLUDED IN THE CONTRACT UNIT PRICE FOR CONCRETE GUTTER, TYPE A MEASURED ALONG THE GUTTER FLOWLINE.
- 2. CONSTRUCTION OF THE GUTTER OUTLET WILL BE PAID FOR AT THE CONTRACT UNIT PRICE PER FOOT, MEASURED ALONG THE GUTTER FLOWLINE, FOR CONCRETE GUTTER, TYPE A.

DETAIL OF GUTTER OUTLET



SIDEWALK GENERAL NOTES

SECTION J-J

THE COST OF CONSTRUCTING THE DEPRESSED CURB AS SHOWN SHALL BE CONSIDERED INCLUDED. IN THE COST OF CONSTRUCTING COMBINATION CONCRETE CURB AND GUTTER TYPE 8-6.24 AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

THE COST OF FURNISHING AND INSTALLING THE 3/4" EXPANSION JOINTS AND *6-24" LONG TIE BARS AND THE COST OF CONSTRUCTING THE P.C.C. SIDEWALK THICKNESS TRANSITION, INCLUDING THE ADJACENT CURBING AS SHOWN, SHALL BE INCLUDED IN THE COST OF CONSTRUCTING P.C. CONCRETE SIDEWALK 6" AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

THE DETECTABLE WARNINGS SHALL BE CONSTRUCTED IN ACCORDANCE WITH STANDARD 424001 AND THE SPECIAL PROVISIONS. THE DETECTABLE WARNINGS WILL BE PAID FOR AT THE CONTRACT UNIT PRICE PER SQUARE FOOT FOR DETECTABLE WARNINGS.

THE INTEGRALLY COLORED CONCRETE RAMP INCLUDING CURBS SHALL BE CONSTRUCTED IN ACCORDANCE WITH STD. 424001 AND THE SPECIAL PROVISIONS. THIS WORK WILL BE NOT PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR P.C. CONCRETE SIDEWALK, 6".

THE NORMAL CROSS SLOPES OF SIDEWALKS SHALL BE 2.0% EXCEPT AT THE RAMP LOCATIONS.

TRANSVERSE GROOVED JOINTS SHALL BE PLACED AT 5' CENTERS AND 3/4" EXPANSION JOINTS AT 100' CENTERS.

CONCRETE SIDEWALK RAMP DETAILS

ILLINOIS DEPARTMENT OF TRANSPORTATION

MISCELLANEOUS DETAILS

DATE : 8-05 DRAWN BY : S.M.W. CHECKED BY : R.L.H.

CITY OF CHAMPAIGN

SECTION NO. 00-00374-00-PV

CHAMPAIGN COUNTY

SHEET 100 OF 149 SHEETS C01330