INDEX OF SHEETS

COVER SHEET

PLAN & PROFILE

BRIDGE PLANS

(SEE PROPOSAL)

STANDARDS: 280001-02 - EROSION CONTROL EE PROPOSAL) 702001-05 - TRAFFIC BLR 22-6 - TRAFFIC BLR 22-4 - TRAFFIC

SUMMARY OF QUANTITIES X080-2A OUANTITY UNIT ITEM CODE NO. 524 CU YD CHANNEL EXCAVATION 20300100 267 TON STONE DUMPED RIPRAP, CLASS A4 28100807 533 SQ YD FILTER FABRIC 28200200 1 EACH REMOVAL OF EXISTING STRUCTURES 50100100 36,2 CU YD CONCRETE STRUCTURES 50300225 PRECAST PRESTRESSED CONCRETE DECK BEAMS 2,800 SQ FT 50400305 (17" DEPTH) 4,260 POUND REINFORCEMENT BARS 50800105 200 FOOT STEEL RAILING, TYPE S1 50900205 FURNISHING STEEL PILES HP 10X42 396 FOOT 51201400 396 FOOT DRIVING STEEL PILES 51202700 2 EACH TEST PILE STEEL HP 10X42 51203400 11 CU YD CONCRETE ENCASEMENT 51204315 20 EACH METAL SHOES 51204600 1 EACH NAME PLATES 51500100

1 L SUM MOBILIZATION

TOLL FREE JOINT UTILITY LOCATING INFORMATION FOR EXCAVATORS (J.U.L.I.É.)

TELEPHONE NO. 1-800-892-0123

1 L SUM TRAFFIC CONTROL AND PROTECTION

FUNCTIONAL CLASS: RURAL LOCAL ROAD ADT = 75

CONTRACT NO. 95446

67100100

70101700

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS

PLANS FOR PROPOSED

FEDERAL-AID B.R.R. PROGRAM

CRAWFORD COUNTY

SECTION 05-02114-00-BR

HUTSONVILLE ROAD DISTRICT


STRUCTURE NO. 017-3280

PROJECT NO. BROS-033(41) JOB NO. C-97-038-05

TR 226

SCALES

PROFILE HORZ. 1 INCH = 50 FEET PROFILE VERT. 1 INCH = 10 FEET



LOCATION MAP

APPROXIMATE SCALE: 1 INCH = 1 MILE NET LENGTH = 101.53 FT, = 0.019 MILES

ILLINOIS REGISTERED PROFESSIONAL ENGINEER # 31350

APPROVED Saple-ber 7, 2005

RELEASING FOR BID BASED ON LIMITED REVIEW

PUTY DIRECTOR OF HIGHWA REGION FOUR ENGINEER STATE OF ILLINOIS