SCHEDULE OF QUANTITIES MCLEAN COUNTY - S.W. SPAGHETTI BOWL - INDIVIDUAL LOCATIONS

SHEET 1 OF 2

Location No.	5-09		
Structure No.	5 \$ 057 1074 L134.10		
County / Route	MCLEAN CO I-74 WB - just East of the I-55/Business Loop 55 interchange		
Scope of Work	This overhead sign structure is being replaced on new drilled shaft foundations.		
CODE NUMBER	PAY ITEM	UNIT	QUANTITY
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	1.00
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1.00
72000300	SIGN PANEL - TYPE 3	SQFT	689.50
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	721.00
73300300	OVERHEAD SIGN STRUCTURE - SPAN, TYPE III-A (5'-0" X 7'-0")	FOOT	86.00
73301810	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	65.00
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CUYD	22.00
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	1.00
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	2.00
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	6.00
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	1.00

Pay Item for CMS is for the advanced interstate notice only. CMS shown on Standards are included in the cost of the Standard.

	5-10	Location No.
	5 S 057 I055 R156.20	Structure No.
	MCLEAN CO I-55 NB - just South of the split with Loop 55 & I-74 East	County / Route
	Truss is to be removed & re-erected on new end supports and new drilled shaft fdns.	Scope of Work
UNIT QUANT	PAY ITEM	CODE NUMBER
EACH	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	70100205
EACH	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	70100420
EACH	TRAFFIC CONTROL AND PROTECTION, STANDARD 701446	70100430
SQFT (SIGN PANEL - TYPE 3	72000300
SQFT	REMOVE SIGN PANEL - TYPE 3	72400330
FOOT	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	73301810
CUYD	DRILLED SHAFT CONCRETE FOUNDATIONS	73400200
EACH	REMOVE CONCRETE FOUNDATION - OVERHEAD	73700300
EACH	STRUCTURAL STEEL SUPPORT FOR OVERHEAD SIGN STRUCTURE - SPAN	73800100
EACH	REMOVE AND REERECT OVERHEAD SIGN STRUCTURE - SPAN	73801100
CAL DA	CHANGEABLE MESSAGE SIGN	X7015005
EACH	ELECTRICAL SERVICE DISCONNECT	X8040310

Location No.	5-11		
Structure No.	5 S 057 U055 R000.20		
County / Route	MCLEAN CO NB Business Loop 55 / Veterans Pkwy - just S. of the exit to I-74 EB		
Scope of Work	This overhead sign structure is being replaced on new drilled shaft foundations.		
CODE NUMBER	PAY ITEM	UNIT	QUANTITY
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	1.00
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1.00
72000300	SIGN PANEL - TYPE 3	SQFT	510.00
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	441.00
73300200	OVERHEAD SIGN STRUCTURE - SPAN, TYPE II-A (4'-6" X 5'-3")	FOOT	70.00
73301810	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	58.00
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CUYD	21.50
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	1.00
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	2.00
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	6.00
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	1.00

Note: new end supports are included in the cost of OVERHEAD SIGN STRUCTURE - SPAN per Section 733 of the Std. Specs. Pay Item for CMS is for the advanced interstate notice only. CMS shown on Standards are included in the cost of the Standard.

• VARIOUS •• D-5 OVD SIN STR REPL 2012-06

FILE NAME :	USER NAME = cearlockjd	DESIGNED -	REVISED -		SCHEDULE OF QUANTITIES			F.A.	SECTION	COUNTY	TOTAL SHEET	
c:\pw_work\pwidot\ceerlockjd\d0266557\D	546179-sht-schedule.dgn	DRAWN ~	REVISED -	STATE OF ILLINOIS					N/E.	••	Various	178 59
	PLOT SCALE = 40.0000 '/ in.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION	MCLEAN COUNTY - S.W. SPAGHETTI BOWL - INDIVIDUAL LOCATIONS						NO. 46179	
	PLOT DATE = 10/7/2011	DATE - REVISED -			SCALE: N/A SHEET NO. 1 OF 2 SHEETS STA. TO STA.		ILLINOIS FED. AID PROJ					