SCHEDULE OF QUANTITIES MCLEAN COUNTY - U.S. 51 BUSN. - INDIVIDUAL LOCATIONS

| Location No. | 5-17 | | |
|----------------|---|-------|----------|
| Structure No. | 5 S 057 U051 R006.80 | | |
| County / Route | MCLEAN CO NB US 51 Business between Raab Rd. and I-55 | | |
| Scope of Work | This overhead sign truss is to be removed & replaced with a breakaway ground mount at Sta. 41+30. The existing ground mount at Sta. 41+61 is also to be removed. | | |
| CODE NUMBER | PAY ITEM | UNIT | QUANTITY |
| 60618320 | CONCRETE MEDIAN SURFACE, 6 INCH | SQFT | 158.0 |
| 63200310 | GUARDRAIL REMOVAL | FOOT | 205.0 |
| 70102630 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701601 | L SUM | 0.1 |
| 72000300 | SIGN PANEL - TYPE 3 | SQFT | 115.0 |
| 72400330 | REMOVE SIGN PANEL - TYPE 3 | SQFT | 362.7 |
| 72700100 | STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY | POUND | 979.0 |
| 73400100 | CONCRETE FOUNDATIONS | CUYD | 2.3 |
| 73600100 | REMOVE OVERHEAD SIGN STRUCTURE - SPAN | EACH | 1.0 |
| 73700100 | REMOVE GROUND MOUNTED SIGN SUPPORT | EACH | 2.0 |
| 73700200 | REMOVE CONCRETE FOUNDATION - GROUND MOUNT | EACH | 2.0 |
| 73700300 | REMOVE CONCRETE FOUNDATION - OVERHEAD | EACH | 2.0 |
| X4403800 | MEDIAN SURFACE REMOVAL | SQFT | 158.0 |
| X6320100 | GUARDRAIL REMOVAL SPECIAL | FOOT | 546.0 |
| X8040310 | ELECTRICAL SERVICE DISCONNECT | EACH | 1,0 |

| Location No. | 5-18 | | |
|----------------|--|-------|----------|
| Structure No. | 5 C 057 U051L006.90 | | |
| County / Route | MCLEAN CO SB US 51 Business between I-55 and Raab Rd. | | |
| Scope of Work | This overhead cantilever is to be removed & replaced with a breakaway ground mount at Sta. 44+70 and a new traffic signal mast arm at Sta. 43+23.5 | | |
| CODE NUMBER | PAY ITEM | UNIT | QUANTITY |
| 70102630 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701601 | L SUM | 0.1 |
| 72000300 | SIGN PANEL - TYPE 3 | SQFT | 66.0 |
| 72400330 | REMOVE SIGN PANEL - TYPE 3 | SQFT | 78.0 |
| 72700100 | STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY | POUND | 495.0 |
| 73400100 | CONCRETE FOUNDATIONS | CUYD | 1.4 |
| 73600200 | REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER | EACH | 1.0 |
| 73700300 | REMOVE CONCRETE FOUNDATION - OVERHEAD | EACH | 1.0 |
| 81028360 | UNDERGROUND CONDUIT, PVC, 2 1/2" DIA. | FOOT | 4.0 |
| 87301245 | ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 145C | FOOT | 42.0 |
| 87700280 | STEEL MAST ARM ASSEMBLY AND POLE, 48 FT. | EACH | 1.0 |
| 87800415 | CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER | FOOT | 13.0 |
| 87900200 | DRILL EXISTING HANDHOLE | EACH | 1.0 |
| 88030020 | SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED | EACH | 2.0 |
| 88030070 | SIGNAL HEAD, LED, 1-FACE, 4-SECTION, BRACKET MOUNTED | EACH | 1.0 |
| 88030080 | SIGNAL HEAD, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED | EACH | 1.0 |
| 89502350 | REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT | FOOT | 110.0 |
| X8040310 | ELECTRICAL SERVICE DISCONNECT | EACH | 1.0 |
| X8950305 | REMOVE EXISTING SIGNAL HEAD | EACH | 3.0 |

| Location No. | 5-19 | | |
|----------------|--|-------|----------|
| Structure No. | 5 C 057 U051L007.30 | | |
| County / Route | MCLEAN CO SB US 51 Business between Northtown Rd. and I-55 | | |
| Scope of Work | This overhead cantilever is to be removed & replaced with a breakaway ground mount at Sta. 58+40 and a new traffic signal mast arm at Sta. 56+91 | | |
| CODE NUMBER | PAY ITEM | UNIT | QUANTITY |
| 70102630 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701601 | L SUM | 0.1 |
| 72000300 | SIGN PANEL - TYPE 3 | SQFT | 115.0 |
| 72400330 | REMOVE SIGN PANEL - TYPE 3 | SQFT | 221.2 |
| 72700100 | STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY | POUND | 946. |
| 73400100 | CONCRETE FOUNDATIONS | CUYD | 2.3 |
| 73600200 | REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER | EACH | 1,1 |
| 73700300 | REMOVE CONCRETE FOUNDATION - OVERHEAD | EACH | 1.1 |
| 81028360 | UNDERGROUND CONDUIT, PVC, 2 1/2" DIA. | FOOT | 25. |
| 87301245 | ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C | FOOT | 458. |
| 87301255 | ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 147C | FOOT | 248. |
| 87700280 | STEEL MAST ARM ASSEMBLY AND POLE, 48 FT. | EACH | 1. |
| 87800415 | CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER | FOOT | 13. |
| 87900200 | DRILL EXISTING HANDHOLE | EACH | 1. |
| 88030020 | SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED | EACH | 2. |
| 88030070 | SIGNAL HEAD, LED, 1-FACE, 4-SECTION, BRACKET MOUNTED | EACH | 1. |
| 88030080 | SIGNAL HEAD, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED | EACH | 1. |
| 89502300 | REMOVE ELECTRIC CABLE FROM CONDUIT | FOOT | 259. |
| X8040310 | ELECTRICAL SERVICE DISCONNECT | EACH | 1. |
| X8950305 | REMOVE EXISTING SIGNAL HEAD | EACH | 3. |

| Location No. | 5-20 | | |
|----------------|--|------|----------|
| Structure No. | 5 B 057 U051 R007.10 | | |
| County / Route | MCLEAN CO NB US 51 Business under I-55 bridge 057-0024 | | |
| Scope of Work | This bridge mounted truss is to be removed. | | |
| CODE NUMBER | PAYITEM | UNIT | QUANTITY |
| 70102630 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701601 | LSUM | 0.14 |
| 72400330 | REMOVE SIGN PANEL - TYPE 3 | SQFT | 84.0 |
| 73602000 | REMOVE OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED | EACH | 1.00 |
| X8040310 | ELECTRICAL SERVICE DISCONNECT | EACH | 1.00 |

• VARIOUS
• D-5 OVD SIN STR REPL 2012-06

| ı | FILE NAME = | USER NAME = cearlockjd | DESIGNED - | REVISED - | |
|---|---|-----------------------------|------------|-----------|--|
| 1 | ct/pwwork/pwidot/coorlook.jd/d0266557/0 | 346179-sht-schedule.dgn | DRAWN - | REVISED - | |
| ı | | PLOT SCALE = 40.0000 '/ in. | CHECKED - | REVISED - | |
| 1 | | PLOT DATE = 10/7/2011 | DATE - | REVISED - | |

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

| | | SCHEDULE OF QUANTITIES | |
|---|------------|--|---|
| - | MCLEAN | COUNTY - U.S. 51 BUSN INDIVIDUAL LOCATIONS | |
| | SCALE: N/A | SHEET NO. 1 OF 1 SHEETS STA. TO STA. | _ |

| F.A. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. | |
|---------------------------|---------|---------|-----------------|--------------|--|
| ٠ | ** | Various | 178 | 148 | |
| CONTRACT NO. 46179 | | | | | |
| ILLINOIS FED. AID PROJECT | | | | | |