

PLOT DATE : +DATE+

DATE

REVISED

SHEET NO. OF SHEETS STA. SCALE:

BAR LIST - EACH FOUNDATION

Bar	Number	Size	Length	Shape			
V4(E) 24		#9	F less 5"				
#4 bar spiral (E) - see Side Elevation							

ł

The foundation dimensions shown are based on the presence of mostly cohesive soils with an average Unconfined Compressive Strength (Qu) of at least 1.25 tsf, which must be determined by previous soil investigations at the jobsite. When other conditions are indicated, the boring data will be included in the plans and the foundation dimensions shown will be the

If the conditions encountered are different than those indicated, the Contractor shall notify the Engineer to determine if the foundation dimensions need to be modified. If dimensions "B" or "F" are revised by more than 12" by the Contractor, "as-built" plans shall be prepared and submitted to the District Bureau of Operations for future reference. No sonotubes or decomposable forms shall be used below the lower conduit entrance. Permanent metal forms or other shielding may not be left in place below that elevation

Backfill shall be placed per Article 502 of Standard Specification and prior to erection

A normal surface finish followed by a Bridge Seat Sealer application will be required on concrete surfaces above the lawest elevation 6" below finished ground line. Cost included

Right Fo	undation		Class DS	
Elevation Bottom	A	В	F	Concrete (Cu. Yds.)
710.04	2'-91/8 "	17'-6 ''	20'-31/8 "	20.8
628.77	2'-0 ''	17'-6 ''	19'-6 ''	21.2

	· · ·			

CTURES AILS		F.A. RTÉ.	SECTION	COUNTY	SHEETS	SHEET NO.	
		VARS	•		17	13	
				CONTRACT	NO. 4	16194	
	TO STA.		ILLINDIS FED. AID PROJECT				
		• D7 OVD :	SIN STR	R REPL 12-21		Coles	, Macon