

NOTES:

- 1. USE BLACK LETTERING ON ORANGE BACKGROUND.
- 2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
- 3. ERECT SIGN () WITH INSTALLED PANEL (2) ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
- 4. REMOVE PANEL 2 SOON AFTER THE START OF CONSTRUCTION.
- 5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- 6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
- 7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

REVISED	-	R.	MIRS	09	-15-97	
REVISED	-	R.	MIRS	12	-11-97	***************************************
REVISED	- T.	RA	MMACH	ER	02-02-	-99
REVISED		_	HICT	ıs	01-31-0	7

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

ARTERIAL ROAD INFORMATION SIGN

		DESIGNED - SLV	REVISED -		DISTRICT ONE DETAIL SHEETS		F.A.P.	SECTION	COUNTY	TOTAL SHEET
	DRAWN - SLV	REVISED -	STATE OF ILLINOIS	IL ROUTE 171 OVER MILNE CREEK		577	D-T	WILL	44 43	
CONSULTING ENGINEERS 1560 WALL ST, SUITE 222		CHECKED - MJY, ST	REVISED -	DEPARTMENT OF TRANSPORTATION	IL NOUTE 1/1 OVER WILINE GREEK		D-9	11-265-06	CONTRACT	NO. 60B10
NAPERVILLE, ILLINOIS 60563 PH: (630) 577-9100		DATE - 10/14/2011	REVISED -		SCALE:	SHEET NO. 11 OF 12 SHEETS STA. 60+40 TO STA. 63+68	FED. ROAD DIST.	. NO. ILLINOIS FED. AID	PROJECT	