

NOTES:

- 1. USE BLACK LETTERING ON ORANGE BACKGROUND.
- 2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
- 3. ERECT SIGN (1) WITH INSTALLED PANEL (2) ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
- 4. REMOVE PANEL 2 SOON AFTER THE START OF CONSTRUCTION.
- 5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- 6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
- 7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

FIL	E NAME =	USER NAME = midyje	DESIGNED -	REVISED - R. MIRS 09-15-97		ARTERIAL ROAD	F.A.	SECTION	COUNTY TOTAL SHEET
c:\	.pw_work\pwidot\midyja\d0248716\DistSt	d.dgn	DRAWN -	REVISED - R. MIRS 12-11-97	STATE OF ILLINOIS		32	26 104-RS-11	MCHENRY 29 29
		PLOT SCALE = 50.0000 '/ in.	CHECKED -	REVISED -T. RAMMACHER 02-02-99	DEPARTMENT OF TRANSPORTATION	INFORMATION SIGN		TC-22	CONTRACT NO. 60N39
		PLOT DATE = 10/20/2011	DATE -	REVISED - C. JUCIUS 01-31-07		SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.	FEC		AID PROJECT