

## BEARING ASSEMBLY

1'-1"

Note: Shim plates shall not be placed under Bearing Assembly.

in lieu of ASTM F1554.

Anchor bolts at fixed bearings may be either cast in place or installed in holes drilled after the supported member is in place.

Anchor bolts for side retainers may be cast in place or installed in holes drilled before or after members are in place.

Drilled and set anchor bolts shall be installed according to Article 521.06 of the Standard Specifications.



12"

## BEARING SEAT ELEVATIONS

Beam	W. Abut.	E. Abut.	
1	751.67	749.12	
2	751.81	749.25 749.38	
3	751.95		
4	752.09	749.50	
5	752.23	749.63	
6	752.06	749.45	
- 7	751.87	749.25	
8	751.69	749.06	
9	751.51	748.86	
10	751.55	748.89	
11	751.69	749.01	

\* Provide 58" thick Shim P

	PH: (312)	EERS & SURVEYORS 551-9780 ucturedesignsinc.com	2E-1	7-1	- 10		
FILE NAME =		USER NAME =	DESIGNED - L	_RT / AG	REVISED -		BEARING DETAILS
· · · ·			CHECKED - C	DAO / LRT	REVISED -	STATE OF ILLINOIS	STRUCTURE NO. 049-0
		PLOT SCALE = N.T.S.	DRAWN ~ 1	TCS / AG	REVISED -	DEPARTMENT OF TRANSPORTATION	
	PLOT DATE = Ø9/Ø1/2011 CHECKED - AG	AG	REVISED -		SHEET NO. OF SHEET		

..\0490534-60P76-008-Bearing details.dgn 12/13/2011 12:14:00 PM\_\_\_



SECTION B-B

-

BILL OF MATERIAL

Item	Unit	Total
Furnishing Elastomeric Bearing Assembly, Type I	Each	11
* Anchor Bolts, 1"	Each	44

\* Anchor Bolts not included in this Contract

	F.A.U RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
0534	1199	2011-056-F	LAKE	19	19	
JJJ4		1	CONTRACT	NO. 6	50P76	
S	ILLINOIS FED. AID PROJECT					