

NOTES:

- 1. USE BLACK LETTERING ON ORANGE BACKGROUND.
- 2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
- 3. ERECT SIGN (1) WITH INSTALLED PANEL (2) ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
- 4. REMOVE PANEL (2) SOON AFTER THE START OF CONSTRUCTION.
- 5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- 6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
- 7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

	Г	DEGTON TO				TEAH	T		TOTAL SHEET
FILE NAME =	USER NAME = midyja	DESIGNED -	REVISED - R. MIRS 09-15-97		ARTERIAL ROAD	RTF	SECTION	COUNTY	SHEETS NO.
c:\pw_work\pwidot\midyja\d0275511\DistSto	d.dgn	DRAWN -	REVISED - R. MIRS 12-11-97	STATE OF ILLINOIS		0327	111-RS-9	WILL	17 17
	PLOT SCALE = 50.0000 '/ in.	CHECKED -	REVISED -T. RAMMACHER 02-02-99	DEPARTMENT OF TRANSPORTATION	INFORMATION SIGN		TC-22	CONTRACT	NO. 60P71
	PLOT DATE = 10/19/2011	DATE -	REVISED - C. JUCIUS 01-31-07		SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.	FED. R		FED. AID PROJECT	