JSER NAME = \$USER\$

PLOT SCALE = \$SCALE\$

PLOT DATE = SDATES

FILE NAME =

\$FILEL\$

DESIGNED

CHECKED

DATE

DA

JR/BB


06/08/2011

REVISED


REVISED

REVISED

REVISED 01/03/2012 ADDENDUM 🛕



TYPICAL SECTION A - 3.0' SEGMENTAL CONCRETE BLOCK WALL



NOTES:

- 1. IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY EXISTING CONDITIONS AND DIMENSIONS BEFORE START OF THE WORK OR ORDERING MATERIALS.
- SEE GRADING PLANS FOR LOCATIONS, GRADING, LENGTH AND ELEVATIONS
- 3. THE BASE FOUNDATION FOR THE GRANULAR LEVELING PAD SHALL BE APPROVED BY THE RESIDENT ENGINEER PRIOR TO PLACEMENT OF THE LEVELING PAD. MINIMUM SOIL PRESSURE UNDER PAD=2000 PSF.
- 4. EACH COURSE OF THE MODULAR BLOCKS TO BE SET BACK 34" FROM THE COURSE BELOW.
- SEE SPECIAL PROVISION FOR SEGMENTAL CONCRETE BLOCK WALL.
- 6. PIPE UNDERDRAINS FOR STRUCTURES SHALL INCLUDE THE 4" DIA. PERFORATED PIPE DRAIN, GEOTECHNICAL FABRIC FOR FRENCH DRAINS, CA-2 DRAINAGE AGGREGATE. PIPES SHALL OUTLET THROUGH WALL.
- 7. USE SUITABLE NON-SPECIAL WASTE FROM DEMINIMUS SITES IN-LIEU OF FURNISHED EXCAVATION IN LOCATIONS THAT 2" COVER IS PRESENT.
- 8. THE GENERAL CONTRACTOR IS REQUIRED TO HIRE AN ENVIRONMENTAL FIRM WITH AT LEAST FIVE (5) DOCUMENTAED LEAKING UNDERGROUND STORAGE TANKS (LUST) CLEANUPS OR THAT IS PRE-QUALIFIED IN HAZARDOUS WASTE BY THE DEPARTMENT TO REMEDIATE THE SOIL CONTAMINATION AND MONITOR FOR WORKER PROTECTION.

10/24/2011					

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION
 SEGMENTAL CONCRETE BLOCK WALL
 F.A.P. RTE.

 TYPICAL SECTION AND ELEVATION

 SCALE: AS SHOWN SHEET NO. 1 OF 2 SHEETS STA. 888+50.00 TO STA. 892+50.00

 FED. ROAD DIST.

A.P. SECTION COUNTY TOTAL SHEET NO. 347 02-00077-00-SW DUPAGE 73 53 CONTRACT NO. 63197