


NOTE: ALL CONSTRUCTION TO BE DONE ACCORDING TO STATE OF ILLINOIS "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION"

> CUT OUT DIRT ON SHOULDER, INSTALL 12" AGGREGATE BASE COURSE, AND PAVE WITH 2 1/2" HMA SURFACE COURSE, MIX "D", N50 TO THE NEW PROPERTY LINE.

ALL GROUND AREAS DISTURBED SHALL BE RESEEDED AND MULCHED OR JUTE MATTED AS SOON AFTER CONSTRUCTION AS POSSIBLE.

A PAVED MAILBOX TURNOUT MUST BE CONSTRUCTED ACCORDING TO IDOT BLR 24-2, IF A MAILBOX IS PRESENT ADJACENT TO A RURAL CROSS-SECTION (NO CURB AND GUTTER). IF NO MAILBOX IS PRESENT ADJACENT TO A RURAL CROSS-SECTION (NO CURB AND GUTTER) OR A MAILBOX IS PRESENT ADJACENT TO AN URBAN CROSS-SECTION (CURB AND GUTTER), NO PAVED MAILBOX TURNOUT SHALL BE PROVIDED. 11-2", NOT-MIX ASPHALT BASE COURSE, 11 1/2", AGGREGATE SUBGRADE 12", POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, NSO, 3/4" (+ VARIES) AND AGGREGATE SHOULDERS, TYPE B 8" PER QUANTITIES IN PLAN IF MAILBOX TURNOUT IS REQUIRED. MAILBOX TURNOUT PAVEMENT DESIGN SHALL MATCH ADJACENT PAVEMENT DESIGN.



9	SEC Group, Inc.
	An HR Green Company 323 Alana Chiva, New Lanau, Illinois 60451 L 815-862-9324 f. 815-862-9328 www.segruptin.com -Michienry, ILYörkville, ILNew Lenax, ILChicago, IL.

USER NAME = RBest	DESIGNED	-	BDC	REVISED	-
	DRAWN	-	RCB	REVISED	
PLOT SCALE = NONE	CHECKED	-	APS	REVISED	-
PLOT DATE = 11/8/2011	DATE	-	11/8/11	REVISED	-
			······································		

ILLINOIS DEPARTMENT OF TRANSPORTATION PROPOSED ROADWAY IMPROVEMENTS C.H. 52 (GOUGAR ROAD) AT U.S. ROUTE 30

I	AUGOSTI ANISONO DETANO	F.A.U RTE.	SECTION NO.	COUNTY	TOTAL	SHEET NO.
MISCELLANEOUS DETAILS			07-00154-11-TL	WILL	70	61
I				CONTRACT	NO. (53597
ı	SCALE: NONE SHEET NO. 13 OF 13 SHEETS STA. TO STA.	FED. RO	AD DIST. NO. ILLINOIS FED. A	ID PROJECT		