# GENERAL NOTES

44 WHERE TRENCH BACKFILL IS REQUIRED, THE MATERIAL USED SHALL BE COMPACTED AS SPECIFIED IN ARTICLE 550.07 OF THE STANDARD SPECIFICATIONS USING METHOD ONE.

45 BEFORE ORDERING STORM SEWERS, CATCH BASINS, PIPE CULVERTS, PIPE DRAINS, AND MANHOLES, THE CONTRACTOR SHALL CONTACT THE ENGINEER AS TO THE LENGTH AND QUANTITY REQUIRED.

46 PATCHING ITEMS WILL BE MEASURED FOR PAYMENT AT EACH LOCATION BASED ON THE FULL ROADWAY WIDTH TO DETERMINE PATCHING TYPE. STAGING OF PATCHES WILL NOT BE USED TO DETERMINE PATCH TYPES.

47 UNLESS OTHERWISE INDICATED, ALL VEGETATIVE AND STRUCTURAL EROSION AND SEDIMENT CONTROL PRACTICES WILL BE CONSTRUCTED ACCORDING TO MINIMUM STANDARDS AND SPECIFICATIONS IN THE ILLINOIS URBAN MANUAL REVISED FEBRUARY 2002.

48 THE KANE-DUPAGE SOIL AND WATER CONSERVATION DISTRICT (KDSWCD) MUST BE NOTIFIED ONE WEEK PRIOR TO THE PRE-CONSTRUCTION CONFERENCE, ONE WEEK PRIOR TO THE COMMENCEMENT OF LAND DISTURBING ACTIVITIES AND ONE WEEK PRIOR TO THE FINAL INSPECTION.

49 A COPY OF THE APPROVED EROSION AND SEDIMENT CONTROL PLAN SHALL BE MAINTAINED ON THE SITE AT ALL TIMES.

50 PRIOR TO COMMENCING LAND DISTURBING ACTIVITIES IN AREAS OTHER THAN INDICATED ON THESE PLANS (INCLUDING BUT NOT LIMITED TO, ADDITIONAL PHASES OF DEVELOPMENT AND OFF-SITE BORROW OR WASTE AREAS) A SUPPLEMENTARY EROSION CONTROL PLAN SHALL BE SUBMITTED TO THE OWNER FOR REVIEW BY THE KDSWCD.

51 THE CONTRACTOR IS RESPONSIBLE FOR INSTALLATION OF ANY ADDITIONAL EROSION CONTROL MEASURES NECESSARY TO PREVENT EROSION AND SEDIMENTATION AS DETERMINED BY THE KDSWCD.

52 SHOULD DEWATERING OPERATIONS BE REQUIRED, THE CONTRACTOR MUST COORDINATE THEIR WORK WITH THE KDSWCD AND MEET ALL KDSWCD REQUIREMENTS. DURING DEWATERING OPERATIONS, WATER WILL BE PUMPED INTO SEDIMENT BASINS OR SILT TRAPS. DEWATERING DIRECTLY INTO FIELD TILES OR STORMWATER STRUCTURES IS PROHIBITED.

53 REMOVAL OF REFLECTIVE PAVEMENT MARKERS OF ALL TYPES IS INCLUDED IN THE CONTRACT UNIT PRICES FOR PAVEMENT MARKING REMOVAL. REMOVAL OF REFLECTIVE PAVEMENT MARKERS IS REQUIRED IN AREAS WHERE THE EXISTING PAVEMENT MARKINGS HAVE BEEN REMOVED OR AS DIRECTED BY THE ENGINEER. WORK SHALL BE PERFORMED IN ACCORDANCE WITH ARTICLE 783.03(b) OF THE SSRBC. THIS WORK WHICH INCLUDES RESTORATION OF EXISTING PAVEMENT TO REMAIN IN PLACE DAMAGED BY REMOVAL OPERATIONS WILL NOT BE MEASURED FOR PAYMENT AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

54 MEDIANS TO BE PAINTED AS DIRECTED BY THE ENGINEER. THIS WORK WILL NOT BE PAID FOR SEPARATELY. THE COST SHALL BE CONSIDERED AS INCLUDED IN THE CONTRACT UNIT PRICE FOR CONCRETE MEDIAN SURFACE, 4 INCH AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

**EMERALD ASH BORER COMPLIANCE AGREEMENT**

NOTICE IS HEREBY GIVEN TO THE CONTRACTOR THAT THIS PROJECT IS IN THE EMERALD ASH BORER QUARANTINED AREA AS DEFINED BY THE ILLINOIS DEPARTMENT OF AGRICULTURE. ALL WORK WITHIN THIS CONTRACT SHALL BE IN ACCORDANCE WITH THE ILLINOIS DEPARTMENT OF AGRICULTURE GUIDELINES.

THE EMERALD ASH BORER COMPLIANCE AGREEMENT MUST BE ENTERED INTO BY THE CONTRACTOR AND THE ILLINOIS DEPARTMENT OF AGRICULTURE PRIOR TO CONSTRUCTION AND THE SIGNED AGREEMENT BETWEEN THE ILLINOIS DEPARTMENT OF AGRICULTURE AND THE CONTRACTOR MUST BE GIVEN TO THE ENGINEER PRIOR TO CONSTRUCTION.

PLEASE SEE THE EMERALD ASH BORER WEBSITE AT WWW.ILLINOISEAB.COM FOR FURTHER INFORMATION.

THE PROPER REMOVAL AND DISPOSAL AS SET FORTH BY THE ILLINOIS DEPARTMENT OF AGRICULTURE SHALL NOT BE PAID FOR SEPARATELY BUT SHALL BE CONSIDERED INCLUDED IN THE COSTS OF THE CONTRACT.

| | |
|---|---|
| ComEd<br>Joe Stacho<br>1N423 Swift Road<br>Lombard, IL 60148<br>630-424-5704 | Aerial-Electric |
| Comcast<br>Martha Gieras<br>688 Industrial Drive<br>Elmhurst, IL 60126<br>630-600-6352 | Underground-Cable TV |
| Nicor<br>Ms. Connie Lane<br>1844 Ferry Road<br>Naperville, IL 60563<br>630-388-3830 | Underground-Gas |
| Verizon<br>Jim Todd<br>7719 W. 60th Place<br>Summit, IL 60501<br>708-458-6410 | Underground- Fiber Optic Telephone |
| ATT<br>Mr. Tom Follin<br>1000 Commerce Drive<br>Oakbrook, IL 60532<br>630-573-6477 | Underground-Telephone |
| AT&T LNS<br>Mr. Bobby Akhter<br>4513 Western Avenue RM 227<br>Lisle, Illinois 60532<br>630-719-1483 | Underground-Telephone |
| Level 3 Communications<br>Ms. Danett Kennedy<br>1025 Eldorado Boulevard<br>Broomfield, CO 80021<br>(720) 888-1000 | Underground-Telephone |
| Elgin Police Department<br>151 Douglas Avenue<br>Elgin, IL 60120<br>847-289-2700 | Police Department |
| Elgin Fire Department<br>550 Summit Street<br>Elgin, IL 60120<br>847- 931-6175 | Fire Department |
| School District 46<br>355 E. Chicago Street<br>Elgin, IL 60120<br>847-888-5000 | School District |

-DENOTES ITEMS AND WORK, NOT PAID FOR SEPARATELY.

PLAN: SURVEYED / PLOTTED / ALIGNMENT CHECKED / CADD FILE NAME / NOTE BOOK / NO. / BY / DATE

PROFILE: SURVEYED / PLOTTED / GRADES CHECKED / BALANCED / STRUCTURE NOTATNS CH'KD / NOTE BOOK / NO. / BY / DATE