


4-FOOT HIGH ORANGE CONSTRUCTION FENCING.
SECURE TO POSTS WITH WIRE TIES


STEEL T-POSTS @ 8-FOOT MAX. SPACING. SET LINE OF POSTS NO CLOSER TO TREE TRUNK THAN THE LIMITS OF TREE CANOPY.

MULTIPLE TREES MAY BE ENCLOSED BY A SINGLE FENCE LINE PROVIDED FENCE INCLUDES LIMITS OF TREE CANOPY.

TREE PROTECTION FENCE SHALL REMAIN IN PLACE THROUGHOUT THE DURATION OF CONSTRUCTION AND SHALL BE REMOVED ONLY BY PERMISSION OF THE OWNER. CONTRACTOR SHALL NOT STORE ANY MATERIALS OR EQUIPMENT WITHIN TREE PROTECTION ZONE.

TREE PROTECTION DETAIL





5 VEGETATED SHORELINE SECTION
SCALE: 1/4" = 1'-0"

FILE NAME =	DESIGNED	-	TL/WS	REVISED	-
	DRAWN	-	TL/BD	REVISED	-
USER NAME =	CHECKED	-	WS	REVISED	-
PLOT DATE =	DATE	-	10/24/2011	REVISED	-



RED GATE ROAD				SECTION	COUNTY	SHEETS	NO.
PLANTING DETAILS				04-00092-00-BR	KANE	440	181
			CONTRACT NO. 63650				
	STA.	TO STA.	ILLINOIS FED. AID PROJECT				

SCALE: VARIES