


NOTES:

1. ONLY STAGE 1 TRAFFIC PATTERN IS BEING SHOWN. DURING WINTER SHUT DOWN, TRAFFIC WILL BE RESUMED ON ALL EXISTING LANES.
2. EXISTING OVERHEAD SIGN STRUCTURE TO BE REMOVED DURING PRE-STAGE AND SIGN PANEL TEMPORARILY MOUNTED TO ROCKTON RD BRIDGE. THE EXISTING SIGN LUMINAIRES SHALL BE REMOVED AND REPLACED WITH NEW INDUCTION LUMINAIRES.
3. THE EXISTING SIGN CONTROLLER AND NEW INDUCTION LUMINAIRES SHALL BE RELOCATED TO THE TEMPORARY LOCATION OF THE SIGN ATTACHED TO THE ROCKTON ROAD BRIDGE DURING CONSTRUCTION OF THIS PROJECT.
4. CONTRACTOR TO INSPECT CONDITION OF CONTROLLER AND NEW INDUCTION LUMINAIRES PRIOR TO REMOVAL FROM EXISTING LOCATION, INSTALLATION ON TEMPORARY BRIDGE MOUNTS, REMOVAL FROM TEMPORARY LOCATIONS AND REINSTALLATION ON NEW SIGN STRUCTURE.
5. REFER TO ISTHA'S STANDARD H-10-00.

LEGEND:

- EXISTING UNIT DUCT
- - - PROPOSED UNIT DUCT
- ⊠ EXISTING LIGHT POLE TO REMAIN UNLESS NOTED OTHERWISE
- ⊠ EXISTING LIGHTING CONTROLLER
- PROPOSED HANDHOLE
- TEMPORARY LIGHT POLE
- TEMPORARY WOOD POLE
- ⊠ UNIT DUCT, 600V 2-1C NO.8, 1C NO.8 GROUND (XLP-TYPE USE) 2" DIA. CNC
- CONDUIT PUSHED, 4" DIA., PVC SCHEDULE 80 (PAID AS UNDERGROUND CONDUIT, PVC, 4" DIA.)



Rev. 1-9-12



USER NAME = USERNAME
 PLOT SCALE = 50,0000 / IN.
 PLOT DATE = 12/9/2011

DESIGNED - BLM
 DRAWN - JPW
 CHECKED - BLM
 DATE - 10/14/11

REVISED -
 REVISED -
 REVISED -
 REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

**TEMPORARY LIGHTING PLAN
 BRIDGE MOUNTED SIGN STRUCTURE STAGE 1 & WINTER SHUT DOWN**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90	(X2-1R)	WINNEBAGO	510	266
CONTRACT NO. 64C29				

ILLINOIS FED. AID PROJECT