

NAME

COMPANY

## NOTES

Detail I - With Bar Splicer or Couplers: Connect one (1) 1" x 7" x "W" steel P to the top layer of couplers with  $2 - \frac{5}{8}'' \phi$  bolts screwed to coupler at approximate Q of each barrier panel. Detail II - With Extended Reinforcement Bars: Connect one (1) 1" x 7" x "W" steel ft to the concrete slab or concrete wearing surface with 2-58"  $\phi$ Expansion Anchors or cast in place inserts

spaced between the top layer of reinforcement at approximate ∉ of each barrier panel. Cost of anchorage is included with Temporary Concrete Barrier. The 1" x 7" x "W" plate shall not be removed until stage II construction forms and all reinforcement bars are in place and the concrete is ready



STEEL RETAINER & 1" x 7" x "W" \* Required only with Detail II

OR STAGE CONSTRUCTION	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
470051	591	14BR-1	KENDALL	429	254
1470000 I			CONTRACT	NO. 6	6985
43 SHEETS		ILLINOIS FED. AI	D PROJECT		