

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 5"					
LOCATION			DISTANCE OF RUN (FOOT)	DESCRIPTION	LENGTH (FEET)
IL 16 IN LITCHFIELD					
EASTBOUND CENTERLINE					
STA 923+73.00	TO	STA 926+26.55	253.6	30' SKIP - 10' DASH, WHITE	63.4
STA 927+00.00	TO	STA 929+53.00	253.0	30' SKIP - 10' DASH, WHITE	63.3
WESTBOUND CENTERLINE					
STA 923+86.60	TO	STA 926+43.00	256.4	30' SKIP - 10' DASH, WHITE	64.1
STA 927+17.00	TO	STA 930+09.83	292.8	30' SKIP - 10' DASH, WHITE	73.2
TOTAL =			1,055.8		264.0

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B- LINE 24"				
LOCATION		DIRECTION	DESCRIPTION	LENGTH (FOOT)
IL 16, LITCHFIELD:				
IL 16/OLD 66	STA 923+83.00	N.B. RIGHT TURN LANE	STOP BAR, WHITE	18.5
IL 16/OLD 66	STA 923+86.60	W.B. THRU LANES & RIGHT TURN LANE	STOP BAR, WHITE	35.0
IL 16/OLD 66	STA 923+90.00	W.B. RIGHT TURN LANE	STOP BAR, WHITE	18.5
IL 16/SHERMAN ST	STA 925+90.00	E.B. RIGHT TURN LANE	STOP BAR, WHITE	18.0
IL 16/SHERMAN ST	STA 926+26.55	E.B. RIGHT THRU LANE	STOP BAR, WHITE	12.0
IL 16/SHERMAN ST	STA 926+31.77	E.B. RIGHT THRU & LEFT TURN LANE	STOP BAR, WHITE	24.2
IL 16/SHERMAN ST	STA 927+19.20	W.B. THRU LANES	STOP BAR, WHITE	18.5
IL 16/SHERMAN ST	STA 927+21.60	W.B. LEFT TURN LANE	STOP BAR, WHITE	11.5
IL 16/SHERMAN ST	STA 927+70.00	W.B. RIGHT TURN LANE	STOP BAR, WHITE	18.7
SHERMAN ST.	STA 10+49.40	S.B. THRU LANE	STOP BAR, WHITE	12.0
SHERMAN ST.	STA 10+45.00	S.B. RIGHT TURN LANE	STOP BAR, WHITE	18.5
SHERMAN ST.	STA 10+53.10	N.B. THRU LANE	STOP BAR, WHITE	12.0
SHERMAN ST.	STA 10+55.00	N.B. RIGHT TURN LANE	STOP BAR, WHITE	18.5
DOUGLAS ST.	STA 936+00.00	S.B. THRU LANE	STOP BAR, WHITE	14.0
DOUGLAS ST.	STA 936+15.00	N.B. THRU LANE	STOP BAR, WHITE	14.0
BROWN ST.	STA 939+15.52	S.B. THRU LANE	STOP BAR, WHITE	14.0
IL 16 MAINLINE	STA 940+67.67	BI-DIRECTIONAL & E.B. THRU LANES	RR XING, WHITE	23.3
IL 16 MAINLINE	STA 941+17.67	BI-DIRECTIONAL & E.B. THRU LANES	RR XING, WHITE	23.3
IL 16 MAINLINE	STA 941+67.67	BI-DIRECTIONAL & E.B. THRU LANES	STOP BAR, WHITE	23.3
N CLINTON ST.	STA 942+00.00	S.B. THRU LANE	STOP BAR, WHITE	11.0
N CLINTON ST.	STA 942+10.00	N.B. THRU LANE	STOP BAR, WHITE	11.0
IL 16 MAINLINE	STA 0+45.43	BI-DIRECTIONAL & W.B. THRU LANES	STOP BAR, WHITE	25.0
IL 16 MAINLINE	STA 0+89.18	BI-DIRECTIONAL & W.B. THRU LANES	RR XING, WHITE	25.0
IL 16 MAINLINE	STA 1+39.18	BI-DIRECTIONAL & W.B. THRU LANES	RR XING, WHITE	25.0
IL 16 MAINLINE	STA 1+80.00	BI-DIRECTIONAL & E.B. THRU LANES	RR XING, WHITE	25.0
IL 16 MAINLINE	STA 2+30.00	BI-DIRECTIONAL & E.B. THRU LANES	RR XING, WHITE	25.0
IL 16 MAINLINE	STA 2+80.00	BI-DIRECTIONAL & E.B. THRU LANES	STOP BAR, WHITE	25.0
IL 16 MAINLINE	STA 3+21.60	BI-DIRECTIONAL & W.B. THRU LANES	STOP BAR, WHITE	25.0
IL 16 MAINLINE	STA 3+71.60	BI-DIRECTIONAL & W.B. THRU LANES	RR XING, WHITE	25.0
IL 16 MAINLINE	STA 4+21.60	BI-DIRECTIONAL & W.B. THRU LANES	RR XING, WHITE	25.0
ADAMS ST.	STA 6+20.00	S.B. THRU LANE	STOP BAR, WHITE	13.0
ADAMS ST.	STA 6+20.00	N.B. THRU LANE	STOP BAR, WHITE	13.0
IL 16/JEFFERSON S	STA 8+85.50	E.B. LEFT TURN LANE	STOP BAR, WHITE	12.0
IL 16/JEFFERSON S	STA 9+08.00	E.B. THRU LANE	STOP BAR, WHITE	18.0
JEFFERSON ST.	43' LEFT OF IL 16 C.L.	S.B. THRU LANE	STOP BAR, WHITE	20.0
JEFFERSON ST.	44' RT. OF IL 16 C.L.	N.B. THRU LANE	STOP BAR, WHITE	15.0
IL 16/JEFFERSON S	STA 9+96.00	W.B. THRU LANE	STOP BAR, WHITE	14.0
IL 16/JEFFERSON S	STA 10+17.10	W.B. LEFT TURN LANE	STOP BAR, WHITE	12.0
MADISON ST.	STA 12+78.00	S.B. THRU LANE	STOP BAR, WHITE	13.0
MADISON ST.	STA 12+78.00	N.B. THRU LANE	STOP BAR, WHITE	15.0
IL 16/STATE ST.	STA 15+69.65	BI-DIRECTIONAL & E.B. THRU LANES	STOP BAR, WHITE	24.5
STATE ST.	STA 16+23.75	S.B. THRU LANE	STOP BAR, WHITE	35.5
STATE ST.	STA 16+23.75	N.B. THRU LANE	STOP BAR, WHITE	40.5
IL 16/STATE ST.	STA 16+74.57	BI-DIRECTIONAL & W.B. THRU LANES	STOP BAR, WHITE	24.5
MONROE ST.	STA 19+67.37	S.B. THRU LANE	STOP BAR, WHITE	19.0
MONROE ST.	STA 19+67.37	N.B. THRU LANE	STOP BAR, WHITE	15.0
IL 16 / IL 127 INTERSECTION:				STOP BAR, WHITE
IL 127	STA 348+10.00	S.B. RIGHT TURN LANE	STOP BAR, WHITE	18.0
IL 127	STA 348+60.00	S.B. LEFT TURN LANE	STOP BAR, WHITE	14.0
IL 16	STA 349+25.00	W.B. RIGHT TURN LANE	STOP BAR, WHITE	18.0
TOTAL =				948.8

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B, INLAID - LINE 6"					
LOCATION			DISTANCE OF RUN (FOOT)	DESCRIPTION	LENGTH (FOOT)
IL 16 IN LITCHFIELD:					
STA 923+88.75	TO	STA 924+78.87	90.12	WB LEFT TURN LANE LINE, WHITE	90.1
STA 924+78.87	TO	STA 925+53.70	74.83	EB LEFT TURN LANE (6' SKIP- 2' DASH), WHITE	18.7
STA 924+78.87	TO	STA 925+53.70	74.83	WB LEFT TURN LANE (6' SKIP- 2' DASH), WHITE	18.7
STA 925+53.70	TO	STA 926+26.55	72.85	EB LEFT TURN LANE LINE, WHITE	72.9
IL 16 AND SHERMANN ST					
STA 927+19.20	TO	STA 928+45.80	126.60	WB LEFT TURN LANE LINE, WHITE	126.6
STA 928+45.80	TO	STA 929+59.70	113.90	WB LEFT TURN LANE (6' SKIP- 2' DASH), WHITE	28.5
STA 929+59.70	TO	STA 933+70.98	411.28	EB MERGE LANE (6' SKIP- 2' DASH), WHITE	102.8
IL 16 AND DOUGLAS ST					
IL 16 AND BROWN ST					
IL 16 AND WASHINGTON ST					
STA 7+21.50	TO	STA 8+00.00	78.50	EB LEFT TURN LANE (6' SKIP- 2' DASH), WHITE	19.6
STA 8+00.00	TO	STA 9+08.00	108.00	EB LEFT TURN LANE LINE, WHITE	108.0
IL 16 AND JEFFERSON ST					
STA 9+96.00	TO	STA 11+00.00	104.00	WB LEFT TURN LANE LINE, WHITE	104.0
STA 11+00.00	TO	STA 11+80.00	80.00	WB LEFT TURN LANE (6' SKIP- 2' DASH), WHITE	20.0
IL 16 AND MADISON					
STA 14+00.00	TO	STA 14+92.50	92.50	E.B. LEFT TURN LANE (6' SKIP- 2' DASH), WHITE	23.1
STA 14+92.50	TO	STA 15+69.65	77.15	E.B. LEFT TURN LANE LINE, WHITE	77.2
IL 16 AND STATE ST					
STA 16+74.57	TO	STA 17+55.00	80.43	W.B. LEFT TURN LANE LINE, WHITE	80.4
STA 17+55.00	TO	STA 18+30.00	75.00	W.B. LEFT TURN LANE (6' SKIP- 2' DASH), WHITE	18.8
IL 16 AND MONROE ST					
IL 16 / IL 127 INTERSECTION:					
STA 343+22.40	TO	STA 345+68.50	246.10	EB LEFT TURN LANE (6' SKIP- 2' DASH), WHITE	61.5
STA 345+68.50	TO	STA 348+14.60	246.10	EB LEFT TURN LANE LINE, WHITE	246.1
STA 353+05.00	TO	STA 354+51.70	146.70	WB LEFT TURN LANE (6' SKIP- 2' DASH), WHITE	36.7
TOTAL =					3,302.8

-- (15, 21)RS-7, 22RS-4, 24RS-8
 --- 42, 325

FILE NAME =	USER NAME = sparkgw	DESIGNED - RTS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES OF QUANTITIES		F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
cr\pwork\pwork\sparkgw\d2222805\067	2067-sht-schedule.dgn	DRAWN - RTS	REVISED -		SCALE:	SHEET NO. 15 OF 18 SHEETS	STA.	TO STA.	MONTGOMERY	80	32
	PLOT SCALE = 1/8" = 100'	CHECKED -	REVISED -						CONTRACT NO. 72D67		
	PLOT DATE = Aug-25-2011 10:15:29AM	DATE - 04-26-11	REVISED -						ILLINOIS FED. AID PROJECT		