

PAINT PAVEMENT MARKING - LINE 5" SCHEDULE

LOCATION STATION TO STATION	DESCRIPTION	LENGTH (FT)	SPACING	LINE 5"	
				WHITE (FT)	YELLOW (FT)
FAP 325 (IL 16)					
STA. 18+62.00 TO STA. 135+28.00	SOLID (EDGE LINE LT)	11,666.0		11,446.0	
STA. 18+62.00 TO STA. 135+28.00	SKIP-DASH (CENTER)	11,666.0	10' @ 40'		2,917.0
STA. 18+62.00 TO STA. 135+28.00	SOLID (EDGE LINE RT)	11,666.0		11,616.0	
STA. 135+28.00 TO STA. 140+56.00	SOLID (EDGE LINE LT)	528.0		528.0	
STA. 135+28.00 TO STA. 140+56.00	SKIP-DASH (CENTER WEST BOUND)	528.0	10' @ 40'		132.0
STA. 135+28.00 TO STA. 140+56.00	SOLID (EAST BOUND NPZ)	528.0			528.0
STA. 135+28.00 TO STA. 140+56.00	SOLID (EDGE LINE RT)	528.0		473.0	
STA. 140+56.00 TO STA. 146+00.00	SOLID (EDGE LINE LT & RT)	544.0		1,088.0	
STA. 140+56.00 TO STA. 146+00.00	SKIP-DASH (CENTER)	544.0	10' @ 40'		136.0
STA. 146+00.00 TO STA. 152+85.00	SOLID (EDGE LINE LT & RT)	685.0		1,370.0	
STA. 146+00.00 TO STA. 152+85.00	SKIP-DASH (CENTER EAST BOUND)	685.0	10' @ 40'		172.0
STA. 146+00.00 TO STA. 152+85.00	SOLID (WEST BOUND NPZ)	685.0			685.0
STA. 152+85.00 TO STA. 167+00.00	SOLID (EDGE LINE LT & RT)	1,415.0		2,830.0	
STA. 152+85.00 TO STA. 167+00.00	SKIP-DASH (CENTER)	1,415.0	10' @ 40'		354.0
STA. 167+00.00 TO STA. 177+60.00	SOLID (EDGE LINE LT & RT)	1,060.0		2,120.0	
STA. 167+00.00 TO STA. 177+60.00	SKIP-DASH (CENTER WEST BOUND)	1,060.0	10' @ 40'		265.0
STA. 167+00.00 TO STA. 177+60.00	SOLID (EAST BOUND NPZ)	1,060.0			1,060.0
STA. 177+60.00 TO STA. 182+80.00	SOLID (EDGE LINE LT & RT)	520.0		1,040.0	
STA. 177+60.00 TO STA. 182+80.00	SOLID (WEST & EAST BOUND NPZ)	520.0			1,040.0
STA. 182+80.00 TO STA. 193+45.00	SOLID (EDGE LINE LT)	1,065.0		1,005.0	
STA. 182+80.00 TO STA. 193+45.00	SOLID (WEST BOUND NPZ)	1,065.0			1,065.0
STA. 182+80.00 TO STA. 193+45.00	SKIP-DASH (CENTER EAST BOUND)	1,065.0	10' @ 40'		267.0
STA. 182+80.00 TO STA. 193+45.00	SOLID (EDGE LINE RT)	1,065.0		995.0	
STA. 193+45.00 TO STA. 204+00.00	SOLID (EDGE LINE LT)	1,055.0		1,055.0	
STA. 193+45.00 TO STA. 204+00.00	SKIP-DASH (CENTER WEST BOUND)	1,055.0	10' @ 40'		264.0
STA. 193+45.00 TO STA. 204+00.00	SOLID (EAST BOUND NPZ)	1,055.0			1,055.0
STA. 193+45.00 TO STA. 204+00.00	SOLID (EDGE LINE RT)	1,055.0		985.0	
STA. 204+00.00 TO STA. 214+48.00	SOLID (EDGE LINE LT & RT)	1,048.0		2,096.0	
STA. 204+00.00 TO STA. 214+48.00	SOLID (WEST BOUND NPZ)	1,048.0			1,048.0
STA. 204+00.00 TO STA. 214+48.00	SKIP-DASH (CENTER EAST BOUND)	1,048.0	10' @ 40'		262.0
STA. 214+48.00 TO STA. 219+85.00	SOLID (EDGE LINE LT & RT)	537.0		1,074.0	
STA. 214+48.00 TO STA. 219+85.00	SOLID (WEST & EAST BOUND NPZ)	537.0			1,074.0
STA. 219+85.00 TO STA. 225+13.00	SOLID (EDGE LINE LT & RT)	528.0		1,056.0	
STA. 219+85.00 TO STA. 225+13.00	SKIP-DASH (CENTER WEST BOUND)	528.0	10' @ 40'		132.0
STA. 219+85.00 TO STA. 225+13.00	SOLID (EAST BOUND NPZ)	528.0			528.0
STA. 225+13.00 TO STA. 235+65.00	SOLID (EDGE LINE LT & RT)	1,052.0		2,104.0	
STA. 225+13.00 TO STA. 235+65.00	SOLID (WEST BOUND NPZ)	1,052.0			1,052.0
STA. 225+13.00 TO STA. 235+65.00	SKIP-DASH (CENTER EAST BOUND)	1,052.0	10' @ 40'		263.0
STA. 235+65.00 TO STA. 245+00.00 *	SOLID (EDGE LINE LT & RT)	935.0		1,900.0	
STA. 235+65.00 TO STA. 245+00.00	SKIP-DASH (CENTER WEST BOUND)	935.0	10' @ 40'		234.0
STA. 235+65.00 TO STA. 245+00.00	SOLID (EAST BOUND NPZ)	935.0			935.0
SUB-TOTAL				44,781.0	15,468.0
TOTAL				60,249.0	

SHOULDER RUMBLE STRIP, 8 INCH SCHEDULE

LOCATION STATION TO STATION	LENGTH (FT)
FAP 325 (IL 16)	
LEFT	
STA 50+95.44 TO STA 64+70.00	1,374.5
STA 66+37.00 TO STA 72+50.00	613.0
RIGHT	
STA 50+95.44 TO STA 72+50.00	2,154.5
TOTAL	
4,142.0	

NOTE: QUANTITIES FOR TEMPORARY PAVEMENT MARKING-LINE 5" ARE THE SAME AS PAINT PAVEMENT MARKING-LINE 5"

*NOTE: EDGE LINE QUANTITIES INCLUDE EDGE LINE FOR RADIUS RETURNS ALONG DORCHESTER RD. AND SPANISH NEEDLE RD.