

	US-A-1	7-1-10							
	FILE NAME =	USER NAME =	DESIGNED - ESW	REVISED - 4-27-11	STATE OF ILLINOIS	OVERHEAD SIGN STRUCTURES -			
			CHECKED - JWS	REVISED -					
		PLOT SCALE =	DRAWN - PDB	REVISED -	DEPARTMENT OF TRANSPORTATION	ELEVATION – ALUMINUM TRUSS &			
1		PLOT DATE =	CHECKED - BRM	REVISED -		SHEET NO. 19 OF 49 SHEE			

00- 4-

## GENERAL NOTES

DESIGN: AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires and Traffic Signals. ("AASHTO Specifications")

CONSTRUCTION: Current (at time of letting) Illinois Department of Transportation Standard Specifications for Road and Bridge Construction, Supplemental Specifications and Special Provisions. ("Standard Specifications")

LOADING: 90 M.P.H. WIND VELOCITY

WALKWAY LOADING: Dead load plus 500 lbs. concentrated live load.

DESIGN STRESSES:

Field Units f'c = 3,500 p.s.i.

fy = 60,000 p.s.i. (reinforcement)

WELDING: All welds to be continuous unless otherwise shown. All welding to be done in accordance with current AWS D1.1 and D1.2 Structural Welding Codes (Steel and Aluminum) and the Standard Specificiations.

MATERIALS: Aluminum Alloys as shown throughout plans. All Structural Steel Pipe shall be ASTM A53 Grade B or A500 Grade B or C. If A500 pipe is substituted for A53, then the outside diameter shall be as detailed and wall thickness greater than or equal to A53. All Structural Steel Plates and Shapes shall conform to AASHTO M270 Gr. 36, Gr. 50 or Gr. 50W\*. Stainless steel for shims, sleeves and handhole covers shall be ASTM A240, Type 302 or 304, or another alloy suitable for exterior exposure and acceptable to the Engineer. The steel pipe and stiffening ribs at the base plate for the column shall have a minimum longitudinal Charpy V-Notch (CVN) energy of 15 lb.-ft. at 40° F. (Zone 2) before galvanizing.

FASTENERS FOR ALUMINUM TRUSSES: All bolts noted as "high strength" must satisfy the requirements of AASHTO M164 (ASTM A325), or approved alternate, and must have matching lock nuts. Threaded studs for splices (if Members interfere) must satisfy the requirements of ASTM A449, ASTM A193, Grade B7, or approved alternate, and must have matching lock nuts. Bolts and lock nuts not required to be high strength must satisfy the requirements of ASTM A307. All bolts and lock nuts must be hot dip galvanized per AASHTO M232. The lock nuts must have nylon or steel inserts. A stainless steel flat washer conforming to ASTM A240 Type 302 or 304, is required under both head and nut or under both nuts where threaded studs are used. High strength bolt installation shall conform to Article 505.04 (f) (2)d of the IDOT Standard Specifications for Road and Bridge Construction. Rotational capacity ("ROCAP") testing of bolts will not be required.

U-BOLTS AND EYEBOLTS: U-Bolts and Eyebolts must be produced from ASTM A276 Type 304, 304L, 316 or 316L, Condition A, cold finished stainless steel, or an equivalent material acceptable to the Engineer. All nuts for U-Bolts and Eyebolts must be lock nuts equivalent to ASTM A307 with nylon or steel inserts and hot dip galvanized per AASHTO M232. A stainless steel flat washer conforming to ASTM A240, Type 302 or 304, is required under each U-Bolt and Evebolt lock nut.

GALVANIZING: All Steel Grating, Plates, Shapes and Pipe shall be Hot Dip Galvanized after fabrication in accordance with AASHTO M111. Painting is not permitted.

ANCHOR RODS: Shall conform to AASHTO M314 Gr. 36, 55 or 105 with a minimum Charpy V-Notch (CVN) energy of 15 lb.-ft. at 40° F.

CONCRETE SURFACES: All concrete surfaces above an elevation 6" below the lowest final ground line at each foundation shall be cleaned and coated with Bridge Seat Sealer in accordance with the Standard Specifications.

REINFORCEMENT BARS: Reinforcement Bars designated (E) shall be epoxy coated in accordance with the Standard Specifications.

FOUNDATIONS: The contract unit price for Concrete Foundations and Drilled Shaft Concrete Foundations shall include reinforcement bars complete in place.

## TOTAL BILL OF MATERIAL

ITEM	UNIT	TOTAL
IFRHEAD SIGN STRUCTURE SPAN TYPE I-A	Foot	413'-0"
FRHEAD SIGN STRUCTURE SPAN TYPE II-A	Foot	-15 -0
FRHEAD SIGN STRUCTURE SPAN TYPE III-A	Foot	
	Foot	273'-6"
ERHEAD SIGN STRUCTURE WALKWAY TYPE A		
MONETE TOORDATIONS	Cu. Yds.	
RILLED SHAFT CONCRETE FOUNDATIONS	Cu. Yds.	130.8

					-		
RES – GENERAL PLAN &	F.A.I RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
RUSS & STEEL SUPPORTS	57/70	(25-3,4)R	EFFINGHAM	1098	261		
NOSS & STELL SULLOUIS		CONTRACT NO. 74299					
49 SHEETS		ILLINOIS FED. AID PROJECT					
· · · · · · · · · · · · · · · · · · ·							