SUMMARY OF QUANTITIES

				TOTAL QUANTITY
SI	CODE NO.	PAY ITEM DESCRIPTION	UNIT	0044
	20400800	FURNISHED EXCAVATION	475	
	25000210	SEEDING, CLASS 2A	0.50	
	25100115	MULCH, METHOD 2	0.50	
	28000400	PERIMETER EROSION BARRIER	FOOT	464
	67100100	MOBILIZATION	1	
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	1	
	X4404000	PARKING LOT PAVEMENT REMOVAL	917	
	Z0007601	BUILDING REMOVAL NO. 1 L SUM		1
	Z0013300	CONCRETE REMOVAL (SPECIAL)	115	
	Z0022800	FENCE REMOVAL FOOT		144
	Z0049901	1 REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO. 1 L SUM		1
				,
		· · · · · · · · · · · · · · · · · · ·		

SCHEDULES

EROSION	EROSION CONTROL SCHEDULE				
	PROPERTY	PERIMETER			
PARCEL NO.	PERIMETER	EROSION			
	(FOOT)	BARRIER (FOOT)			
8818100, 8826275	464	464			
	TOTALS	464			

SEEDING AND MULCHING SCHEDULE				
	SEEDING,	MULCH, METHOD		
PARCEL NO.	CLASS 2	2 AREA		
	AREA (ACRES)	(ACRES)		
8818100, 8826275	0.31	0.31		
TOTALS	0.31	0.31		
ROUNDED TOTALS	0.50	0.50		

	REMOVAL SCHEDULE			
PARCEL NO.	PARKING LOT PAVEMENT REMOVAL (SQ YD)	CONCRETE REMOVAL (SPECIAL) (SQYD) ¹	FENCE REMOVAL (FOOT)	
8818100, 8826275	917	115	144	
TOTALS	917	115	- 144	

NOTE: 1. ASSUME 12" THICKNESS.

* DENOTES SPECIALTY ITEM

FILE NAME =	USER NAME = pumperno	DESIGNED OP	REVISED -			F.A.U. SECTION	COUNTY TOTAL SHEET
D8TRI-76F3Ø-sht-S0Q-Ø1.dgn		DRAWN OP	REVISED -	STATE OF ILLINOIS	SUMMARY AND SCHEDULES OF QUANTITIES	RTE. SECTION	ST CLAIR 6 3
	PLOT SCALE = 1.0000 '/ in.	CHECKED DBM	REVISED -	DEPARTMENT OF TRANSPORTATION		3214 02-1-12UM	CONTRACT NO. 76F30
	PLOT DATE = 11/30/2011	DATE 11-30-11	REVISED -		SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.	FED. ROAD DIST. NO. ILLINOIS FED.	AID PROJECT

	FURNISHED
LOCATION	CUYD
PARKING LOT	
PAVEMENT	
REMOVED ¹	459
CONCRETE	· ·
REMOVAL (SPECIAL)	
REMOVED ²	13
TOTALS	472
ROUNDED TOTALS	475

NOTE:

1. ASSUME 6" PARKING LOT PAVEMENT THICKNESS AND 12" SUBGRADE.

2. ASSUME 12" THICKNESS FOR CONCRETE REMOVAL (SPECIAL).