

COMB CONC CURB AND GUTTER (SEE PLANS FOR TYPE) -INSIDE FACE OF WALL-11/2" CL TYP. PLACE #4 BARS 12" CTRS.IN BOTH DIRECTIONS IN 41/2" 7" 14" WALLS AND IN TOP OF BOTTOM 1" Ø GALV. IRON STEPS ** SLAB. - 11/2" CL. SPACED 12" TO 18" C-C. USE WHEN INLET IS OVER ELEVATION 4' DEEP.

DESIGN PIPE "D"

DEGIGIT	DIA	
Α	18"&LESS	2'~6''
В	21"&24"	3'-0''
С	27"&30"	3′-7′′
D	33"&36"	4'-2"
E	42"	4'-9"
F	48"	5′-0′′
G	54"	6′-1′′

NOTES:

FILE NAME =

\D978182-sht-details.dgn

PROVIDE 11/2" CLEARANCE TYP. ALL REINFORCEMENT UNLESS OTHERWISE SPECIFIED.


CLASS SI CONCRETE SHALL BE USED THROUGHOUT. SET FACE OF INLET 1" BEHIND FACE OF CURB. DEPRESS GUTTER FLOWLINE AT INLET $2^{1}\!/_{2}$ " BELOW NORMAL GUTTER FLOWLINE. CONSTRUCT TRANSITION IN FLOWLINE IN 10 FEET EACH SIDE OF INLET. PIPES TO BE CONNECTED TO INLET AS SHOWN ON STORM SEWER LAYOUT.

INLETS WILL BE PAID FOR AT THE CONTRACT UNIT PRICE EACH FOR INLET, SPECIAL, NO. 1 WHICH PRICE SHALL INCLUDE THE CAST IRON FRAME, SPECIAL, TYPE 1 WITH TYPE 1 CLOSED LID, THE REINFORCEMENT BARS, METAL STEPS AND JOINT FILLER.

**THE GALVONIZED IRON STEPS AS DETAILED HEREON ARE TYPICAL. STEPS OF OTHER DESIGN AND MATERIAL THAT WILL CONFORM TO THE MINIMUM REQUIREMENTS OF THE STEPS SHOWN. MAY BE USED WHEN APPROVED BY THE ENGINEER.

IF THE INLET IS NOT CAST IN PLACE THEN THE INLET SHALL BE PRODUCED ACCORDING TO THE DEPARTMENT'S CURRENT POLICY MEMORANDUM, "QUALITY CONTROL/QUALITY ASSURANCE PROGRAM FOR PRECAST CONCRETE PRODUCTS".

LOT SCALE = 50.0000 '/ IN



SECTION

NOTE TO DESIGNER:

DESIGNED

DRAWN

CHECKED

WHEN USING THIS STANDARD THE DESIGNER SHOULD ALSO CHECK BDE SPECIAL PROVISION 419 "PRECAST CONCRETE PRODUCTS".

REVISED

REVISED

REVISED


REVISED




STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION**

DETAILS OF CONCRETE COLLAR

PIPE TO PIPE



SIDE VIEW




TABULATION DIAMETER CL SI CONC OF PIPE CU YDS EST

THE CONCRETE COLLAR SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE PER CUBIC YARD FOR CONCRETE COLLAR, AS SHOWN ON THE PLANS, WHICH PRICE SHALL INCLUDE THE REMOVAL OF SUCH PORTIONS THE EXISTING HEADWALLS AS MAY BE REQUIRED.

CLASS SI CONCRETE SHALL BE USED THROUGHOUT.

MOUNTABLE CURB DETAIL



DRAWN 1-10-9 REVISED 3-26-08 STD. 9-87 R

COUNTY TOTAL SHEETS NO. SECTION * (X1-6-2)HBK-2, HB-1,2; (1X-1)R-1 WILLIAMSON 968 717 * F.A.I. 57 AND F.A.P. 331 CONTRACT NO. 78182 ILLINOIS FED. AID PROJECT

DISTRICT DETAILS

SHEET NO. OF SHEETS STA.

I-57 AND IL ROUTE 13