	20201200 REM & DISP OF UNSUITABLE MATERIAL (CU YD) (NOTE 1)	20200100 EARTH EXCAVATION (CU YD)	EXCAVATION TO BE USED IN EMBANKMENT (ADJ 15% FOR SHRINKAGE) (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+ OR SHORTAGE (-) (CU YD)	
LOCATION						
15TH AVENUE - SOUTH LIMITS TO BRIDGE	10	84	72	1	+71	
15TH AVENUE - BRIDGE TO NORTH LIMITS	45	71	61	42	+19	
TOTAL	55	155	133	43	0	

NOTE 1: INCLUDES TOPSOIL STRIPPING.

NOTE 2: 50 CY OF REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL WAS ASSUMED FOR UNDERCUTTING. TOTAL QUANTITY OF REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL IS 105 CY.

AGGREGATE SUBGRADE [MPROVEMENT (CU YD) HAS BEEN PROVIDED FOR USE AT THE LOCATIONS INDICATED FOR SOILS THAT TEND TO BE UNSTABLE AND/OR UNSUITABLE. THE ACTUAL NEED FOR REMOVAL AND REPLACEMENT WITH AGGREGATE SUBGRADE IMPROVEMENT (CU YD) WILL BE DETERMINED IN THE FIELD AT THE TIME OF CONSTRUCTION BY THE GEOTECHNICAL ENGINEER. ALL POTENTIALLY UNSTABLE SOILS SHOULD BE TESTED WITH A STATIC CONE AND/OR DYNAMIC CONE PENETROMETER AND TREATED IN ACCORDANCE WITH ARTICLE 301.04 (04/01/2016) OF THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION AND THE CURRENT IDOT SUBGRADE STABILITY MANUAL. IF UNSTABLE AND/OR UNSUITABLE SOILS ARE NOT ENCOUNTERED. THEN THE QUANTITY SHALL BE DEDUCTED AND NO ADDITIONAL COMPENSATION WILL BE DUE TO THE CONTRACTOR.

-∧

A REVISED EARTHWORK TABLE GENERAL NOTE PER [DOT GEOTECHNICAL UNIT RECENT MODIFICATIONS.

FILE NAME =	USER NAME = 0000min	DESIGNED - CEC	REVISED - 1/3/17	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	15TH AVENUE OVER SILVER CREEK	MUN	SECTION	COUNTY	TOTAL SHE
c:\transystems\pwllocal\transyscorp-pwl\ce	comin\d0229413\0023_SCHEDULE.dgn	DRAWN - CEC	REVISED -			1090	10-00117-00-BR	COOK 48	SHEETS NU.
	PLOT SCALE = 2.0000 '/ in.	CHECKED - DWB	REVISED -		SCHEDULE OF QUANTITIES EARTHWORK TABLE	1090	10-00111-00-04		T NO 61034
Ţ	PLOT DATE = 1/3/2017	DATE 10/17/2016	REVISED -		SCALE: NONE SHEET NO. 7 OF 48 SHEETS STA. TO STA.	ILLINOIS FED.			