CONTRACT NO. 66363 Sheet 16 of 20

#### **NOTES**

Bar splicer assemblies shall be of an approved type and shall develop in tension at least 125 percent of the yield strength of the lapped reinforcement bars.

Splicer rods shall be of minimum 60 ksi yield strength, threaded or coiled full length. All reinforcement bars shall be lapped and tied to the splicer rods or dowel bars. Bar splicer assemblies shall be epoxy coated according to the requirements for

reinforcement bars. Other systems of similar design may be submitted to the Engineer for approval. Approval shall be based on certified test results from an approved testing laboratory that the proposed bar splicer assembly satisfies the following requirements:

Minimum Capacity = 1.25 x fy x  $A_t$ 


(Lension iii kips) Minimum \*\*Pull-out Strength = 1.25 x  $fs_{allow}$  x  $A_t$ 

Where fy = Yield strength of lapped reinforcement bars in ksi.

fs<sub>allow</sub>= Allowable tensile stress in lapped reinforcement bars in ksi (Service Load)  $A_t$  = Tensile stress area of lapped reinforcement bars. \* = 28 day concrete

-							
BAR SPLICER ASSEMBLIES							
		Strength Requirements					
	Splicer Rod or Dowel Bar Length		Min. Pull-Out Strength kips - tension				
#4	1'-8''	14.7	<b>5.</b> 9				
#5	2'-0''	23.0	9.2				
#6	2'-7''	33.1	13.3				
#7	3′-5″	45.1	18.0				
#8	4'-6''	58.9	23.6				
#9	5′-9″	75.0	30.0				
#10	7'-3''	95.0	38.0				
#11	9'-0''	117.4	46.8				

Bar splicer assembles shall be according to Section 508 of the Standard Specifications, except as noted. The furnishing and installation of bar splicer assemblies will be measured and paid for at the contract unit price each for "BAR SPLICERS."



### STANDARD


Bar Size	No. Assemblies Required	Location
#5	345	Deck
#6	16	Diaphragm
#7	20	Abutments
#8	10	Pier Cap
#5	26	Pier Wall

# BAR SPLICER ASSEMBLY DETAILS

IL. RTE. 9 OVER WALL TOWN DRAINAGE DITCH FAP ROUTE 697 - SECTION 17BR-1 FORD COUNTY STATION 993+80.38 S.N. 027-0094

FILE: SPLICE.DG

4440 ASH GROVE SPRINGFIELD, IL. 62707 (217) 793-8600 casinc@famvid.com OZYURT AND STONE, INC.



#### BAR SPLICER ASSEMBLY ALTERNATIVES

The diameter of this part is

equal or larger than the

diameter of bar spliced.

\*\* Heavy Hex Nuts conforming to ASTM A 563, Grade C, D or DH may be used.

WELDED SECTIONS

ROLLED THREAD DOWEL BAR

Wire Connector

\*\* ONE PIECE


The diameter of this part

of the bar spliced.

is the same as the diameter

### INSTALLATION AND SETTING METHODS


"A": Set bar splicer assembly by means of a template bolt. "B" : Set bar splicer assembly by nailing to wood forms or cementing to steel forms. (E): Indicates epoxy coating.



# FOR INTEGRAL OR SEMI-INTEGRAL ABUTMENTS

	Ваг	S	plicer	fo	r #5	5 bar		
Min.	Capacity	=	23.0	kip	s -	tensi	on	
Min.	Pull-out	St	rength	=	9.2	kips	-	tensio
No.	Required	=	64					

,	······································			
DESIGNED	P.S.L.			
CHECKED	A.R.K. & F.J.S.			
DRAWN	K.T.R.			
CHECKED	P.S.L. & A.R.K.			
BSD-1	9-01-03			



	Bar	Splice	r fo	r #5	5 bar		
Min.	Capacity	= 23.0	) kip	s -	tensi	on	
Min.	Pull-out	Streng	th =	9.2	kips	-	tension
No.	Required	_					

JOB NO.: 0306.2 CONSULTING ENGINEERS

STANDARDS\GENERAL\BPLAN.DGN 1:1 7-17-98