January 11, 2005

SUBJECT: FAP Route 836

Project BRF-0830(024) Section (119 BR)BR Champaign County

Item No. 56, January 21, 2005 Letting

Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised sheet 4 of the Plans.
- Revised page 2 of the Schedule of Prices.
- Revised page ii of the Table of Contents to the Special Provisions.
- 4. Added page 93 to the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Michael L. Hine Engineer of Design and Environment

By: Ted B. Walschleger, P. E.

Tete Jalushyou A.E.

Engineer of Project Management

cc: J. E. Crowe; Roger Driskell; R. E. Anderson; Jim White; Design & Environment File

TBW:MS:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF PRICES CONTRACT 70355 NUMBER -

State Job # - C-95-011-04
PPS NBR - 5-52110-0000
County Name - CHAMPAIGN- -

Project Number BRF-0836/024/000 Route FAP 836

Code - 19 - - District - 5 - -

Section Number - (119BR)BR

ltem Number	Pay Item Description	Unit of Measure	Quantity	х	Unit Price	=	Total Price
28000300	TEMP DITCH CHECKS	EACH	12.000				
28000400	PERIMETER EROS BAR	FOOT	938.000				
28100107	STONE RIPRAP CL A4	SQ YD	1,097.000				
28200100	FILTER FAB FOR RIPRAP	SQ YD	1,097.000				
40600100	BIT MATLS PR CT	GALLON	24.000				
40600300	AGG PR CT	TON	1.000				
* DELETED							
* 42001400	BR APPROACH PAVT SPL	SQ YD	240.000				
42001430	BR APPR PVT CON (FLX)	SQ YD	48.000				
44000006	BIT SURF REM 1 1/2	SQ YD	200.000				
44000100	PAVEMENT REM	SQ YD	352.000				
50100100	REM EXIST STRUCT	EACH	1.000				
50105210	REM EXIST CULVERTS	FOOT	83.000				
50200100	STRUCTURE EXCAVATION	CU YD	528.000				
50300225	CONC STRUCT	CU YD	225.000				
50300255	CONC SUP-STR	CU YD	490.000				
		* REVI	SED : JANUARY 7, 2005				

SUPERPAVE BITUMINOUS CONCRETE MIXTURES (BDE)	43
TEMPORARY EROSION CONTROL (BDE)	49
TRAFFIC BARRIER TERMINALS (BDE)	50
TRAFFIC CONTROL DEFICIENCY DEDUCTION (BDE)	51
TRUCK BED RELEASE AGENT (BDE)	52
WEIGHT CONTROL DEFICIENCY DEDUCTION	52
WORK ZONE TRAFFIC CONTROL DEVICES (BDE)	
REMOVE AND RE-ERECT STEEL PLATE BEAM GUARDRAIL AND TRAFFIC BARRIER TEF	RMINALS
(BDE)	54
SEEDING AND SODDING (BDE)	55
SELF-CONSOLIDATING CONCRETE FOR PRECAST PRODUCTS (BDE)	57
STONE FOR EROSION PROTECTION, SEDIMENT CONTROL, AND ROCKFILL (BDE)	59
STEEL COST ADJUSTMENT (BDE)	61
UNDERWATER STRUCTURE EXCAVATION PROTECTION	65
FABRIC REINFORCED ELASTOMERIC MAT	65
DIAMOND GRINDING AND SURFACE TESTING BRIDGE SECTIONS	66
PRECAST PRESTRESSED CONCRETE I-BEAMS AND BULB-T BEAMS BURSTING STEEL	DETAILS
STORM WATER POLLUTION PREVENTION PLAN	85
BRIDGE APPROACH PAVEMENT (SPECIAL)	93

BRIDGE APPROACH PAVEMENT (SPECIAL)

Description. This work shall consist of constructing bridge approach pavements ¼" (6 mm) thicker than shown on Highway Standard 420401. The cover over the top layer of reinforcement shall be increased by ¼" (6 mm) to comply with the requirements of the special provision for DIAMOND GRINDING AND SURFACE TESTING BRIDGE SECTIONS.

Method of Measurement. Bridge Approach Pavement (Special) shall be measured in square yards (square meters). The length will be measured along the centerline of the surface of the approach pavement. The width will be the width of the pavement as shown on the plans. In computing the area for Bridge Approach Pavement (Special), a deduction will be made for the area displaced by the inlet.

Basis of Payment. Bridge Approach Pavement (Special) will be paid for at the contract unit price per square yard (square meter) for BRIDGE APPROACH PAVEMENT (SPECIAL), and no other compensation shall be allowed.