## LIST OF STANDARDS

STANDARD NO.

DESCRIPTION

000001-04 STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS
001006 DECIMAL OF AN INCH AND A FOOT
701101-01 OFF-ROAD OPERATIONS, MULTILANE, 4.5M (15') TO 600 mm (24") FROM PAVEMENT EDGE
701106-01 OFF-ROAD OPERATIONS, MULTILANE, MORE THAN 4.5 M (15') AWAY
702001-05 TRAFFIC CONTROL DEVICES

## **GENERAL NOTES**

G.N.-100 ENGLISH UNITS OF MEASUREMENT SHALL GOVERN OVER AND SUPERSEDE ANY METRIC UNITS SHOWN IN THIS CONTRACT. WHERE INCLUDED, METRIC UNITS ARE FOR INFORMATION ONLY.

G.N. - 105.07
EXISTING STATE-OWNED AND MAINTAINED UTILITY LINES ARE SHOWN ON THE PLANS TO INDICATE THEIR PRESENCE AND APPROXIMATE LOCATION. THE CONTRACTOR SHALL NOTIFY THE DISTRICT OPERATIONS ENGINEER TWO WEEKS PRIOR TO COMMENCING ANY EXCAVATION IN THE VICINITY OF THESE LINES. THE STATE WILL THEN LOCATE AND MARK THE HORIZONTAL LOCATIONS OF THE LINES AND PROVIDE ANY AVAILABLE INFORMATION AS TO THEIR DEPTH. SHOULD ANY OF THE LINES BE DAMAGED BY THE CONTRACTOR'S OPERATION, THE CONTRACTOR SHALL REPAIR THEM TO THE SATISFACTION OF THE ENGINEER AND AT NO COST TO THE STATE.

ALSO THERE MAY BE UTILITIES PRESENT WHICH WERE INSTALLED BY THE STATE BUT ARE MAINTAINED BY OTHERS (CITY, TOWN, ETC.) THE APPROXIMATE LOCATIONS OF THESE LINES ARE ALSO SHOWN ON THE PLANS ALONG WITH THE NAME OF THE MAINTAINING AGENCY. THE CONTRACTOR SHALL COORDINATE THE LOCATING OF THESE LINES WITH THE LOCAL AGENCY PRIOR TO COMMENCING ANY EXCAVATION OR BORING IN THEIR VICINITY. SHOULD THESE LINES BE DAMAGED BY THE CONTRACTOR'S OPERATIONS, THE CONTRACTOR SHALL REPAIR THEM TO THE SATISFACTION OF, AND AT NO COST TO, THE LOCAL AGENCY AND THE STATE.

G.N. -107.31

UTILITY LINES WERE PLOTTED FROM INFORMATION FURNISHED BY THE VARIOUS UTILITY COMPANIES INVOLVED AND THEIR ACCURACY SHOULD BE CONSIDERED APPROXIMATE ONLY.

J.U.L.I.E. - JOINT UTILITY LOCATION INFORMATION FOR EXCAVATORS SYSTEM (800) 892-0123.
THE FOLLOWING UTILITY OWNERS MARKED WITH AN '\*' BELONG TO J.U.L.I.E.:

Mr. Dale Shaver

\* Mediacom LLC
903 East Howard Street
Pontiac, II 61764

Mr. Gregg Hazel \* Village of Rantoul 200 W. Grove Ave. Rantoul, II 61866

Mr. Scott Stogsdill
\* Nicor Gas
Engineering Department
1844 Ferry Rd.
Naperville, II 60563-4028

Mrs. Jackie Roelfs \* Verizon North, Inc ILL0301 212 E Grove St. Rantoul, IL 61866

Mr. Michael Anderson
• Eastern Illini Electric Cooperative
330 West Ottawa
PO Box 96
Paxton, II 60957-0096

F.A.I. SECTION COUNTY TOTAL SHEETS NO.

57 • CHAMPAIGN 10 2

CONTRACT NO. 70441 \* D-5 CONTRACT MAINT 2005-1

## **INDEX OF SHEETS**

SHEET NO.	<u>I TEM</u>
1	COVER SHEET
2	INDEX OF SHEETS
2	LIST OF STANDARDS
2	GENERAL NOTES
3	SUMMARY OF QUANTITIES
4	F. A. I. 57 & US 136 PLAN SHEET
5	WIRING DIAGRAMS & SYMBOL LEGEND
6	DETAIL OF NIGHTTIME LIGHTING INSPECTION
7	DETAIL FOR RAMP WORK AREAS
8	DETAIL OF LIGHT POLE FOUNDATIONS
9	DETAIL FOR POLE STANDARDS
10	DETAIL FOR CONTROL INSTALLATION CB-RCS-6

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION DISTRICT FIVE

REVIEWED BY:

DISTRICT ENGINEER OF PROGRAM DEVELOPMENT

DATE:

10/26/04

EXAMINED BY:

Sold A. Carelius of DISTRICT ENGINEER OF PROJECT IMPLEMENTATION

DISTRICT ENGINEER OF BUREAU OF OPERATIONS