

SUMMARY OF QUANTITIES						80% FED. 20% STATE		
CODE NO.	ITEM	UNIT	TOTAL	CONSTRUCTION TYPE CODE				
				URBAN	ROAD	BRIDGE	100% VILLAGE OF WHEELING	
				0004	0011	0043		
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	332	332				
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	151	151				
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	750	750				
20300100	CHANNEL EXCAVATION	CU YD	210		210			
20200100	EARTH EXCAVATION	CU YD	2,225	2,225				
Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	144	144				
20700220	POROUS GRANULAR EMBANKMENT	CU YD	2,610		2,610			
20800150	TRENCH BACKFILL	CU YD	1,040	340			700	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	3,010	3,010				
25000310	SEEDING, CLASS 4	ACRE	0.06	0.06				
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	168	168				
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	168	168				
25100630	EROSION CONTROL BLANKET	SQ YD	9,320	9,320				
25200110	SODDING, SALT TOLERANT	SQ YD	2,788	2,788				
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1,865	1,865				
28000400	PERIMETER EROSION BARRIER	FOOT	1,631	1,631				
28000510	INLET FILTERS	EACH	20	20				
28100107	STONE RIPRAP, CLASS A4	SQ YD	330		330			
28200200	FILTER FABRIC	SQ YD	420		420			
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	165	165				
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3,115	3,115				
40600300	AGGREGATE (PRIME COAT)	TON	80	80				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	51	51				
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	284	284				
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	155	25			130	
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	330	330				
40701926	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 12 1/4"	SQ YD	3,340	3,340				
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	40	40				
42000300	PORTLAND CEMENT CONCRETE PAVEMENT 8"	SQ YD	360	360				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	5,240	5,240				
42400410	PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH	SQ FT	1,416	1,416				
42400800	DETECTABLE WARNINGS	SQ FT	224	224				
44000100	PAVEMENT REMOVAL	SQ YD	2,335	2,335				
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	2,465	2,465				

80% STATE/20% WHEELING - 003B (BIKE PATH)

* = SPECIALTY ITEM

SUMMARY OF QUANTITIES						80% FED. 20% STATE		
CODE NO.	ITEM	UNIT	TOTAL	CONSTRUCTION TYPE CODE				
				URBAN	ROAD	BRIDGE	100% VILLAGE OF WHEELING	
				0004	0011	0043		
Z0004544	HOT-MIX ASPHALT DRIVEWAY PAVEMENT REMOVAL	SQ YD	22	22				
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	552	552				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1,990	1,990				
44000600	SIDEWALK REMOVAL	SQ FT	11,080	11,080				
Z0004552	APPROACH SLAB REMOVAL	SQ YD	222	222				
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1			
50200100	STRUCTURE EXCAVATION	CU YD	2,550		2,550			
50200201	COFFERDAM (LOCATION 1)	EACH	1		1			
50200202	COFFERDAM (LOCATION 2)	EACH	1		1			
50300225	CONCRETE STRUCTURES	CU YD	210		210			
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	17,420		17,420			
50800515	BAR SPLICERS	EACH	26		26			
50901720	BICYCLE RAILING	FOOT	38		38			
50901750	PARAPET RAILING	FOOT	75		75			
51500100	NAME PLATES	EACH	1		1			
55101200	STORM SEWER REMOVAL 24"	FOOT	42	42				
55101900	STORM SEWER REMOVAL 48"	FOOT	33	33				
56100500	WATER MAIN 4"	FOOT	10				10	
56100600	WATER MAIN 6"	FOOT	210				210	
56100700	WATER MAIN 8"	FOOT	30				30	
56100900	WATER MAIN 12"	FOOT	940				940	
56104800	WATER VALVES 4"	EACH	1				1	
56104900	WATER VALVES 6"	EACH	2				2	
56105200	WATER VALVES 12"	EACH	2				2	
56200300	WATER SERVICE 1" ^{LINE}	FOOT	210				210	
56200700	WATER SERVICE 2" ^{LINE}	FOOT	25				25	
56400500	FIRE HYDRANTS TO BE REMOVED	EACH	3				3	
60107600	PIPE UNDERDRAINS 4"	FOOT	240	240				
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2				
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	5	5				
60240210	INLETS, TYPE B, TYPE 1 FRAME, OPEN LID	EACH	4	4				
60248900	VALVE VAULTS, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	6				6	
60255500	MANHOLES TO BE ADJUSTED	EACH	1	1				



FILE NAME =	USER NAME = RDS	DESIGNED - JDD	REVISED -
FILEL		DRAWN - RDS	REVISED -
	PLOT SCALE = 1"=58'	CHECKED -	REVISED -
	PLOT DATE = 11-12-10	DATE - 11-12-10	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
IL ROUTE 68 (DUNDEE ROAD) OVER WHEELING DRAINAGE DITCH

SCALE: N.T.S. SHEET NO. OF SHEETS STA. 113+57.00 TO STA. 123+00.00

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
343	98-B	COOK	65	3
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 60H20	

Rev.