POROUS GRANULAR EMBANKMENT, SUBGRADE

STA TO STA	CU YD
113+57 TO 116+00 LT	40
113+57 TO 116+00 RT	40
121+00 TO 123+00 LT	32
121+00 TO 123+00 RT	32
TOTAL	144

TOPSOIL FURNISH AND PLACE, 4"

STA TO STA	SQ YD
113+57 TO 119+25 LT	1,300
113+57 TO 119+25 RT	953
119+64 TO 123+00 LT	260
119+64 TO 123+00 RT	497
TOTAL	3,010

SEEDING, CLASS 4

STA TO STA	ACRE
119+00 TO 119+25 LT	0.03
118+90 TO 119+25 RT	0.01
119+64 TO 119+80 LT	0.01
119+64 TO 119+80 RT	0.01
TOTAL	0.06

NITROGEN FERTILIZER NUTRIENT

STA TO STA	POUND
113+57 TO 119+25 LT	72
113+57 TO 119+25 RT	53
119+64 TO 123+00 LT	15
119+64 TO 123+00 RT	28
TOTAL	168

POTASSIUM FERTILIZER NUTRIENT

STA TO STA	POUND
113+57 TO 119+25 LT	72
113+57 TO 119+25 RT	53
119+64 TO 123+00 LT	15
119+64 TO 123+00 RT	28
TOTAL	168

EROSION CONTROL BLANKET

STA TO STA	SQ YD
113+57 TO 119+25 LT	3,898
119+00 TO 119+25 LT	150
113+57 TO 119+25 RT	2,860
118+90 TO 119+25 RT	75
119+64 TO 123+00 LT	782
119+64 TO 119+80 LT	20
119+64 TO 119+80 RT	45
119+64 TO 123+00 RT	1,490
TOTAL	9,320

SODDING, SALT TOLERANT

STA TO STA	SQ YD
113+57 TO 119+25 LT	1,196
113+57 TO 119+25 RT	870
119+64 TO 123+00 LT	274
119+64 TO 123+00 RT	448
TOTAL	2,788

TEMPORARY EROSION CONTROL SEEDING

STA TO STA	POUND
113+57 TO 119+25 LT	805
113+57 TO 119+25 RT	591
119+64 TO 123+00 LT	162
119+64 TO 123+00 RT	308
TOTAL	1,865

PERIMETER EROSION BARRIER

STA TO STA	FOOT
113+57 TO 119+25 LT	595
113+57 TO 119+25 RT	504
119+64 TO 123+00 LT	267
119+64 TO 123+00 RT	265
TOTAL	1,631

INLET FILTERS

STA	EACH
114+52 RT	2
116+61 RT	2
118+45 RT	2
120+70 RT	2
122+36 RT	2
114+52 LT	2
116+58 LT	2
118+75 LT	2
120+70 LT	2
122+35 LT	2
TOTAL	20

BITUMINOUS MATERIALS (PRIME COAT)

STA TO STA	GALLON
STAGE I	1,260
STAGE II	1,855
TOTAL	3,115

AGGREGATE (PRIME COAT)

STA TO STA	TON
STAGE I	32
STAGE II	48
TOTAL	80

CONSTRUCTING TEST STRIP

STA	EACH
STAGE I	1
STAGE II	1
TOTAL	2

HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT

STA	SQ YD
113+57	25
123+00	26
TOTAL	51

POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90

STA TO STA	TON
STAGE I	142
STAGE II	142
TOTAL	284

HOT-MIX ASPHALT BINDER COURSE, MIX "C", N50

STA TO STA	TON
BIKEPATH, 2½ INCH	
113+87 TO 120+26	100
120+47 TO 120+80	5
121+05 TO 122+21	18
122+45 TO 123+00	7
DRIVEWAY, 2 INCH	
118+62 TO 122+22	5
HMA PARKING LOT, 2 INCH	
119+89 TO 122+00 LT	15
TOTAL	150

POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90

STA	TON
STAGE I	165
STAGE II	165
TOTAL	330

INCIDENTAL HOT-MIX ASPHALT SURFACING

STA	TON
STAGE I	20
STAGE II	20
TOTAL	40

HOT-MIX ASPHALT PAVEMENT (FULL DEPTH), 12¼"

STA	SQ YD
STAGE I	1,390
STAGE II	1,950
TOTAL	3,340

PORTLAND CEMENT CONCRETE PAVEMENT 8"

STA	SQ YD
114+36.5 RT	26
115+66 RT	25
115+84 RT	26
118+62 RT	22
120+00 RT	26
120+37 LT	47
120+91 LT	51
121+08 LT	30
122+08 RT (RT IN)	19
122+58 RT (RT OUT)	24
122+25 LT	64
TOTAL	360

PORTLAND CEMENT CONCRETE SIDEWALK, 5"

STA TO STA	SQ FT
114+46 TO 115+55 RT	872
115+77 TO 116+73 RT	768
116+95 TO 118+52 RT	1,256
118+72 TO 119+88 RT	928
120+12 TO 120+94 RT	656
121+20 TO 122+15 RT	760
TOTAL	5,240

PORTLAND CEMENT CONCRETE SIDEWALK, 8"

DRIVE LOCATION	SQ FT
114+36.5 RT	160
115+66 RT	208
115+84 RT	200
118+62 RT	192
120+00 RT	192
121+08 RT	224
122+08 RT	112
122+58 RT	128
TOTAL	1,416

DETECTABLE WARNINGS

STA	SQ FT
114+26 RT	16
114+46 RT	16
115+55 RT	16
115+77 RT	16
116+73 RT	16
116+95 RT	16
118+52 RT	16
118+72 RT	16
119+88 RT	16
120+12 RT	16
120+94 RT	16
121+20 RT	16
122+15 RT	16
122+35 RT	16
TOTAL	224

PAVEMENT REMOVAL

STA	SQ YD
STAGE I	770
STAGE II	1,565
TOTAL	2,335

Applied Technologies

FILE NAME = $FILEL$	USER NAME = RDS	DESIGNED - JDD	REVISED -
		DRAWN - RDS	REVISED -
	PLOT SCALE = 1"=50'	CHECKED -	REVISED -
	PLOT DATE = 11-12-10	DATE - 11-12-10	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
IL ROUTE 68 (DUNDEE ROAD) OVER WHEELING DRAINAGE DITCH

SCALE: 1"=50' | SHEET NO. OF SHEETS | STA. 113+57.00 TO STA. 123+00.00

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
343	98-B	COOK	65	7
		CONTRACT NO. 60H20		

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT