

## STANDARD BAR SPLICER ASSEMBLY

Minimum Lap Lengths							
Bar size to be spliced	Table 1	Table 2	Table 3	Table 4			
3, 4	1'-5''	1'-11''	2'-1''	2'-4"			
5	1'-9''	2'-5".	2'-7''	2'-11''			
6	2'-1"	2'-11''	3'-1"	3'-6''			
. 7	2'-9''	3'-10''	4'-2''	4'-8''			
8	3'-8''	5′-1′′	5′-5′′	6'-2''			
9	. 4'-7"	6'-5''	. 6'-10''	7'-9''			

Table 1: Black bar, 0.8 Class C

DESIGNED MAH

CHECKED JMH

DRAWN DR

11-1-09

BSD-1

Table 2: Black bar, Top bar lap, 0.8 Class C


Table 3: Epoxy bar, 0.8 Class C

Table 4: Epoxy bar, Top bar lap, 0.8 Class C

Threaded splicer bar length = min, lap length +  $l_2'''$  + thread length

\* Epoxy not required on Bar Splicer Assembly components used in conjunction with black bars.

## STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION




## INSTALLATION AND SETTING METHODS

"A": Set bar splicer assembly by means of a template bolt.
"B": Set bar splicer assembly by nailing to wood forms or cementing to steel forms.

(E): Indicates epoxy coating.

Location	Bar	No. assemblies	Table for minimum
Location	size	required	lap length
Superstructure	#5	213	Table 3
Approach	#4	50	Table 3
Approach	#5	92	Table 3
Approach Footing	#5	80	Table 3
E. & W. Abutments	#5	36	Table 3
E. & W. Abutments	#6	8	Table 3



## NOTES

Splicer bars shall be deformed with threaded ends and have a minimum 60 ksi yield strength.

All reinforcement shall be lapped and tied to the splicer bars.

Bar splicer assemblies shall be epoxy coated according to the requirements for reinforcement bars. See Section 508 of the Standard Specifications.

See special provision for Mechanical Splicers.

See approved list of bar splicer assemblies and mechanical splicers for alternatives

BAR SPLICER ASSEMBLY AND MECHANICAL SPLICER DETAILS STRUCTURE NO. 016-0581

COLLINS 123 N. WACKER DR., SUITE 300 CHICAGO, IL 60606 ENGINEERS (312) 704-9300 SILLINOIS PROFESSIONAL DESIGN FIRM LICENSE NO. 184-000993

SHEET NO. S25	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHE
OF	339	116-Y-2-BR-1	COOK	74	45
S27 SHEETS			CONTRACT	NO. 60	)J00
		TILINOIS FED AT	D PROJECT		