
STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION



STANDARD BAR SPLICER ASSEMBLY

Minimum Lap Lengths						
Bar size to be spliced	Table 1	Table 2	Table 3	Table 4		
3, 4	1'-5''	1'-11''	2'-1"	2'-4"		
5	1'-9''	2'-5"	2'-7"	2'-11''		
6	2'-1''	2'-11''	3'-1"	3'-6''		
7	2'-9"	3'-10''	4'-2"	4'-8''		
8	3'-8''	5'-1"	5'-5"	6'-2"		
9	4'-7"	6'-5"	6'-10"	7'-9"		

Table 1: Black bar, 0.8 Class C

Bridge Deck

Threaded

Reinforcement

bar (E)

Table 2: Black bar, Top bar lap, 0.8 Class C Table 3: Epoxy bar, 0.8 Class C

Table 4: Epoxy bar, Top bar lap, 0.8 Class C

Threaded splicer bar length = min. lap length + $1^l2''$ + thread length

* Epoxy not required on Bar Splicer Assembly components used in conjunction with black bars.

Location	Bar size	No. assemblies required	Table for minimum lap length
Tee Cleb	#4	20	Table 1
Top Slab	#7	20	Table 2
Bottom Slab	#5	40	Table 1
Walls	#5	18	Table 2
	Total	98	


BAR SPLICER ASSEMBLY FOR #5 BAR ON

INTEGRAL OR SEMI-INTEGRAL ABUTMENTS

No. required = -

Approach Slab


Threaded splicer bar (E)




INSTALLATION AND SETTING METHODS

"A" : Set bar splicer assembly by means of a template bolt. "B": Set bar splicer assembly by nailing to wood forms or cementing to steel forms.

(E): Indicates epoxy coating.





STANDARD MECHANICAL SPLICER

Location	Bar size	No. assemblies required
Other State of the		

 $\frac{\textit{NOTES}}{\textit{Splicer bars shall be deformed with threaded ends and have a minimum 60 ksi}}$ yield strength.

All reinforcement shall be lapped and tied to the splicer bars.

Bar splicer assemblies shall be epoxy coated according to the requirements for reinforcement bars. See Section 508 of the Standard Specifications. See special provision for Mechanical Splicers.

See approved list of bar splicer assemblies and mechanical splicers for

BAR SPLICER ASSEMBLY AND MECHANICAL SPLICER DETAILS IL. ROUTE 56 OVER FERRY CREEK F.A.P. RTE. 365 SECTION (58&59) WRS-3 DuPAGE COUNTY STA. 150+84.00 STRUCTURE NO. 022-2025

DESIGNED CHECKED DRAWN -CHECKED

CHRISTIAN-ROGE & ASSOCIATES, INC. ENGINEERS-PLANNERS-SURVEYORS 211 WEST WACKER DRIVE CHICAGO, ILLINOIS 60606 PHONE: (312)372-2023 FAX: (312)372-5274

SHEET NO. S5	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	365	(58&59) WRS-3	DuPAGE	466	204
S7 SHEETS			CONTRACT	NO. 62	420
		ILLINOIS FED. A	ID PROJECT		