

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
353	(12&13)WRS-4	WILL	608	5
STA.		TO STA.		
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

URBAN

FUNDING BREAKDOWN		80% FED 20% STATE	80% STATE 20% FPDWC	80% STATE 20% VOF	80% STATE 20% VOF	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	100% VOF	80% FED 20% STATE	80% FED 13.3% STATE 6.7% VOF	80% FED 10% STATE 10% FT	80% FED 10% STATE 5% VOF 5% FT	80% FED 20% STATE	80% FED 20% STATE	
LOCATION OF WORK		ROADWAY	BIKEPATH	BIKEPATH	SIDEWALK	SIDEWALK	HICKORY CREEK BRIDGE	BOX CULVERTS	LIGHTING	LANDSCAPING	WATERMAIN	WATERMAIN	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	
SUMMARY OF QUANTITIES																			
CODE NO.	PAY ITEM	UNIT	TOTAL	0003	0021	0021	0021	0021	0013	0040	0021	0031	0043	0043	0021	0021	0021	0021	0021
28100105	STONE RIPRAP, CLASS A3	SQ YD	261	261															
28100107	STONE RIPRAP, CLASS A4	SQ YD	1,061						751	310									
28200200	FILTER FABRIC	SQ YD	1,061						751	310									
31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	22,262	13,266	3,627 ¹	5,369 ²													
31200502	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4 1/2"	SQ YD	141,757	141,757															
2	35101598	AGGREGATE BASE COURSE, TYPE B 3"	SQ YD	4,218			2,668	1,300					250						
2	35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	564	564														
2	35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	415	415														
	35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	3,413	3,413														
	35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	7,660	7,660														
	35501324	HOT-MIX ASPHALT BASE COURSE, 10"	SQ YD	565	565														
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	7,211	7,211														
	40600300	AGGREGATE (PRIME COAT)	TON	20	20														
	40600895	CONSTRUCTING TEST STRIP	EACH	4	4														
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	58	58														
	40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	868	868														
	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	2,716	1,204	610	902												
	40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	229	229														
	40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	309	309														
	40701861	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 9"	SQ YD	7,882	7,819								63						
	40701881	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 10"	SQ YD	1,822	1,822														
	42000416	PORTLAND CEMENT CONCRETE PAVEMENT, 9 3/4" (JOINTED)	SQ YD	135,293	135,293														
	42001300	PROTECTIVE COAT	SQ YD	171,392	167,424			2,668	1,300										
	42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	1,206	1,206														
	42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	564	564														
	42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	1,072	1,072														
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	37,954			24,005	11,700					2,249						
	42400800	DETECTABLE WARNINGS	SQ FT	392		120	20	60	192										
	44000100	PAVEMENT REMOVAL	SQ YD	131,599	131,536								63						
	44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	1,066	1,066														

- INDICATES SPECIALTY ITEMS
- 1 100% WILL COUNTY FOREST PRESERVE COST
- 2 100% VILLAGE OF FRANKFORT COST 0003

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SUMMARY OF QUANTITIES
SCALE: VERT. DRAWN BY JRR		CHECKED BY JRV
DATE 6/11/2010		