

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
353	(12&13)WRS-4	WILL	608	9
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	

URBAN

SUMMARY OF QUANTITIES		FUNDING BREAKDOWN		80% FED 20% STATE	80% STATE 20% FPDWC	80% STATE 20% VOF	80% STATE 20% VOF	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	100% VOF	80% FED 20% STATE	80% FED 13.3% STATE 6.7% VOF	80% FED 10% STATE 10% FT	80% FED 10% STATE 5% VOF 5% FT	80% FED 20% STATE	80% FED 20% STATE
		LOCATION OF WORK		ROADWAY	BIKEPATH	BIKEPATH	SIDEWALK	SIDEWALK	HICKORY CREEK BRIDGE	BOX CULVERTS	LIGHTING	LANDSCAPING	WATERMAIN	WATERMAIN	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS
CODE NO.	PAY ITEM	UNIT	TOTAL	0003	0021	0021	0021	0021	0013	0040	0021	0031	0043	0043	0021	0021	0021	0021	0021	0021
550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	60	60																
550A0470	STORM SEWERS, CLASS A, TYPE 2 42"	FOOT	845	845																
550A0500	STORM SEWERS, CLASS A, TYPE 2 60"	FOOT	189	189																
550A0730	STORM SEWERS, CLASS A, TYPE 3 30"	FOOT	189	189																
55100200	STORM SEWER REMOVAL 6"	FOOT	162	162																
55100300	STORM SEWER REMOVAL 8"	FOOT	228	228																
55100400	STORM SEWER REMOVAL 10"	FOOT	381	381																
55100500	STORM SEWER REMOVAL 12"	FOOT	2,845	2,845																
55100700	STORM SEWER REMOVAL 15"	FOOT	2,586	2,586																
55100800	STORM SEWER REMOVAL 16"	FOOT	48	48																
55100900	STORM SEWER REMOVAL 18"	FOOT	1,830	1,830																
55101100	STORM SEWER REMOVAL 21"	FOOT	383	383																
55101200	STORM SEWER REMOVAL 24"	FOOT	787	787																
55101300	STORM SEWER REMOVAL 27"	FOOT	77	77																
55101400	STORM SEWER REMOVAL 30"	FOOT	58	58																
55101600	STORM SEWER REMOVAL 36"	FOOT	202	202																
55101900	STORM SEWER REMOVAL 48"	FOOT	104	104																
● 56105750	BUTTERFLY VALVES 12"	EACH	8											5	3					
● 56108800	TAPPING VALVES AND SLEEVES 6"	EACH	1											1						
● 56109100	TAPPING VALVES AND SLEEVES 12"	EACH	7											4	3					
● 56400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	9	9																
● 56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	3	3																
58700300	CONCRETE SEALER	SQ FT	514						514											
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	72						72											
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	1	1																
60107600	PIPE UNDERDRAINS 4"	FOOT	5,400	5,400																
60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1																
60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	16	16																
60201105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 11 FRAME AND GRATE	EACH	3	3																
60201110	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 11V FRAME AND GRATE	EACH	11	11																

● INDICATES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ. DATE 6/11/2010

DRAWN BY JRR CHECKED BY JRV