

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
353	(12&13)WRS-4	WILL	608	19
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	

URBAN

FUNDING BREAKDOWN		80% FED 20% STATE	80% STATE 20% FPDWC	80% STATE 20% VOF	80% STATE 20% VOF	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	100% VOF	80% FED 20% STATE	80% FED 13.3% STATE 6.7% VOF	80% FED 10% STATE 10% FT	80% FED 10% STATE 5% VOF 5% FT	80% FED 20% STATE	80% FED 20% STATE	
LOCATION OF WORK		ROADWAY	BIKEPATH	BIKEPATH	SIDEWALK	SIDEWALK	HICKORY CREEK BRIDGE	BOX CULVERTS	LIGHTING	LANDSCAPING	WATERMAIN	WATERMAIN	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	
SUMMARY OF QUANTITIES																			
CODE NO.	PAY ITEM	UNIT	TOTAL	0003	0021	0021	0021	0021	0013	0040	0021	0031	0043	0043	0021	0021	0021	0021	0021
X0327030	REMOVE DECORATIVE ARBOR	EACH	2	2															
X0327031	EXPLORATORY EXCAVATION	L SUM	1					1											
X0327032	TEMPORARY VIDEO DETECTION	EACH	1												1				
X0327033	RELOCATE EXISTING VALVE VAULT AND CONNECT TO PROPOSED WATER MAIN	L SUM	1										1						
X0327034	24" DIAMETER STEEL SLEEVE, 0.375" WALL THICKNESS, AUGERED	FOOT	355										130	225					
X0351580	PVC WATER MAIN 12"	FOOT	6,200										5,500	700					
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	142					142											
X2130010	EXPLORATION TRENCH, SPECIAL	FOOT	500	500															
X2502024	SEEDING, CLASS 4B (MODIFIED)	ACRE	1.25	1.25															
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	50	50															
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	47	47															
X4023000	TEMPORARY ACCESS (ROAD)	EACH	24	24															
X4201400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	363	363															
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	3,654	3,654															
X4403800	MEDIAN SURFACE REMOVAL	SQ FT	40,379	40,379															
X5012502	CONCRETE REMOVAL (SPECIAL)	CU YD	14					14											
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1					1											
X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2	EACH	1					1											
X5630006	CUT AND CAP EXISTING 6" WATER MAIN	EACH	1										1						
X5630012	CUT AND CAP EXISTING 12" WATER MAIN	EACH	10										8	2					
X6020088	MANHOLES, TYPE A, 8' DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1															
X6020098	MANHOLES, TYPE A, 9' DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1															
X6022900	CATCH BASINS TO BE RECONSTRUCTED (SPECIAL)	EACH	49	49															
X6026050	SANITARY MANHOLES TO BE ADJUSTED	EACH	17	17															
X6026800	INLETS TO BE RECONSTRUCTED (SPECIAL)	EACH	1	1															
X6028000	MANHOLES TO BE RECONSTRUCTED (SPECIAL)	EACH	12	12															
X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	24	24															
X7030104	WET TEMPORARY PAVEMENT MARKING TAPE, TYPE III 4 INCH	FOOT	153,148	153,148															
X7030106	WET TEMPORARY PAVEMENT MARKING TAPE, TYPE III 6 INCH	FOOT	7,171	7,171															
X7030112	WET TEMPORARY PAVEMENT MARKING TAPE, TYPE III 12 INCH	FOOT	2,152	2,152															

● INDICATES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. DRAWN BY JRR
 HORIZ. CHECKED BY JRV
 DATE 6/11/2010