

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
353	(12&13)WRS-4	WILL	608	43
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS FED. AID PROJECT		

STATION	CLASS SI CONC. (OUTLET) (CUYD)	CONCRETE CURB, TYPE B (FT)	COMB. CONC. C&G, TYPE B-6.12 (FT)	COMB. CONC. C&G, TYPE B-6.24 (FT)	COMB. CONC. C&G, TYPE B-9.12 (FT)	COMB. CONC. C&G, TYPE M-2.24 (FT)	CONC. MEDIAN SURFACE, 4 INCH (SQFT)	CONC. MEDIAN, TYPE SB-6.12 (SQFT)	CONC. MEDIAN, TYPE SB-6.24 (SQFT)	CONC. MEDIAN, TYPE SB-6.24 (MODIFIED) (SQFT)	CORRUGATED MEDIAN (SQFT)	P.C.C. DRIVEWAY PAVEMENT, 6 INCH (SQYD)	P.C.C. DRIVEWAY PAVEMENT, 8 INCH (SQYD)
	60600095	60600605	60603800	60605000	60605900	60608521	60618300	60619600	60620000	60620200	60624600	42300200	42300400
U.S. ROUTE 30 410+00 TO 423+00	0	0	0	0	0	609	0	0	0	0	0	0	0
423+00 TO 435+00	5.5	99	143	2,256	0	1,003	0	0	688	2,460	154	0	0
435+00 TO 450+00	0	0	0	5,366	0	0	0	0	442	1,231	80	0	0
450+00 TO 465+00	0	0	104	4,991	0	0	0	0	537	2,197	169	0	0
465+00 TO 480+00	0	0	0	4,939	0	0	0	0	786	2,434	84	0	0
480+00 TO 495+00	0	0	128	3,929	0	0	333	0	687	2,308	134	0	0
495+00 TO 510+00	5.4	0	0	4,432	0	0	0	1,002	538	2,457	193	181	0
510+00 TO 525+00	0	0	0	4,647	0	0	0	378	884	3,092	160	0	0
525+00 TO 539+00	0	78	43	3,895	0	0	0	1,380	442	3,604	274	0	197
539+00 TO 554+00	0	382	200	4,637	0	0	0	248	345	3,043	886	0	449
554+00 TO 569+00	0	64	61	5,324	0	0	0	0	442	1,230	91	0	0
569+00 TO 584+00	0	115	97	3,963	0	0	0	2,340	397	3,715	539	0	0
584+00 TO 591+10.14	12.5	0	0	2,471	0	0	0	0	0	0	0	0	0
94TH AVE 525+72 TO 529+00	0	0	0	0	0	0	0	0	0	0	0	109	241
93RD AVE 546+65 TO 549+00	8.8	0	0	0	0	0	0	0	0	0	0	0	0
PFEIFFER RD 593+50 TO 598+00	0	0	0	900	0	0	0	0	0	0	0	0	94
84TH AVE 701+15 TO 703+67.22	0	0	0	401	0	0	0	0	0	0	0	243	0
HILLSIDE RD 745+30 TO 749+00	9.3	0	0	19	0	0	0	0	0	0	0	0	0
80TH AVE 794+89.46 TO 804+25.34	6.3	0	0	330	0	0	0	0	0	0	0	0	0
HUNTER WOODS/FRANKFORT SQ. 896+32.18 TO 903+86	0	21	154	377	0	0	0	0	0	0	0	31	91
HARLEM AVENUE 981+31.38 TO 989+00	0	0	0	178	0	0	0	0	0	0	0	0	0
989+00 TO 998+00	0	0	627	1,800	0	0	4,402	1,015	0	0	0	0	0
1002+00 TO 1011+84.62	0	18	0	3,601	0	0	0	0	300	778	0	0	0
STAGE 3 REPLACEMENT	0	0	0	1,508	1,014	0	10,573	0	0	0	0	0	0
TOTALS	47.8	777	1,557	59,964	1,014	1,612	15,308	6,363	6,488	28,590	2,764	564	1,072

STATION	SIGN PANEL TYPE 1 (SQFT)	SIGN PANEL TYPE 2 (SQFT)	REMOVE SIGN PANEL ASSEMBLY - TYPE A (EACH)	REMOVE SIGN PANEL ASSEMBLY - TYPE B (EACH)	REMOVE SIGN PANEL - TYPE 1 (SQFT)	RELOCATE SIGN PANEL ASSEMBLY - TYPE A (SQFT)	TELESCOPING STEEL SIGN SUPPORT (FOOT)	METAL POST TYPE A (FOOT)
	72000100	72000200	72400100	72400200	72400310	72400500	72800100	72900100
U.S. ROUTE 30 410+00 TO 423+00	0	0	0	0	9	0	0	0
423+00 TO 435+00	37.8	36*	7	0	0	0	61.0	46*
435+00 TO 450+00	68.9	10+54*	7	1	0	0	148.8	69*
450+00 TO 465+00	95.4	0	11	2	0	0	162.3	0
465+00 TO 480+00	70.0	0	9	0	0	0	146.0	0
480+00 TO 495+00	62.0	0	3	0	0	0	116.0	0
495+00 TO 510+00	135.6	90*	14	0	0	0	225.3	115*
510+00 TO 525+00	108.9	18*	10	0	0	1	216.3	23*
525+00 TO 539+00	131.0	18*	13	0	0	1	329.0	23*
539+00 TO 554+00	142.5	0	11	2	0	0	250.5	0
554+00 TO 569+00	39.8	10	3	2	0	0	90.5	0
569+00 TO 584+00	209.3	0	22	0	0	4	408.8	0
584+00 TO 591+10.14	29.4	0	4	0	0	0	47.0	0
94TH AVE 525+72 TO 529+00	0	0	1	0	0	0	0	0
93RD AVE 546+65 TO 549+00	7.5	0	2	0	0	0	15.0	0
PFEIFFER RD 593+50 TO 598+00	12.5	0	1	0	0	0	29.5	0
84TH AVE 701+15 TO 703+67.22	0	0	1	0	0	0	0	0
HILLSIDE RD 745+30 TO 749+00	5.0	0	0	0	0	0	14.5	0
80TH AVE 794+89.46 TO 804+25.34	0	0	2	0	0	0	0	0
HUNTER WOODS/FRANKFORT SQ. 896+32.18 TO 903+86	18.8	0	3	0	0	0	44.0	0
HARLEM AVENUE 981+31.38 TO 989+00	23.6	0	1	0	0	0	42.3	0
989+00 TO 998+00	41.6	36*	5	0	0	0	64.0	46*
1002+00 TO 1011+84.62	45.6	0	6	0	0	0	102.5	0
TOTALS	1,286	272	136	7	9	6	2,514	322*

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

U.S. ROUTE 30
SCHEDULE OF QUANTITIES

SCALE: VERT. _____
HORIZ. _____
DATE 6/11/2010

DRAWN BY DJK
CHECKED BY JRJ

SEE MAST ARM MOUNTED SIGN DETAIL SHEETS FOR ADDITIONAL SIGN PANEL QUANTITIES * QUANTITY FOR WETLAND SIGNING SHOWN ON EROSION CONTROL PLANS