

SUMMARY OF QUANTITIES				TOTAL QTY	TRAFFIC SIGNALS	SIGNING
S.I. CODE NO.	PAY ITEM	UNIT				
67100100	MOBILIZATION	L SUM	1	0.5	0.5	
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	0.5	0.5	
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	0.5	0.5	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0.5	0.5	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	0.5	0.5	
X7200366	SIGN PANEL--TYPE 3 (SPECIAL)	SQ FT	675		675	
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	832		832	
81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	300	300		
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	13	13		
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	7000	7000		
89502210	MODIFY EXISTING CONTROLLER CABINET	EACH	13	13		
Z0000850	TEMPORARY INFORMATION SIGNING	SQ FT	103		103	
XX006926	ILLUMINATED STREET NAME SIGN	EACH	39	39		

FILE NAME = 07441_02-QUAN-01 - IDOT.P01

USER NAME =	DESIGNED -- MRS	REVISED --
	CHECKED -- PKB	REVISED --
PLOT SCALE =	DRAWN -- RG	REVISED --
PLOT DATE = 10-21-10	CHECKED -- AG	REVISED --

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

HARLEM AVENUE BEAUTIFICATION
FROM SOUTHWEST HIGHWAY TO 65TH STREET
SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
348	07-00055-01-SG	COOK	55	3
CONTRACT NO. 63510				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT HPP-3482(001)				

SCALE: NONE SHEET NO. 3 OF 55 SHEETS STA. TO STA.