

LANDSCAPING AND EROSION CONTROL ITEMS

PAY ITEM	UNIT	Sta. 118+70 to Sta. 123+50	Sta. 123+50 to Sta. 130+00	TOTAL
TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	16	56	72
TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	180	24	204
TEMPORARY FENCE	FOOT	0	30	30
SEEDING, CLASS 2A	ACRE	0.05	0.2	0.25
SEEDING, CLASS 4 (MODIFIED)	ACRE	0.33	0.92	1.25
SEEDING, CLASS 5 (MODIFIED)	ACRE	0.33	0.92	1.25
EROSION CONTROL BLANKET	SQ YD	1543	5717	7260
TEMPORARY EROSION CONTROL SEEDING	POUND	64	239	303
PERIMETER EROSION BARRIER	FOOT	889	1331	2220

MARKING, STRIPING, AND SIGNAGE ITEMS

PAY ITEM	UNIT	Sta. 114+90 to Sta. 118+70	Sta. 118+70 to Sta. 124+50	Sta. 124+50 to Sta. 126+60	Sta. 126+60 to Sta. 130+10	TOTAL
SIGN PANEL - TYPE 1	SQ FT	0	26	9	0	35
RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	0	2	0	0	2
WOOD SIGN SUPPORT	FOOT	0	112	14	0	126
THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1520	2320	840	1400	6080
TEMPORARY INFORMATIONAL SIGNS	EACH	1	0	0	1	2
GUARDRAIL MARKERS, TYPE A	EACH	0	8	2	0	10
GUARDRAIL MARKERS, TYPE B	EACH	0	4	0	0	4
TERMINAL MARKER - DIRECT APPLIED	EACH	0	2	2	0	4

PAVEMENT ITEMS

PAY ITEM	UNIT	Sta. 114+90 to Sta. 118+70	Sta. 118+70 to Sta. 124+50	Sta. 124+50 to Sta. 126+60	Sta. 126+60 to Sta. 130+10	TOTAL
LEVELING BINDER (MACHINE METHOD), N50	TON	55	0	0	50	105
HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	76	0	0	77	153
HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	0	558	282	32	872
HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	115	124	63	116	418
AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	0	31	79	0	110
AGGREGATE WEDGE SHOULDER, TYPE B	TON	13	0	0	11	24
HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	0	382	178	0	560


REMOVAL ITEMS

PAY ITEM	UNIT	Sta. 114+90 to Sta. 118+70	Sta. 118+70 to Sta. 124+50	Sta. 124+50 to Sta. 126+60	Sta. 126+60 to Sta. 130+10	TOTAL
PAVEMENT REMOVAL	SQ YD	0	997	801	0	1798
GUARDRAIL REMOVAL	FOOT	0	715	313	0	1028
REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	0	6	1	0	7

GUARDRAIL ITEMS

PAY ITEM	UNIT	Sta. 114+90 to Sta. 118+70	Sta. 118+70 to Sta. 124+50	Sta. 124+50 to Sta. 126+60	Sta. 126+60 to Sta. 130+10	TOTAL
STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	0	399.2	38.3	0	437.5
TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	0	4	0	0	4
TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	0	2	2	0	4

FILE NAME = P:\CIBEL\WEST Projects\2289\98-8882\Bolsum\PRINT\Civil\Drawn\SHA\SCHEDULE.L.dgn

 WILLS BURKE KELSEY ASSOCIATES LTD. 118 West Main Street, Suite 201 St. Charles, Illinois 60174	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE =	CHECKED -	REVISED -			2332	03-14185-02-BR	KANE	73	6
PLOT DATE = 10/22/10	DATE - 10/22/10	REVISED -		SCALE:	SHEET NO. 6 OF 73 SHEETS	STA.	TO STA.	CONTRACT NO. 63521 FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT		