

STATION	TO STATION	EARTH EXCAVATION CU YD	AVAILABLE EXCAVATION ADJUSTED FOR SHRINKAGE CU YD (15.0%)	EMBANKMENT CU YD	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) CU YD
BIRCH ST.					
10+39.59	10+50.00	8.8	7.4	0.0	7.4
10+50.00	11+00.00	40.3	34.2	0.0	34.2
11+00.00	11+42.54	43.5	37.0	0.0	37.0
11+42.54	11+50.00	7.7	6.6	0.0	6.6
11+50.00	11+64.03	13.5	11.4	0.0	11.4
11+64.03	12+00.00	39.0	33.1	0.0	33.1
12+00.00	12+50.00	51.2	43.5	0.0	43.5
12+50.00	12+76.15	34.0	28.9	0.0	28.9
12+76.15	13+00.00	31.1	26.5	0.0	26.5
13+00.00	13+12.22	13.6	11.5	0.0	11.5
13+12.22	13+50.00	46.0	39.1	0.0	39.1
13+50.00	14+00.00	53.3	45.3	0.0	45.3
CHERRY AVE.					
21+03.52	21+20.95	16.1	13.7	0.0	13.7
21+20.95	21+50.00	38.8	33.0	0.0	33.0
21+50.00	22+00.00	73.8	62.7	0.0	62.7
22+00.00	22+18.37	27.0	22.9	0.0	22.9
22+18.37	22+50.00	41.6	35.3	0.0	35.3
22+50.00	23+00.00	66.9	56.8	0.0	56.8
23+00.00	23+50.00	68.1	57.9	0.0	57.9
23+50.00	24+00.00	63.1	53.6	0.0	53.6
24+00.00	24+50.00	54.5	46.4	0.0	46.4
24+50.00	24+62.79	12.4	10.5	0.0	10.5
24+62.79	24+82.43	21.7	18.5	0.0	18.5
24+82.43	25+00.00	18.8	16.0	0.0	16.0
25+00.00	25+13.51	14.0	11.9	0.0	11.9
25+13.51	25+50.00	37.2	31.6	0.0	31.6
25+50.00	26+00.00	49.9	42.4	0.0	42.4
26+00.00	26+14.01	15.4	13.1	0.0	13.1
26+14.01	26+50.00	46.2	39.3	0.0	39.3
26+50.00	26+89.38	47.8	40.7	0.0	40.7
26+89.38	27+00.00	11.5	9.8	0.0	9.8
27+00.00	27+31.51	37.8	32.1	0.0	32.1
27+31.51	27+50.00	23.4	19.9	0.0	19.9
27+50.00	27+71.90	26.2	22.3	0.0	22.3
27+71.90	28+00.00	27.6	23.5	0.0	23.5
28+00.00	28+11.43	10.4	8.9	0.0	8.9
28+11.43	28+50.00	34.9	29.6	0.0	29.6
28+50.00	29+00.00	44.3	37.6	0.0	37.6
29+00.00	29+38.49	36.8	31.3	0.0	31.3
29+38.49	29+50.00	12.7	10.8	0.0	10.8
29+50.00	30+00.00	59.0	50.1	0.0	50.1
30+00.00	30+18.76	19.1	16.3	0.0	16.3
30+18.76	30+50.00	27.4	23.3	0.0	23.3
30+50.00	31+00.00	42.0	35.7	0.0	35.7
31+00.00	31+50.00	53.1	45.1	0.0	45.1
TOTAL		1561.5	1327.0	0.0	1327.3

PAVEMENT REMOVAL				SQ YD
LOCATION	STATION	TO STATION		QUANTITY
BIRCH ST.	10+12.5	14+28		1,208.7
CHERRY AVE.	21+03.5	31+54.3		2,960.5
WILLOW ST.	26+06.5	26+80		89.2
TOTAL				4,258

HOT-MIX ASPHALT SURFACE REMOVAL, 3 3/4"				SQ YD
LOCATION	STATION	TO STATION		QUANTITY
CHERRY AVE.	31+54	36+35		1,506
TOTAL				1,506

COMBINATION CURB AND GUTTER REMOVAL				FOOT	
LOCATION	STATION	TO STATION		QUANTITY	
BIRCH ST.					
	14+25.6	LT	12+82.6	LT	168.9
	12+67.6	LT	10+13.0	LT	296.7
	14+25.6	RT	11+69.8	RT	273.7
	11+58.2	RT	10+14.0	RT	158.4
CHERRY AVE.					
	21+15.4	RT	31+53.0	RT	1,061.8
	21+78.8	LT	26+30.1	LT	466.7
	23+03.1	LT	23+15.2	LT	17.3
	26+58.3	LT	31+52.8	LT	523.4
	29+24.2	LT	29+29.9	LT	7.8
	29+45.7	LT	29+52.9	LT	9.0
	29+24.7	RT	29+30.5	RT	8.0
	29+47.3	RT	29+53.6	RT	8.1
TOTAL				3,000.0	

COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12					FOOT
LOCATION	STATION	TO STATION			QUANTITY
BIRCH ST.					
	10+13.9	LT	14+25.6	LT	431.9
	11+52.5	LT	11+57.6	LT	11.5
	11+70.0	LT	11+77.0	LT	15.3
	10+14.4	RT	14+25.4	RT	443.7
	12+61.9	RT	12+67.7	RT	21.6
	12+83.1	RT	12+89.8	RT	21.9
CHERRY AVE.					
	21+88.0	LT	26+29.9	LT	463.8
	26+58.3	LT	31+52.6	LT	523.4
	29+24.5	LT	29+29.9	LT	7.8
	29+45.7	LT	29+52.9	LT	9.0
	21+03.6	RT	31+52.8	RT	1,061.6
	29+24.7	RT	29+30.5	RT	8.0
	29+47.3	RT	29+53.5	RT	8.1
TOTAL					3,028.0

HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50				TON
LOCATION	STATION	TO STATION		QUANTITY
CHERRY AVE.	31+54.3	36+35.0		126.5
BIRCH ST. (DWYS)	10+31.4	14+25.4		45.4
CHERRY AVE. (DWYS)	21+30.0	30+10.4		64.6
TOTAL				236.5

HOT MIX ASPHALT BINDER COURSE, 1L-19.0, N50				TON
LOCATION	STATION	TO STATION		QUANTITY
CHERRY AVE.	31+54.3	36+35.0		193.1
TOTAL				193.1

HOT MIX ASPHALT PAVEMENT (FULL-DEPTH), 6"				SQ YD
LOCATION	STATION	TO STATION		QUANTITY
BIRCH ST.	10+12.8	14+28.0		1,153.3
CHERRY AVE.	21+03.9	31+54.3		2,917.8
TOTAL				4,071.1

DRIVEWAY PAVEMENT REMOVAL					SQ YD
LOCATION	STATION	STATION			QUANTITY
BIRCH ST.	10+14.8	LT	10+32.3	LT	15.9
BIRCH ST.	10+31.7	LT	10+47.5	LT	22.6
BIRCH ST.	10+46.9	LT	11+34.8	LT	48.4
BIRCH ST.	11+33.9	LT	11+48.3	LT	21.2
BIRCH ST.	11+48.3	LT	12+67.8	LT	73.0
BIRCH ST.	12+62.7	LT	12+89.9	LT	32.9
BIRCH ST.	12+83.1	LT	13+14.1	LT	23.6
BIRCH ST.	13+16.8	LT	14+25.6	LT	63.4
BIRCH ST.	11+18.7	RT	11+57.2	RT	38.2
BIRCH ST.	11+57.2	RT	11+70.0	RT	13.5
BIRCH ST.	11+70.0	RT	11+95.9	RT	16.4
BIRCH ST.	11+95.0	RT	12+17.2	RT	25.7
BIRCH ST.	12+15.9	RT	12+53.0	RT	20.1
BIRCH ST.	12+52.9	RT	12+71.8	RT	25.6
BIRCH ST.	12+71.8	RT	12+80.8	RT	17.0
BIRCH ST.	12+80.8	RT	13+05.9	RT	13.9
BIRCH ST.	13+05.9	RT	13+18.6	RT	24.5
CHERRY AVE.	21+13.5	RT	21+30.4	RT	34.1
CHERRY AVE.	21+29.9	RT	21+97.2	RT	36.9
CHERRY AVE.	21+94.7	RT	22+43.5	RT	90.6
CHERRY AVE.	22+41.0	RT	22+93.7	RT	28.8
CHERRY AVE.	24+43.7	RT	24+78.0	RT	42.2
CHERRY AVE.	24+98.8	RT	25+30.2	RT	43.1
CHERRY AVE.	26+05.9	RT	26+25.3	RT	26.8
CHERRY AVE.	26+82.3	RT	26+94.9	RT	17.0
CHERRY AVE.	27+25.5	RT	27+38.8	RT	15.8
CHERRY AVE.	27+65.6	RT	27+77.0	RT	15.0
CHERRY AVE.	28+06.8	RT	28+17.4	RT	13.9
CHERRY AVE.	28+45.7	RT	28+56.7	RT	14.3
CHERRY AVE.	29+32.1	RT	29+44.4	RT	6.8
CHERRY AVE.	30+09.4	RT	30+29.0	RT	22.4
CHERRY AVE.	22+81.8	LT	23+15.3	LT	38.8
CHERRY AVE.	24+76.6	LT	24+97.8	LT	18.6
CHERRY AVE.	24+89.5	LT	25+12.5	LT	29.0
CHERRY AVE.	27+22.3	LT	27+36.8	LT	16.1
CHERRY AVE.	27+65.9	LT	27+77.2	LT	14.4
CHERRY AVE.	28+05.6	LT	28+17.5	LT	13.1
CHERRY AVE.	28+45.7	LT	28+56.1	LT	13.0
CHERRY AVE.	29+30.9	LT	29+43.6	LT	6.9
CHERRY AVE.	29+87.9	LT	30+09.1	LT	29.3
TOTAL					1,082.6