

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	90% FEDERAL, 10% STATE CONSTRUCTION AND SAFETY CODES		
				0004	0011	0014
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	340	340		
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	152	152		
20200100	EARTH EXCAVATION	CU YD	6806	6806		
20400800	FURNISHED EXCAVATION	CU YD	6395	6295		100
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	2291		741	1550
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	50791	50791		
* 25000210	SEEDING, CLASS 2A	ACRE	17.75	17.75		
* 25000310	SEEDING, CLASS 4	ACRE	0.25	0.25		
* 25000350	SEEDING, CLASS 7	ACRE	0.75	0.75		
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1598	1598		
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1598	1598		
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1598	1598		
† * 25000750	MOWING	ACRE	23.75	23.75		
25100630	EROSION CONTROL BLANKET	SQ YD	85940	85940		
28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	80	80		
28000305	TEMPORARY DITCH CHECKS	FOOT	700	700		
28000400	PERIMETER EROSION BARRIER	FOOT	7650	7650		
28000500	INLET AND PIPE PROTECTION	EACH	7	7		
28001000	AGGREGATE (EROSION CONTROL)	TON	25	25		
28100109	STONE RIPRAP, CLASS A5	SQ YD	1022			1022
28100707	STONE DUMPED RIPRAP, CLASS A4	SQ YD	42	42		
28200200	FILTER FABRIC	SQ YD	1022			1022
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	13769	13769		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	29.1	26.8		2.3
40600845	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N90	TON	5095	5095		
40600895	CONSTRUCTING TEST STRIP	EACH	2	2		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	3064	717		2347
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	7729	7729		
40603345	HOT - MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	814			814
40603515	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	2799	2799		

† NON-PARTICIPATING

* SPECIALTY ITEMS