

© Copyright Hanson Professional Services Inc. 2005. YEAR\$



Hanson Professional Services Inc.

TEMPORARY CONCRETE BARRIER SCHEDULE					
LOCATION				70400100	70400200
				TEMPORARY CONCRETE BARRIER FOOT	RELOCATE TEMPORARY CONCRETE BARRIER FOOT
ROADWAY	BEGIN STATION	OFFSET	END STATION	OFFSET	
I-280	1388+88	35 RT	1389+12	31 RT	25
I-280	1389+12	31 RT	1394+62	30 RT	550
I-280	1389+28	31 LT	1394+65	31 LT	537.5
I-280	1394+65	31 LT	1394+90	35 LT	25
I-280	100+75	29 RT	107+99	29 RT	725
I-280	103+65	85 RT	104+64	68 RT	100
I-280	104+64	68 RT	107+14	69 RT	250
I-280	102+04	29 LT	109+30	29 LT	725
I-280	102+88	67 LT	105+58	67 LT	250
I-280	105+66	67 LT	106+37	84 LT	100
I-280	200+39	20 LT	203+00	44 LT	262.5
I-280	203+00	44 LT	288+37	44 LT	8537.5
SUBTOTAL				12087.5	0
I-280	288+37	44 LT	312+39	27 RT	2350
I-280	102+90	35 RT	106+15	46 RT	325
I-280	103+84	46 LT	107+08	35 LT	325
I-280	104+30	45 RT	106+15	45 RT	187.5
I-280	103+82	45 LT	106+69	45 LT	187.5
4th Street	241+82	122 RT	241+88	177 RT	237.5
4th Street	241+83	122 RT	241+71	177 RT	237.5
US 67	255+18	165 RT	255+15	85 LT	250
US 67	254+80	85 RT	254+81	165 LT	250
US 67	254+80	85 RT	254+95	164 LT	250
US 67	255+03	165 RT	255+15	85 LT	250
SUBTOTAL				0	4850
I-280	1384+25	18 RT	1386+36	36.1 RT	212.5
I-280	1386+36	36 RT	1394+99	36.1 RT	862.5
I-280	1388+89	36 LT	1397+39	36.1 LT	850
I-280	1397+39	36 LT	1399+25	20.5 LT	187.5
I-280	202+22	29 LT	310+00	44.0 RT	11037.5
I-280	310+00	44 RT	311+99	25.6 RT	200
4th Street	241+82	122 RT	241+88	177.0 RT	237.5
4th Street	241+83	122 RT	241+71	177.0 RT	237.5
US 67	255+18	165 RT	255+15	84.6 LT	250
US 67	254+80	85 RT	254+81	164.7 LT	250
US 67	254+80	85 RT	254+95	164.2 LT	250
US 67	255+03	165 RT	255+15	84.6 LT	250
SUBTOTAL				0	14825
Bridge Patching and Over-Lay				Sheet 57-58	Sheet 60-61, 63A-63B
SUBTOTAL					
TOTAL				12087.5	19675

TOPSOIL FURNISH AND PLACE, 4"				
LOCATION				21101615
				TOPSOIL FURNISH AND PLACE, 4"
ROADWAY	BEGIN STATION	END STATION	OFFSET	SQ YD
I-280	95+00.00	97+00.00	0 RT	1111.26
I-280	97+00.00	99+80.00	0 RT	1213.00
I-280	102+39.00	107+50.00	0 RT	3122.77
I-280	102+44.00	103+95.00	75 LT	587.09
I-280	102+70.00	104+90.00	75 RT	743.91
I-280	105+50.00	106+90.00	100 LT	544.02
I-280	106+09.00	107+80.00	75 LT	685.02
I-280	200+50.00	202+00.00		357.00
I-280	204+00.00	205+50.00		397.00
I-280	223+40.00	232+06.35	LT Ditch	1197.45
I-280	223+40.00	232+06.35	LT Median	1902.30
I-280	223+40.00	232+06.35	RT Median	1411.49
I-280	223+40.00	232+06.35	RT Ditch	1209.74
I-280	233+44.01	240+51.86	LT Ditch	309.25
I-280	233+44.01	240+51.86	LT Median	954.04
I-280	233+44.01	240+51.86	RT Median	839.50
I-280	233+44.01	240+51.86	RT Ditch	626.18
I-280	242+82.77	253+75.73	LT Ditch	370.22
I-280	242+82.77	253+75.73	LT Median	1525.22
I-280	242+82.77	253+75.73	RT Median	1605.54
I-280	242+82.77	253+75.73	RT Ditch	269.23
I-280	258+14.14	262+93.17	LT Ditch	2909.10
I-280	258+14.14	262+93.17	LT Median	1369.53
I-280	258+14.14	262+93.17	RT Median	1311.15
I-280	258+14.14	262+93.17	RT Ditch	324.85
I-280	268+21.12	285+57.55	LT Ditch	890.34
I-280	268+21.12	285+57.55	LT Median	4788.94
I-280	268+21.12	285+57.55	RT Median	4624.16
I-280	268+21.12	285+57.55	RT Ditch	2529.74
I-280	272+00.00	275+50.00		731.00
I-280	279+50.00	282+50.00		449.00
I-280	288+18.48	298+00.00	LT Ditch	403.60
I-280	288+18.48	298+00.00	LT Median	2491.59
I-280	288+18.48	298+00.00	RT Median	2385.83
I-280	288+18.48	298+00.00	RT Ditch	1016.79
I-280	307+50.00	308+00.00		394.00
I-280	311+00.00	312+50.00		338.00
I-92	1386+60.00	1390+35.00	0 RT	811.18
I-92	1388+80.00	1390+15.00	65 RT	225.06
I-92	1389+35.00	1390+65.00	65 LT	216.83
I-92	1392+50.00	1395+10.00	70 RT	577.90
I-92	1393+20.00	1394+40.00	65 LT	199.89
I-92	1393+30.00	1397+10.00	0 RT	844.10
TOTAL				50790.79

REMOVE OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED SCHEDULE			
LOCATION (I-92)			73602000
			REMOVE OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED
EACH			
BEGIN STATION	OFFSET	END STATION	OFFSET
1391+50.00	LT		
1392+25.00	RT		
SUBTOTAL			2
TOTAL			2

MODULAR GLARE SCREEN SYSTEM SCHEDULE			
LOCATION (I-280)			63801205
			TEMPORARY MODULAR GLARE FOOT
BEGIN STATION	OFFSET	END STATION	OFFSET
203+00.00	LT	208+00.00	LT
305+00.00	RT	310+00.00	RT
SUBTOTAL			1000
TOTAL			1000

CONCRETE ENCASEMENT SCHEDULE			
LOCATION (I-280)			50300280
			CONCRETE ENCASEMENT CU YD
BEGIN STATION	OFFSET	END STATION	OFFSET
202+36.83	0	203+63.17	0
309+36.83	0	310+63.17	0
SUBTOTAL			64.6
TOTAL			64.6

GEOTECHNICAL REINFORCEMENT SCHEDULE			
LOCATION (I-280)			Z0028415
			GEOTECHNICAL REINFORCEMENT SQ YD
BEGIN STATION	OFFSET	END STATION	OFFSET
200+22.51	26.00 LT	205+77.49	26.00 LT
200+22.51	26.00 RT	205+77.49	26.00 RT
307+22.51	26.00 LT	312+77.49	26.00 LT
307+22.51	26.00 RT	312+77.49	26.00 RT
SUBTOTAL			1973
TOTAL			1973

SIGN SCHEDULE					
LOCATION		72000200	72000300	72400320	72400330
		SIGN PANEL - TYPE 2	SIGN PANEL - TYPE 3	REMOVE SIGN PANEL - TYPE 2	REMOVE SIGN PANEL - TYPE 3
ROADWAY	BEGIN STATION	LT/RT/STRUCTURE	SQ FT	SQ FT	SQ FT
I-280	98+00.00	86 RT			180.5
I-280	105+40.28	STRUCTURE		171	
I-280	112+00.00	86 LT			171.0
I-280	284+02.59	RT		196	
I-280	289+31.89	LT	32	32	196.0
I-280	104+58.17	STRUCTURE		181	
TOTAL			32	548	547.5

MEDIAN CLOSURE SCHEDULE			
LOCATION (I-280)			X0322288
			MEDIAN CLOSURE EACH
BEGIN STATION	OFFSET	END STATION	OFFSET
203+00.00			1
310+00.00			1
SUBTOTAL			2
TOTAL			2

STAGING DRAINAGE SCHEDULE						
LOCATION		542D0217	542D0223	54244405	X0322392	Z0065752
		PIPE CULVERTS, CLASS D, TYPE 1 12"	PIPE CULVERTS, CLASS D, TYPE 1 18"	FLUSH INLET BOX FOR MEDIAN STANDARD 542546	BEVELED PIPE AND GUARD	SLOTTED DRAIN 12" WITH 6" SLOT
ROADWAY	STATION	OFFSET	STATION	FOOT	FOOT	FOOT
I-280	201+10.00		204+00.17		290	
I-280	202+36.83		203+63.17			127
I-280	203+63.17		204+00.17	37		
I-280	204+00.00					
I-280	204+04.76				1	
I-280	308+55.00		204+70.00		65	
I-280	309+36.83		309+36.83		82	
I-280	310+63.17		310+63.17			127
I-280	310+63.17		311+77.00		114	
TOTAL				37	551	127

⚠ SHEET REVISED 10/19/10

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

MOT SCHEDULE
SCHEDULE OF QUANTITIES

FILE NAME = B:\BATHS-ehv-schedule.dgn	USER NAME = georg00020	DESIGNED = JDW	REVISED = 9/2/10 - EEC	SCALE: SHEET NO. OF SHEETS STA. TO STA.
MODEL NAME = S-MOT Schedule 1	PLOT SCALE =	DRAWN = DAP	REVISED = 9/24/10 - EEC	
	PLOT DATE = 9/15/2010	CHECKED = DES	REVISED = 9/27/10 - EEC	
		DATE = 07/23/10	REVISED =	

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
280	81-1B-1,1B,1B-1,1B-2,VB,VB-11R	ROCK ISLAND	503	16 B
FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT 7				CONTRACT NO. 64815