



Hanson Professional Services Inc.

PAVEMENT MARKING SCHEDULE									
LOCATION					X7800640	X7800610	78004230	78100100	78100105
					URETHANE PAVEMENT MARKING - LINE 8"	URETHANE PAVEMENT MARKING TYPE I - LINE 4"	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 6"	RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)
					FOOT	FOOT	FOOT	EACH	EACH
ROADWAY	BEGIN STATION	END STATION	OFFSET	LT/RT/RAMP					
I-280	200+22.51	205+77.49	32.00	RT		555			
I-280	200+22.51	205+77.49	32.00	LT		555			
I-280	200+22.51	312+77.49	44.00	RT			2814		
I-280	200+22.51	312+77.49	44.00	LT			2814		
I-280	223+00.00	298+00.00	32.00	RT		7500			
I-280	223+00.00	298+00.00	32.00	LT		7500			
I-280	223+00.00	298+00.00	56.00	RT		7500			
I-280	223+00.00	298+00.00	56.00	LT		7500			
I-280	223+00.00	231+43.95	44.00	RT				21	
I-280	223+00.00	232+29.95	44.00	LT				23	
I-280	231+43.95	233+40.40	32.00	RT					5
I-280	232+29.95	234+32.59	32.00	LT					5
I-280	233+40.40	240+87.76	44.00	RT				19	
I-280	234+32.59	240+87.85	44.00	LT				16	
I-280	240+87.76	242+46.78	32.00	RT					4
I-280	240+87.85	242+46.77	32.00	LT					4
I-280	242+46.77	254+15.69	44.00	LT				29	
I-280	242+46.78	254+15.71	44.00	RT				29	
I-280	254+15.69	255+78.12	32.00	LT					4
I-280	254+15.71	255+78.13	32.00	RT					4
I-280	255+78.12	263+25.29	44.00	LT				19	
I-280	255+78.13	263+68.13	44.00	RT				20	
I-280	263+25.29	265+92.04	32.00	LT					7
I-280	263+68.13	266+41.05	32.00	RT					7
I-280	265+92.04	285+69.77	44.00	LT				49	
I-280	285+41.05	285+95.97	44.00	RT				49	
I-280	285+69.77	287+81.09	32.00	LT					5
I-280	285+95.97	288+02.14	32.00	RT					5
I-280	287+81.09	298+00.00	44.00	LT				25	
I-280	288+02.14	298+00.00	44.00	RT				25	
I-280	307+22.51	312+77.49	32.00	RT		555			
I-280	307+22.51	312+77.49	32.00	LT		555			
IL 92	1370+00.00	1420+00.00	20.00	RT		5000			
IL 92	1370+00.00	1420+00.00	20.00	LT		5000			
IL 92	1370+00.00	1390+63.71	32.00	LT				52	
IL 92	1370+00.00	1420+00.00	32.00	LT			1250		
IL 92	1370+00.00	1420+00.00	32.00	RT			1250		
IL 92	1373+33.16	1377+00.28	44.00	RT	367				
IL 92	1373+33.16	1377+00.28	63.00	*RT	367				
IL 92	1377+00.00	1385+73.06	44.00	RT		873			
IL 92	1381+55.30	1382+98.41	44.00	LT	143				
IL 92	1381+55.30	1382+98.41	87.00	*LT	143				
IL 92	1382+98.41	1387+08.90	44.00	LT		408			
IL 92	1385+73.35	1387+07.87	44.00	RT	135				
IL 92	1385+73.35	1387+07.87	44.00	*RT	135				
IL 92	1387+06.90	1388+33.43	44.00	LT	127				
IL 92	1387+06.90	1388+33.43	44.00	*LT	127				
IL 92	1390+26.74	1393+13.13	44.00	LT					
IL 92	1390+26.74	1393+13.13	44.00	LT			72		
IL 92	1390+26.74	1393+13.13	32.00	RT					7
IL 92	1390+26.74	1393+13.13	44.00	RT					7
IL 92	1390+26.74	1393+13.13	32.00	LT					7
IL 92	1390+26.74	1393+13.13	44.00	LT					7
IL 92	1390+63.71	1393+50.09	44.00	RT					
IL 92	1390+63.71	1393+50.09	44.00	RT			72		
IL 92	1393+13.13	1420+00.00	32.00	RT				67	
IL 92	1393+50.09	1420+00.00	32.00	LT				66	
IL 92	1395+02.02	1396+23.24	44.00	RT	121				
IL 92	1395+02.02	1396+23.24	71.00	*RT	121				
IL 92	1396+23.24	1401+97.58	44.00	RT		574			
IL 92	1396+64.32	1397+96.66	44.00	LT	132				
IL 92	1396+64.32	1397+96.65	62.00	*LT	134				
IL 92	1397+96.67	1405+40.36	44.00	LT		744			
IL 92	1401+97.58	1407+22.04	44.00	RT	524				
IL 92	1401+97.58	1407+22.04	44.00	*RT	524				
IL 92	1405+40.36	1409+48.02	44.00	LT	408				
IL 92	1405+40.36	1409+48.02	44.00	*LT	408				
IL 92	1412+92.21	1420+00.00	44.00	LT		708			
IL 92	1414+51.54	1420+00.00	44.00	RT		548			
IL 92	1370+00.00	1390+26.74	32.00	RT				51	
TOTAL					3916	46076	8271	561	79

PAVEMENT MARKING REMOVAL SCHEDULE					
LOCATION				78300100	NOTES
				PAVEMENT MARKING REMOVAL	
ROADWAY	BEGIN STATION	END STATION	LT/RT/RAMP	SQ FT	
I-280	94+85.00	103+75.00	RT	74	EB SKIP DASH
I-280	103+05.00	104+50.00	RT	49	EB RAMP EDGE LINE
I-280	105+55.00	107+05.00	LT	50	WB RAMP EDGE LINE
I-280	199+85.00	202+00.00	RT	72	EB MEDIAN EDGE LINE
I-280	202+00.00	203+00.00	LT	10	WB SKIP DASH
I-280	202+00.00	295+73.00	LT	3124	WB OUTSIDE EDGE LINE
I-280	202+00.00	310+00.00	LT	3600	WB MEDIAN EDGE LINE
I-280	302+19.00	312+50.00	LT	344	WB OUTSIDE EDGE LINE
I-280	307+25.00	317+12.00	LT	84	WB SKIP DASH
I-280	310+00.00	313+11.00	RT	104	EB MEDIAN EDGE LINE
IL-92	1373+00.00	1390+22.00	RT	144	NB SKIP DASH
IL-92	1385+70.00	1387+05.00	RT	99	NB RAMP GORE
IL-92	1385+30.00	1390+25.00	RT	165	NB MEDIAN EDGE LINE
IL-92	1386+96.00	1388+35.00	LT	90	SB RAMP GORE
IL-92	1386+96.00	1390+48.00	LT	118	SB MEDIAN EDGE LINE
IL-92	1386+96.00	1390+58.00	LT	30	SB SKIP DASH
IL-92	1387+42.00	1389+20.00	LT	60	SB EDGE LINE
IL-92	1393+30.00	1396+97.00	RT	123	NB MEDIAN EDGE LINE
IL-92	1393+50.00	1398+45.00	LT	165	NB MEDIAN EDGE LINE
IL-92	1393+55.00	1426+00.00	LT	270	NB SKIP DASH
IL-92	1394+60.00	1396+97.00	RT	20	NB SKIP DASH
IL-92	1395+00.00	1396+51.00	RT	117	NB RAMP GORE
IL-92	1395+10.00	1397+35.00	LT	75	SB OUTSIDE EDGE LINE
IL-92	1396+72.00	1397+75.00	LT	93	SB RAMP GORE
I-280	174+50.00	179+57.00	RT	44	EB SKIP DASH
I-280	184+50.00	199+85.00	RT	512	EB OUTSIDE EDGE LINE
I-280	198+72.00	202+00.00	LT	110	WB OUTSIDE EDGE LINE
I-280	199+50.00	202+00.00	LT	84	WB MEDIAN EDGE LINE
I-280	298+00.00	312+00.00	RT	467	EB OUTSIDE EDGE LINE
I-280	203+50.00	220+23.00	RT	558	EB MEDIAN EDGE LINE
I-280	298+00.00	312+00.00	RT	467	EB MEDIAN EDGE LINE
I-280	311+00.00	314+27.00	LT	109	WB MEDIAN EDGE LINE
I-280	311+00.00	356+73.00	LT	380	WB SKIP DASH
I-280	327+90.00	329+65.00	LT	119	WB MEDIAN GORE
IL-92	1367+56.00	13+73.00	RT	47	NB SKIP DASH
IL-92	1382+56.00	1387+08.00	RT	151	NB OUTSIDE EDGE LINE
IL-92	1395+00.00	1398+26.00	RT	109	NB OUTSIDE EDGE LINE
IL-92	1397+35.00	1401+20.00	LT	129	SB OUTSIDE EDGE LINE
SUBTOTAL				12366	
Bridge Patching and Over-Lay					See Bridge Patching and Over-Lay Plan Sheets
TOTAL				12366	

BARRIER WALL MARKERS				
LOCATION				78200520
				BARRIER WALL MARKERS, TYPE B
ROADWAY	BEGIN STATION	END STATION	LT/RT	EACH
I-280	231+08.86	233+30.48	RT	4
I-280	231+51.30	233+69.66	RT	4
I-280	231+97.59	234+25.94	LT	4
I-280	232+42.24	234+67.25	LT	4
I-280	240+72.86	242+61.79	RT	4
I-280	240+72.86	242+61.79	RT	4
I-280	240+72.86	242+61.79	LT	4
I-280	240+72.86	242+61.79	LT	4
I-280	254+00.73	255+93.15	RT	4
I-280	254+00.73	255+93.15	RT	4
I-280	254+00.73	255+93.15	LT	4
I-280	254+00.73	255+93.15	LT	4
I-280	263+62.88	266+84.10	RT	4
I-280	263+53.39	266+41.01	RT	4
I-280	263+23.09	266+12.78	LT	4
I-280	262+99.99	265+89.68	LT	4
I-280	286+02.78	288+07.65	RT	4
I-280	285+90.43	287+97.90	RT	4
I-280	285+75.58	287+85.91	LT	4
I-280	285+63.00	287+75.66	LT	4
IL 92	1389+94.42	1393+10.79	RT	4
IL 92	1390+22.13	1393+38.52	RT	4
IL 92	1390+38.32	1393+54.70	LT	4
IL 92	1390+66.03	1393+82.42	LT	4
TOTAL				96