Station			Description	Offset	70300220 Temp. Marking Line - 4" WHITE (Foot)	70300220 Temp. Marking Line - 4" YELLOW (Foot)	78300100 Pav't Marking removal (Sq.Ft.)	70400100 Temp. Conc. Barrier Wall (Foot)	Z0030250 IMP ATTN TEMP NRD TL3 (Each)	X7050167 Temp TBT Ty1 Special (Tangent) (Each)	70500100 Temp SPBGR TA (Foot)	70500665 TEMP TR BAR TERM T6 (Each)	20400800 Furnish Excav. (Cu. Yd.)
BARRIER WALL													
231+99.9	-	234+64.5	Temp. Concrete Barrier Wall	46.6' - 45.37' Lt				262.5					
234+64.5	-	236+53.0	Temp. Concrete Barrier Wall - taper	45.37' - 32.26' Lt				187.5					
		236+53.0	Temp. impact attenuator	32.26' Lt					1				
240+52.5	-	242+65.0	Temp. Concrete Barrier Wall	46.5' Lt				212.5					
242+65.0	-	244+52.1	Temp. Concrete Barrier Wall - taper	46.5' - 32.41' Lt				187.5					
		244+52.1	Temp. impact attenuator	32.41' Lt					1				
253+80.0	-	256+05.0	Temp. Concrete Barrier Wall	46.5' Lt				225.0					
256+05.0	-	257+92.1	Temp. Concrete Barrier Wall - taper	46.5' - 32.68' Lt				187.5					
		257+92.1	Temp. impact attenuator	32.68' Lt					1				
262+87.5	-	266+25.0	Temp. Concrete Barrier Wall	46.5' Lt				337.5					
266+25.0	-	268+25.9	Temp. Concrete Barrier Wall - taper	46.5' - 32.04' Lt				187.5					
		268+25.9	Temp. impact attenuator	32.04' Lt					1				
285+00.0	-	288+41.7	Temp. Concrete Barrier Wall	46.51' Lt				337.5					
288+41.7	-	290+43.0	Temp. Concrete Barrier Wall - taper	46.5' - 30.68 ' Lt				187.5					
		290+43.0	Temp. impact attenuator	30.68' Lt					1				
GUARDRAIL													
		228+89.9	Temp TBT Ty1 (special) Tangent							1			25
228+89.9	-	231+78.5	guardrail								287.50		
		231+78.5	Temp TBT Ty 6									1	
		237+53.1	Temp TBT Ty1 (special) Tangent							1			25
237+53.1	-	240+52.5	guardrail								300		
		240+52.5	Temp TBT Ty 6									1	
		250+80.3	Temp TBT Ty1 (special) Tangent							1			25
250+80.3	-	253+80.0	guardrail								300		
		253+80.0	Temp TBT Ty 6									1	
		260+21.1	Temp TBT Ty1 (special) Tangent							1			25
260+21.1	-	262+96.1	guardrail								275		
		262+96.1	Temp TBT Ty 6									1	
		282+64.0	Temp TBT Ty1 (special) Tangent							1			
282+64.0	-	285+36.5	guardrail								275		
		285+36.5	Temp TBT Ty 6									1	
PAVEMENT MARKINGS													
178+70.0	-	188+69.7	EB - taper	32.3' - 44.3' Rt		999.72							
188+69.7	-	208+00.0	EB - left edge line	44.3' Rt		1930.35							
183+90.0	-	210+00.0	left edge line	44.3' Lt		2610.00							
230+20.0	-	232+00.0	right edge line	56.08' - 58.97' Lt	180.02								
230+20.0	-	231+99.7	left edge line	44.3' - 48.47' Lt		179.73							
230+20.0	-	236+53.0	remove right edge line	56.08' - 56.15' Lt			211.01						
				SHEET TOTALS	180.02	5,719.80	211.01	2,312.50	5.00	5.00	1,437.50	5.00	100.00

* 81-1(B-1, HB, HB-1, HB-2, VB, VB-1)R