

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	INDEX OF SHEETS AND TOTAL BILL OF MATERIALS
2-3	SIGN REMOVAL PLAN AND SIGN REPLACEMENT
4	SIGN PANEL DETAILS

LIST OF ILLINOIS DOT HIGHWAY STANDARDS

STD. NUMBER	DESCRIPTION
720001	SIGN PANEL MOUNTING DETAILS
720006	SIGN PANEL ERECTION DETAILS
720011	METAL POST FOR SIGNS, MARKERS & DELINEATORS
720021-02	SIGN PANELS EXTRUDED ALUMINUM TYPE
729001	APPLICATIONS OF TYPES A & B METAL POSTS (FOR SIGNS & MARKERS)

BILL OF MATERIALS

TOTAL BILL OF MATERIALS (FOR INFORMATION ONLY)					
DESCRIPTION	UNIT	TOTAL QUANTITY	REGULATORY AND WARNING SIGNS	GROUND MOUNTED SIGNS	BRIDGE MOUNTED SIGNS
SIGN PANEL - TYPE 2	SQ FT	32.00	32.00	0	0
SIGN PANEL - TYPE 3	SQ FT	547.50	0.00	196.00	351.50
STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	2,137.50	0.00	2,137.50	0.00
Wood Sign Support	Foot	40.0	40.0	0.00	0.00
CONCRETE FOUNDATIONS	CU YD	4.18		4.18	0.00
REINFORCEMENT BARS	POUND	244.0		244.00	0.00

BILL OF MATERIALS – REMOVAL

SIGN REMOVAL NUMBER	ALIGNMENT NAME	STATION	LOCATION (LEFT, RIGHT, MEDIAN, STRUCTURE)	PANEL WIDTH FEET	PANEL HEIGHT FEET	SIGN AREA SQ FT	POST MATERIAL	REMOVE SIGN PANEL TYPE 2 SQ FT	REMOVE SIGN PANEL TYPE 3 SQ FT	REMARKS
001	I-280	104+58.17	STRUCTURE	19	9.5	180.50			180.50	IL-92 EAST - ROCK ISLAND
002	I-280	105+40.28	STRUCTURE	18	9.5	171.00			171.00	IL-92 WEST - ANDALUSIA
003	I-280	284+02.59	RT	14	14	196.00	Steel		196.00	EXIT 15 - AIRPORT RD -MILAN - US 67
004	I-280	289+31.89	LT	2.5	3	7.50	Steel	7.50		SPEED LIMIT 65 - MIN 45